

EXPECTED IMPLEMENTATION JULY 2021

234 SUPERPAVE ASPHALT BASE (REV 11-2-20) (FA 1-15-21) (7-21)

SUBARTICLE 234-7.1.3 is deleted and the following substituted:

234-7 Construction Requirements.

234-7.1 General: Meet the general construction requirements of Section 330, with the following modifications:

234-7.1.1 Temperature Limitations: Spread the mixture only when the air temperature is at least 40°F. Do not place the material on frozen subgrade.

234-7.1.2 Tack Coat: Unless otherwise authorized by the Engineer, apply a tack coat between successive layers of base material.

234-7.1.3 Thickness of Layers: Construct each course in layers, such that the compacted thickness is in compliance with the layer thicknesses in 234-8.1.1 and spread rate tolerance in 234-8.2.

D

R

A

F

T