

# EXPECTED IMPLEMENTATION JULY 2021

D

## 641 PRESTRESSED CONCRETE POLES (REV 2-3-21) (FA 2-8-21) (7-21)

SUBARTICLE 641-2.2 is deleted and the following substituted:

**641-2.2 Camera Lowering Device:** Use lowering devices that meet the requirements of Section 996 and are listed on the Department's Approved Product List (APL).

R

SUBARTICLE 641-2.2.1 is deleted:

SUBARTICLE 651-2.2.2 is deleted:

A

SUBARTICLE 641-2.2.2.1 is deleted:

SUBARTICLE 641-2.2.2.2 is deleted and the following substituted:

**641-2.2.1 Connector Block:** Lubricate all components, including the connector block and contacts, in accordance with the manufacturer's recommendations.

F

SUBARTICLE 641-2.2.3 is deleted and the following substituted:

**641-2.2.2 Lowering Tool:** Provide a minimum of one lowering tool and any additional tools as required in the Plans. Deliver the lowering tool to the Department before final acceptance.

T

SUBARTICLE 641-2.2.5 is deleted and the following substituted:

**641-2.2.3 Wiring:** All wiring must meet NEC requirements and be installed in accordance with the equipment manufacturers' recommendations for each device connected on the pole, at the lowering device, and in the field cabinet.

# EXPECTED IMPLEMENTATION JULY 2021

SUBARTICLE 641-2.2.6 is deleted and the following substituted:

**D**

**641-2.2.4 External-Mount Lowering System Enclosure for Mounting to Existing Structures:** The cabinet must allow for unobstructed operation of the winch, access for servicing and provide sufficient clear area for operation of the winch manually and with an electric drill. Include a pin tumbler lock keyed for use with a No. 2 key and two keys, unless otherwise directed by the Plans. Provide all necessary mounting hardware, conduits, standoffs, and conduit mounts required for a complete and functional system.

**R**

**A**

**F**

**T**