

EXPECTED IMPLEMENTATION JULY 2021

682 VIDEO EQUIPMENT (REV 11-12-20) (FA 2-3-21) (7-21)

SUBARTICLE 682-1.4 is deleted and the following substituted:

682-1.4 Field Acceptance Testing.

Conduct field acceptance testing in accordance with Section 611.

Perform local field inspection at each local CCTV field site to verify and confirm the following:

1. Physical construction has been completed as specified in the Plans and all existing and proposed lanes are clearly visible with no line of site obstructions.
2. The quality and tightness of ground and surge protector connections.
3. Proper voltages for all power supplies and related power circuits.
4. All connections, including correct installation of communication and power cables.

D

R

A

F

T