

EXPECTED IMPLEMENTATION JULY 2021

684 NETWORK DEVICES (REV 11-12-20) (FA 2-3-21) (7-21)

SUBARTICLE 684-1.4 is deleted and the following substituted:

684-1.4 Field Acceptance Testing: Conduct field acceptance testing in accordance Section 611.

Once the MFES has been installed, conduct local field inspection at the MFES field site according to the approved test plan. Perform the following:

1. Verify that physical construction has been completed as detailed in the Plans.
2. Inspect the quality and tightness of ground and surge protector connections.
3. Verify proper voltages for all power supplies and related power circuits.
4. Connect devices to the power sources.
5. Verify all connections, including correct installation of communication and power cables.

D

R

A

F

T