

EXPECTED IMPLEMENTATION JULY 2021

D

701 PROFILED THERMOPLASTIC PAVEMENT MARKINGS (REV 11-3-20) (FA 1-8-21) (7-21)

ARTICLE 701-9 is deleted and the following substituted:

701-9 Method of Measurement.

701-9.1 Profiled Thermoplastic Markings: The quantities of 6 inch solid and 10'-30' skip lines to be paid will be the plan quantity length, in gross miles, subject to 9-1.3.2. The gross mile measurement will be taken as the distance from the beginning of the profiled thermoplastic line to the end of the profiled thermoplastic line and will include the unmarked gaps for skip lines. The gross mile will not include designated unmarked lengths at intersections, turn lanes, etc.

701-9.2 Removal of Existing Thermoplastic Markings: The quantity to be paid for removal of existing thermoplastic pavement markings will be the area, in square feet, acceptably removed. Payment for removal of thermoplastic pavement markings will only be made for locations where the existing pavement surface is to remain.

R

ARTICLE 701-10 is deleted and the following substituted:

701-10 Basis of Payment.

Price and payment will be full compensation for all work specified in this Section, including, all cleaning and preparing of surfaces, furnishing of all materials, application, curing and protection of all items, protection of traffic, furnishing of all tools, machines and equipment, and all incidentals necessary to complete the work. Final payment will be withheld until all deficiencies are corrected.

Payment will be made under:

Item No. 701	Profiled Thermoplastic Pavement Markings.
	Solid - per gross mile
	Skip - per gross mile
	Remove - per square foot

A

F

ARTICLE 701-11 is deleted.

T