

ORINATION FORM

Proposed Revisions to the Specifications

(Please provide all information - incomplete forms will be returned)

Date:

Office:

Originator:

Specification Section:

Telephone:

Article/Subarticle:

email:

****Will the proposed revision require changes to:**

Publication	Yes	No	Office Staff Contacted and date contacted
Standard Plans Index			
Traffic Engineering Manual			
FDOT Design Manual			
Construction Project Administration Manual			
Basis of Estimate/Pay Items			
Structures Design Guidelines			
Approved Product List			
Materials Manual			

**This section must be completed prior to processing proposed revisions.

Will this revision necessitate any of the following:

Design Bulletin

Construction Bulletin

Estimates Bulletin

Materials Bulletin

Are all references to external publications current?

Yes

No

If not, what references need to be updated? (Please include changes in the redline document.)

Why does the existing language need to be changed?

Summary of the changes:

Are these changes applicable to all Department jobs?

Yes

No

If not, what are the restrictions?

Contact the State Specifications Office for assistance in completing this form.

Daniel Strickland 850-414-4130 Daniel.Strickland@dot.state.fl.us Rebecca Frimmel 850-414-4155 Rebecca.Frimmel@dot.state.fl.us

Valencia Cunningham 850-414-4101 Valencia.Cunningham@dot.state.fl.us Darla Hunsicker 850-414-4114 Darla.Hunsicker@dot.state.fl.us



RON DESANTIS
GOVERNOR

KEVIN J. THIBAUT, P.E.
SECRETARY

M E M O R A N D U M

DATE: November 19, 2020
TO: Specification Review Distribution List
FROM: Daniel Strickland, P.E., State Specifications Engineer
SUBJECT: Proposed Specification: **7010900 PROFILED THERMOPLASTIC PAVEMENT MARKINGS**

In accordance with Specification Development Procedures, we are sending you a copy of a proposed specification change.

The changes are proposed by Olivia Townsend from the State Construction Office to update language to plan quantity in the Standard Specification.

Please share this proposal with others within your responsibility. Review comments are due within four weeks and should be sent to Mail Station 75 or online at <http://fdotewp1.dot.state.fl.us/programmanagement/development/industryreview.aspx> . Comments received after **December 17, 2020**, may not be considered. Your input is encouraged.

DS/dh

Attachment

**PROFILED THERMOPLASTIC PAVEMENT MARKINGS
(REV 11-3-20)**

ARTICLE 701-9 is deleted and the following substituted:

701-10-9 Submittals.Method of Measurement.

~~701-9.1 Submittal Instructions: Prepare a certification of quantities, using the Department's current approved form, for each project in the Contract. Submit the certification of quantities and daily worksheets to the Engineer. The Department will not pay for any disputed items until the Engineer approves the certification of quantities.~~

~~701-9.2 Contractor's Certification of Quantities: Request payment by submitting a certification of quantities no later than Twelve O'clock noon Monday after the estimate cut-off date or as directed by the Engineer, based on the amount of work done or completed. Ensure the certification of quantities consists of the following:~~

~~1. Contract Number, FPID Number, Certification Number, Certification Date and the period that the certification represents.~~

~~2. The basis for arriving at the amount of the progress certification, less payments previously made and less any amount previously retained or withheld. The basis will include a detailed breakdown shown on the certification of items of payment.~~

701-9.1 Profiled Thermoplastic Markings: The quantities of 6 inch solid and 10'-30' skip lines to be paid will be the plan quantity length, authorized and acceptably applied, under this Section will be paid as follows:

1. The length, in gross miles, subject to 9-1.3.2. The gross mile measurement will be taken as the distance from the beginning of the profiled thermoplastic line to the end of the profiled thermoplastic line and will include the unmarked gaps for skip lines. The gross mile will not include designated unmarked lengths at intersections, turn lanes, etc., of 6 inch solid and 10'-30' skip lines.

701-9.2 Removal of Existing Thermoplastic Markings: The quantity to be paid for removal of existing thermoplastic pavement markings will be 2.-tThe area, in square feet, for removal of existing thermoplastic pavement markings acceptably removed. Payment for removal of thermoplastic pavement markings will only be made for locations where the existing pavement surface is to remain.-

~~The gross mile measurement will be taken as the distance from the beginning of the profiled thermoplastic line to the end of the profiled thermoplastic line and will include the unmarked gaps for skip lines. The gross mile will not include designated unmarked lengths at intersections, turn lanes, etc. Final measurement will be determined by plan dimensions or stations, subject to 9-1.3.1.~~

ARTICLE 701-10 is deleted and the following substituted:

701-11-10 Method of Measurement.Basis of Payment.

~~The quantities, authorized and acceptably applied, under this Section will be paid as follows:~~

~~1. The length, in gross miles, of 6 inch solid and 10' 30' skip lines.~~

~~2. The area, in square feet, for removal of existing thermoplastic pavement markings acceptably removed. Payment for removal of thermoplastic pavement markings will only be made for locations where the existing pavement surface is to remain.~~

~~The gross mile measurement will be taken as the distance from the beginning of the profiled thermoplastic line to the end of the profiled thermoplastic line and will include the unmarked gaps for skip lines. The gross mile will not include designated unmarked lengths at intersections, turn lanes, etc. Final measurement will be determined by plan dimensions or stations, subject to 9-1.3.1.~~

Price and payment will be full compensation for all work specified in this Section, including, all cleaning and preparing of surfaces, furnishing of all materials, application, curing and protection of all items, protection of traffic, furnishing of all tools, machines and equipment, and all incidentals necessary to complete the work. Final payment will be withheld until all deficiencies are corrected.

Payment will be made under:

Item No. 701	Profiled Thermoplastic Pavement Markings.
	Solid - per gross mile
	Skip - per gross mile
	Remove - per square foot

ARTICLE 701-11 is deleted.

~~701-11 Basis of Payment.~~

~~Price and payment will be full compensation for all work specified in this Section, including, all cleaning and preparing of surfaces, furnishing of all materials, application, curing and protection of all items, protection of traffic, furnishing of all tools, machines and equipment, and all incidentals necessary to complete the work. Final payment will be withheld until all deficiencies are corrected.~~

~~Payment will be made under:~~

Item No. 701	Profiled Thermoplastic Pavement Markings.
_____	Solid per gross mile
_____	Skip per gross mile
_____	Remove per square foot