



Florida Department of Transportation

RON DESANTIS
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

KEVIN J. THIBAUT, P.E.
SECRETARY

December 15, 2020

Khoa Nguyen
Director, Office of Technical Services
Federal Highway Administration
3500 Financial Plaza, Suite 400
Tallahassee, Florida 32312

Re: State Specifications Office
Section: **704**
Proposed Specification: **7040000 TUBULAR MARKERS.**

Dear Mr. Nguyen:

We are submitting, for your approval, two copies of the above referenced Supplemental Specification.

The changes are proposed by Gevin McDaniel from the Roadway Design Office to use the same product as the Managed Laned Markers for permanent channelizing devices on Arterials and Collectors. The colors for these Tubular Markers will be the same as the lane line that they supplement (white or yellow) per the MUTCD requirements. This language will be added as a new Section to the Standard Specification.

Please review and transmit your comments, if any, within two weeks. Comments should be sent via email to daniel.strickland@dot.state.fl.us.

If you have any questions relating to this specification change, please call me at 414-4130.

Sincerely,

Signature on file

Daniel Strickland, P.E.
State Specifications Engineer

DS/dh

Attachment

cc: Florida Transportation Builders' Assoc.
State Construction Engineer

TUBULAR MARKERS

(REV ~~9-28~~12-14-20)

The following new Section is added after Section 701.

SECTION 704
TUBULAR MARKERS

704-1 Description.

Furnish and install tubular markers at the locations called for in the Standard Plans or in the Plans.

704-2 Materials.

Meet the following requirements:

Durable Tubular Markers.....Section 991

Standard Tubular MarkersSection 991

704-2.1 Product Acceptance on the Project: Use tubular markers listed on the Department's Approved Product List (APL).

704-3 Installation Requirements.

Install tubular markers in accordance with the manufacturer's installation instructions posted on the APL. Use the same color as the pavement marking being emphasized.

704-4 Method of Measurement.

The quantity to be paid will be the plan quantity of the number of tubular markers furnished, installed, and accepted.

704-5 Basis of Payment.

Prices and payments will be full compensation for work specified in this Section, including the cost of labor, materials, and incidental items required to complete the work.

Payment will be made under:

Item No. 704 - 1 Tubular Marker - each.

TUBULAR MARKERS
(REV 12-14-20)

The following new Section is added after Section 701.

SECTION 704
TUBULAR MARKERS

704-1 Description.

Furnish and install tubular markers at the locations called for in the Standard Plans or in the Plans.

704-2 Materials.

Meet the following requirements:

Durable Tubular Markers.....Section 991

Standard Tubular MarkersSection 991

704-2.1 Product Acceptance on the Project: Use tubular markers listed on the Department's Approved Product List (APL).

704-3 Installation Requirements.

Install tubular markers in accordance with the manufacturer's installation instructions posted on the APL. Use the same color as the pavement marking being emphasized.

704-4 Method of Measurement.

The quantity to be paid will be the plan quantity of the number of tubular markers furnished, installed, and accepted.

704-5 Basis of Payment.

Prices and payments will be full compensation for work specified in this Section, including the cost of labor, materials, and incidental items required to complete the work.

Payment will be made under:

Item No. 704 - 1 Tubular Marker - each.