

# EXPECTED IMPLEMENTATION JULY 2021

## 704 TUBULAR MARKERS (REV 12-14-20) (FA 1-8-21) (7-21)

The following new Section is added after Section 701.

### SECTION 704 TUBULAR MARKERS

#### 704-1 Description.

Furnish and install tubular markers at the locations called for in the Standard Plans or in the Plans.

#### 704-2 Materials.

Meet the following requirements:

Durable Tubular Markers.....Section 991

Standard Tubular Markers .....Section 991

**704-2.1 Product Acceptance on the Project:** Use tubular markers listed on the Department's Approved Product List (APL).

#### 704-3 Installation Requirements.

Install tubular markers in accordance with the manufacturer's installation instructions posted on the APL. Use the same color as the pavement marking being emphasized.

#### 704-4 Method of Measurement.

The quantity to be paid will be the plan quantity of the number of tubular markers furnished, installed, and accepted.

#### 704-5 Basis of Payment.

Prices and payments will be full compensation for work specified in this Section, including the cost of labor, materials, and incidental items required to complete the work.

Payment will be made under:

Item No. 704 - 1 Tubular Marker - each.