

EXPECTED IMPLEMENTATION JULY 2021

D

709 TWO REACTIVE COMPONENTS PAVEMENT MARKINGS (REV 11-3-20) (FA 1-8-21) (7-21)

ARTICLE 709-9 is deleted and the following substituted:

709-9 Method of Measurement.

709-9.1 Two Reactive Components Markings: The quantity of solid, 10'-30' skip, and 3'-9' dotted, 6'-10' dotted, 2'-2' dotted, and 2'-4' dotted lines to be paid will be the plan quantity length, in gross miles, subject to 9-1.3.2.

The gross mile measurement will be taken as the distance from the beginning of the two reactive component line to the end of the two reactive component line and will include the unmarked gaps for skip and dotted lines. The gross mile measurement will not include designated unmarked lengths at intersections, turn lanes, etc.

701-9.2 Removal of Existing Thermoplastic Markings: The quantity to be paid for removal of existing thermoplastic pavement markings will be the area, in square feet, acceptably removed. Payment for removal of thermoplastic pavement markings will only be made for locations where the existing pavement surface is to remain.

R

ARTICLE 709-10 is deleted and the following substituted:

709-10 Basis of Payment.

Price and payment will be full compensation for all work specified in this Section, including, all cleaning and preparing of surfaces, furnishing of all materials, application, curing and protection of all items, protection of traffic, furnishing of all tools, machines and equipment, and all incidentals necessary to complete the work. Final payment will be withheld until all deficiencies are corrected.

Payment will be made under:

Item No. 709	Two Reactive Components
	Solid - per gross mile.
	Skip - per gross mile.
	Remove - per square foot.

A

F

ARTICLE 709-11 is deleted.

T