

# EXPECTED IMPLEMENTATION JULY 2022

## 102 MAINTENANCE OF TRAFFIC. (REV 12-1-21) (FA 1-26-22) (7-22)

ARTICLE 102-10 is deleted and the following substituted:

### 102-10 Work Zone Pavement Marking.

**102-10.1 Description:** Furnish and install work zone pavement markings for MOT in construction areas and in close conformity with the lines and details shown in the Plans and Standard Plans.

Centerlines, lane lines, edge lines, stop bars, standard crosswalks, and turn arrows will be required in work zones prior to opening the road to traffic.

#### 102.10.2 Painted Pavement Markings:

**102-10.2.1 General:** Use painted pavement markings meeting the requirements of Section 710. Use standard paint unless otherwise identified in the Plans or approved by the Engineer.

#### 102-10.3 Removable Tape:

**102-10.3.1 General:** Use removable tape listed on the APL as shown in the Plans and meeting the requirements of 990-4.

**102-10.3.2 Application:** Apply removable tape with a mechanical applicator to provide pavement lines that are neat, accurate and uniform. Equip the mechanical applicator with a film cut-off device and with measuring devices that automatically and accumulatively measure the length of each line placed within an accuracy tolerance of plus or minus 2%. Ensure removable tape adheres to the road surface. Removable tape may be placed by hand on short sections, 500 feet or less, if it is done in a neat accurate manner.

**102-10.3.3 Retroreflectivity:** Apply white and yellow removable tape pavement markings that will attain an initial retroreflectivity of not less than  $300 \text{ mcd/lx}\cdot\text{m}^2$  for white and not less than  $250 \text{ mcd/lx}\cdot\text{m}^2$  for yellow markings. Black portions of contrast tapes and black masking tapes must have a retroreflectance of less than  $20 \text{ mcd/lx}\cdot\text{m}^2$ .

Measure, record and certify on the Department approved form and submit to the Engineer, the retroreflectivity of white and yellow removable tape pavement markings in accordance with FM 5-541.

**102-10.3.4 Removability:** Provide removable tape capable of being removed from bituminous concrete and portland cement concrete pavement intact or in substantially large strips, either manually or by a mechanical roll-up device, at temperatures above 40°F, without the use of heat, solvents, grinding or blasting.

**102-10.4 Temporary Raised Pavement Markers (RPMs):** Use Class B RPMs except for work that consists of ground-in rumble strips at centerline locations. For ground-in rumble strips at centerline locations, use temporary RPMs in accordance with Section 710. Provide only temporary RPMs listed on the APL. Install all markers in accordance with the manufacturer's recommendations, the Standard Plans, and Section 706. After initial installation, replace broken or missing temporary RPMs in

# EXPECTED IMPLEMENTATION JULY 2022

locations where more than three consecutive temporary RPMs are broken or missing at no expense to the Department.

0

AREA

1

2