
## EXPECTED IMPLEMENTATION JULY 2022



(REV 12-21-21) (FA 2-14-22) (7-22)

ARTICLE 234-9 is deleted and the following substituted:

## 234-9 Method of Measurement.

The quantity to be paid for will be the plan quantity. For each pay item, the pay area will be adjusted based upon the following formula:

Pay Area = Surface Area (actual tonnage placed/adjusted plan quantity tonnage).

Where: The adjusted plan quantity tonnage is calculated by multiplying the plan quantity square yards (including any Engineer approved quantity revisions) times the spread rate as defined in 234-8.1 and dividing by 2,000 pounds per ton, except the pay item's tonnage-weighted average G<sub>mm</sub> is used instead of the design G<sub>mm</sub> as defined in 234-8.1.

The pay area shall not exceed 110% of the designed surface area. Prepare and submit a Certification of Quantities to the Engineer in accordance with 9 2.1.2.