
## EXPECTED IMPLEMENTATION JULY 2022



ARTICLE 522-4 s deleted and the following substituted:

## 522-4 Foundation.

Shape and compact the foundation materials with suitable equipment to a firm, even surface, true to grade and cross-slope. Meet the testing frequency and maximum lift thickness requirements of Section 120. Record density test results in the Earthwork Records System (ERS) section of the Department's database. Compact cut-and-fill areas within 1 foot beyond each side of the sidewalk or driveway, when right-of-way conditions allow. Compact the foundation material below the bottom of concrete for a minimum depth of 1 foot for cut areas, 1 foot for fill areas less than 1 foot, and 2 feet for all other fill areas to a density not less than 95% of the maximum density as determined by FM 1-T099. Compact the material in the remaining fill areas to match the adjacent area density.