

EXPECTED IMPLEMENTATION JULY 2022

523 PATTERNED PAVEMENT. **(REV 1-27-22) (FA 1-28-22) (7-22)**

SECTION 523 is deleted and the following substituted:

SECTION 523 PATTERNED PAVEMENT

523-1 Description.

Patterned pavement is defined as a post applied surface marking material to either the pavement surface or to an imprinted pavement surface.

523-2 Materials.

Use patterned pavement products listed on the Department's Approved Product List (APL) meeting the requirements of Section 974.

Prior to installation, submit pattern and color samples to the Engineer for confirmation that the product meets the pattern and color specified in the Plans. Do not begin installation until acceptance by the Engineer.

The Engineer will take random samples of all material in accordance with the Department's Sampling, Testing and Reporting Guide schedule.

523-3 Construction Requirements.

Install patterned pavement on asphalt or concrete locations with the color and pattern as specified in the Plans. Prepare the surface and install patterned pavement in accordance with the manufacturer's installation instructions, using materials and equipment recommended and approved by the manufacturer.

Install overlay products to a thickness not exceeding 180 mils.

Patterns and variations within the installation shall comply with ADA requirements.

Complete all utility, traffic loop detector, and other items requiring a cut and installation under the finished surface, prior to product installation.

Protect treated surfaces from traffic and environmental effects until the product is completely installed, including drying and curing according to the manufacturer's instructions.

For installation on new asphalt roadways, apply patterned pavement a minimum of 14 days after placement of the adjacent pavement.

Patterned pavements shall be weather resistant, friction resistant, and through normal wear, shall show no signs of failure due to tearing, stretching, rollback, blistering, excessive cracking, chipping, discoloration, poor adhesion to the pavement, pavement damage, or vehicular damage.

Upon completion of the installation, the Engineer will check the area at random locations for geometric accuracy. If any of the chosen areas are found to be deficient, correct the entire patterned area at no additional cost to the Department.

EXPECTED IMPLEMENTATION JULY 2022

Submit certification to the engineer, including the APL number and that the patterned pavement was installed in accordance with the manufacturer's installation instructions and this Section.

523-4 Method of Measurement.

The quantity to be paid will be the plan quantity in square yards of patterned pavement, completed and accepted. No deduction will be made for areas occupied by landscaping, manholes, inlets, drainage structures, or by any public utility appurtenances within the area.

523-5 Basis of Payment.

Price and payment will be full compensation for all work specified in this Section. Payment will be made under:

Item No. 523- 3- Patterned Pavement - per square yard.