

EXPECTED IMPLEMENTATION JULY 2022

641 PRESTRESSED CONCRETE POLES (REV 11-10-21) (FA 1-12-22) (7-22)

ARTICLE 641-5 is deleted and the following substituted:

641-5 Pole Removal.

When removal of the pole and partial foundation removal is specified in the Plans, the remaining pole, foundation and any protrusions, such as pole keys, dead men, guying apparatus, conduit, anchor bolts, or reinforcing steel, must be removed to a minimum depth of 4 feet below existing grade.

When removal of the pole and complete foundation removal is specified in the Plans completely remove each pole including the foundation and all accessories and attachments, such as pole keys, dead men, guying apparatus, conduit, anchor bolts, and reinforcing steel.

Disconnect span wires carefully at the pole, and salvage all usable hardware and attachment devices as determined by the Engineer. Remove all devices supported by the span wire (including wiring) prior to the removal of the span wire.

SUBARTICLE 641-6.3 is deleted and the following substituted:

641-6.3 Pole Removal:

641-6.3.1 Pole Removal Partial: The quantity to be paid for will be the removal of each pole, including the foundation and all accessories and attachments, to a depth of not less than 4 feet below existing grade.

641-6.3.2 Pole Removal Complete: The quantity to be paid for will be the complete removal of the pole, foundation and all accessories and attachments.