



*Florida Department of Transportation*

RON DESANTIS  
GOVERNOR

605 Suwannee Street  
Tallahassee, FL 32399-0450

KEVIN J. THIBAUT, P.E.  
SECRETARY

December 14, 2021

Khoa Nguyen  
Director, Office of Technical Services  
Federal Highway Administration  
3500 Financial Plaza, Suite 400  
Tallahassee, Florida 32312

Re: State Specifications Office  
Section: **700**  
Proposed Specification: **7000203 Highway Signing.**

Dear Mr. Nguyen:

We are submitting, for your approval, two copies of the above referenced Supplemental Specification.

The changes are proposed by Olivia Townsend to clarify language for the depth of removal foundations for highway signing.

Please review and transmit your comments, if any, within two weeks. Comments should be sent via email to [daniel.strickland@dot.state.fl.us](mailto:daniel.strickland@dot.state.fl.us).

If you have any questions relating to this specification change, please call me at 850-414-4130.

Sincerely,

Signature on file

Daniel Strickland, P.E.  
State Specifications Engineer

DS/dh

Attachment

cc: Florida Transportation Builders' Assoc.  
State Construction Engineer

**HIGHWAY SIGNING.****(REV 11-3-21)**

SUBARTICLE 700-2.3 is deleted and the following substituted:

**700-2.3 Method of Measurement:** For single post and multi post sign assemblies, an assembly consists of all the signs mounted on a single structure. The Contract unit price per assembly for ground mounted signs (single post and multi-post), furnished and installed, will include furnishing the sign panels, support structure, foundation, hardware, and labor necessary for a complete and accepted installation.

The retroreflective sign strip will be paid for separately, and the Contract unit price per each will include furnishing the retroreflective sign strip, hardware and labor necessary for a complete and accepted installation.

For overhead signs, sign panels will be paid separately from support structures. The Contract unit price per each for sign panel, furnished and installed, will include furnishing the sign panels, hardware, and labor necessary for a complete and accepted installation. The Contract unit price for each overhead static sign structure, furnished and installed, will include furnishing the support structure, foundation, hardware, and labor necessary for a complete and accepted installation.

For the removal of overhead static sign structures, the quantity to be paid for will be the number of overhead static sign structures, including the foundation, to be removed.

When partial foundation removal is called for, remove the support structure, and foundation to a minimum depth of four feet below existing grade.

When complete foundation removal is called for, completely remove the support structure including the foundation.

Relocation of signs will consist of removing the existing sign assembly and installing the sign on a new foundation at the location shown in the Plans.

When the Plans call for existing ground-mounted signs to be relocated or removed, after removing the sign panel from the assembly, remove supports and footings. Restore the area of the sign removal or relocation to the condition of the adjacent area.

**HIGHWAY SIGNING.****(REV 11-3-21)**

SUBARTICLE 700-2.3 is deleted and the following substituted:

**700-2.3 Method of Measurement:** For single post and multi post sign assemblies, an assembly consists of all the signs mounted on a single structure. The Contract unit price per assembly for ground mounted signs (single post and multi-post), furnished and installed, will include furnishing the sign panels, support structure, foundation, hardware, and labor necessary for a complete and accepted installation.

The retroreflective sign strip will be paid for separately, and the Contract unit price per each will include furnishing the retroreflective sign strip, hardware and labor necessary for a complete and accepted installation.

For overhead signs, sign panels will be paid separately from support structures. The Contract unit price per each for sign panel, furnished and installed, will include furnishing the sign panels, hardware, and labor necessary for a complete and accepted installation. The Contract unit price for each overhead static sign structure, furnished and installed, will include furnishing the support structure, foundation, hardware, and labor necessary for a complete and accepted installation.

For the removal of overhead static sign structures, the quantity to be paid for will be the number of overhead static sign structures, including the foundation, to be removed.

When partial foundation removal is called for, remove the support structure, and foundation to a minimum depth of four feet below existing grade.

When complete foundation removal is called for, completely remove the support structure including the foundation.

Relocation of signs will consist of removing the existing sign assembly and installing the sign on a new foundation at the location shown in the Plans.

When the Plans call for existing ground-mounted signs to be relocated or removed, after removing the sign panel from the assembly, remove supports and footings. Restore the area of the sign removal or relocation to the condition of the adjacent area.