### **ORIGINATION FORM**

### **Proposed Revisions to the Specifications**

(Please provide all information - incomplete forms will be returned)

Date:	Office:				
Originator:	Specification Section:				
Telephone:	Article/Subarticle:				
email:	Α	Associated Section(s) Revisions:			
Will the proposed revision require changes to:					
Publication	Yes	No	Office S	Staff Contacted	
Standard Plans Index					
Traffic Engineering Manual					
FDOT Design Manual					
Construction Project Administration Manual					
Basis of Estimate/Pay Items					
Structures Design Guidelines					
Approved Product List					
Materials Manual					
		1			
Will this revision necessitate any of the following	ng:				
Design Bulletin Construction Bulletin	E:	stimates Bulle	etin	<b>Materials Bulletin</b>	
Are all references to external publications current?  Yes  No					
If not, what references need to be updated? (Pl	ease inclu	ıde changes iı	n the redline do	ocument.)	
Why does the existing language need to be cha	ngod2				
willy does the existing language need to be tha	iigeu:				
Summary of the changes:					
Are these changes applicable to all Department If not, what are the restrictions?	jobs?	Yes	No		



RON DESANTIS GOVERNOR

## KEVIN J. THIBAULT, P.E. SECRETARY

#### MEMORANDUM

**DATE:** November 12, 2021

**TO:** Specification Review Distribution List

**FROM:** Daniel Strickland, P.E., State Specifications Engineer

**SUBJECT:** Proposed Specification: **7000203 Highway Signing.** 

In accordance with Specification Development Procedures, we are sending you a copy of a proposed specification change.

The changes are proposed by Olivia Townsend to clarify language for the depth of removal foundations for highway signing in the Standard Specification.

Please share this proposal with others within your responsibility. Review comments are due within four weeks and should be sent to Mail Station 75 or online at <a href="http://fdotewp1.dot.state.fl.us/programmanagement/development/industryreview.aspx">http://fdotewp1.dot.state.fl.us/programmanagement/development/industryreview.aspx</a>.

Comments received after **December 9, 2021**, may not be considered. Your input is encouraged.

DS/dh

Attachment

# HIGHWAY SIGNING. (REV 11-3-21)

SUBARTICLE 700-2.3 is deleted and the following substituted:

**700-2.3 Method of Measurement:** For single post and multi post sign assemblies, an assembly consists of all the signs mounted on a single structure. The Contract unit price per assembly for ground mounted signs (single post and multi-post), furnished and installed, will include furnishing the sign panels, support structure, foundation, hardware, and labor necessary for a complete and accepted installation.

The retroreflective sign strip will be paid for separately, and the Contract unit price per each will include furnishing the retroreflective sign strip, hardware and labor necessary for a complete and accepted installation.

For overhead signs, sign panels will be paid separately from support structures. The Contract unit price per each for sign panel, furnished and installed, will include furnishing the sign panels, hardware, and labor necessary for a complete and accepted installation. The Contract unit price for each overhead static sign structure, furnished and installed, will include furnishing the support structure, foundation, hardware, and labor necessary for a complete and accepted installation.

For the removal of overhead static sign structures, the quantity to be paid for will be the number of overhead static sign structures, including the foundation, to be removed.

When partial foundation removal is called for, remove the support structure, and foundation to a minimum depth of four feet below existing grade.

When complete foundation removal is called for, completely remove the support structure including the foundation.

Relocation of signs will consist of removing the existing sign assembly and installing the sign on a new foundation at the location shown in the Plans.

When the Plans call for existing ground-mounted signs to be relocated or removed, after removing the sign panel from the assembly, remove supports and footings. Restore the area of the sign removal or relocation to the condition of the adjacent area.