

EXPECTED IMPLEMENTATION JULY 2022

700 HIGHWAY SIGNING. (REV 11-30-21) (FA 1-26-22) (7-22)

SUBARTICLE 700-4.13 is deleted and the following substituted:

700-4.13 Installation Requirements: Provide a walk-in DMS for locations over interstate travel lanes. Verify that any ventilation system incorporated within the sign is operational per the manufacturer's recommendations.

Ensure that the location of the lifting eyebolts, left in place or removed, is sealed to prevent water entry after installation.

Load the initial message libraries on both the sign control software and the sign controller. The Engineer will furnish the messages to be placed in these libraries.

