
EXPECTED IMPLEMENTATION JULY 2022



SUBARTICLE 713-4.3 is deleted and the following substituted:

713-4.3 Retroreflectivity: Apply white and yellow pavement markings that will attain an initial retroreflectivity of not less than 450 mcd/lx·m² for white markings and not less than 350 mcd/lx·m² for yellow markings. Black pavement markings must have a retroreflectance of less than 20 mcd/lx·m².

Measure, record and certify on Department approved form and submit to the Engineer, the retroreflectivity of white and yellow pavement markings in accordance with FM 5-541.