

EXPECTED IMPLEMENTATION JULY 2024 (FY 2024-25)

430 PIPE CULVERTS (REV 7-19-23) (FA 10-3-23) (FY2024-25)

ARTICLE 430-9 is deleted and the following is substituted:

430-9 Specific Requirements for Steel Reinforced Polyethylene Ribbed Pipe, Corrugated High-Density Polyethylene Pipe and Polyvinyl Chloride (PVC) Pipe.

430-9.1 Sampling Requirements: Submit a sample of each pipe material and diameter used on each project to the Engineer a minimum of two weeks prior to the installation, provided that the pipe meets all of the following:

1. Pipe is corrugated or ribbed
2. Pipe diameter is 12" or larger
3. Project quantity for a pipe diameter is more than 100 linear feet, unless intended for use as cross drain

4. Pipe is not perforated, unless the material is PVC
5. Pipe is intended for applications requiring 100 year design service life as defined in the Florida Department of Transportation Drainage Manual.

The length of each sample pipe section must comprise at least seven regular corrugations (not including the first three corrugations of the pipe on the bell or spigot ends).

430-9.2 Field Joints: Use gasketed joints to seal side drain, and storm and cross drain. Use gaskets meeting the requirements of Section 449. Ensure that the pipe manufacturer provides a joint design approved by the Engineer before use.

430-9.3 Installation Requirements Including Trenching, Foundation and Backfilling Operations: Check structure shape regularly during backfilling to verify acceptability of the construction method used.

Replace pipe deflected 5% or more of the certified actual mean diameter of the pipe at final inspection at no cost to the Department.