



Florida Department of Transportation

RON DESANTIS
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

JARED W. PERDUE, P.E.
SECRETARY

September 6, 2023

Khoa Nguyen
Director, Office of Technical Services
Federal Highway Administration
3500 Financial Plaza, Suite 400
Tallahassee, Florida 32312

Re: State Specifications Office
Section: 611
Proposed Specification: **6110402 Acceptance Procedures for Traffic Control Signals, Devices, and Intelligent Transportation System Devices.**

Dear Mr. Nguyen:

We are submitting, for your approval, two copies of the above referenced Supplemental Specification.

The changes are proposed by Derek Vollmer to reflect all currently published stand-alone test forms.

Please review and transmit your comments, if any, within two weeks (10 business days). Comments should be sent via email daniel.strickland@dot.state.fl.us.

If you have any questions relating to this specification change, please call me at (850) 414-4130.

Sincerely,

Daniel Strickland, P.E.
State Specifications Engineer

DS/dh

Attachment

cc: Florida Transportation Builders' Assoc.
State Construction Engineer

ACCEPTANCE PROCEDURES FOR TRAFFIC CONTROL SIGNALS, DEVICES, AND INTELLIGENT TRANSPORTATION SYSTEM DEVICES.

(REV 7-11-23)

SUBARTICLE 611-4.2 is deleted and the following substituted:

611-4.2 Intelligent Transportation System Device Installation: Test all stand-alone functions of the ITS devices as detailed in the Contract Documents and as approved by the Engineer.

For the managed field Ethernet switch (MFES), complete FDOT Form Number 750-040-07 for all installed field switches.

For the closed-circuit television (CCTV) camera, complete FDOT Form Number 750-040-08 for all installed CCTV cameras.

For microwave vehicle detection system (MVDS), complete FDOT Form Number 750-040-09 for all installed MVDS sensors.

For the camera lowering device (CLD), complete FDOT Form Number 750-040-10 for all installed CLDs.

For the dynamic message sign (DMS), complete FDOT Form Number 750-040-11 for all installed DMS.

For the remote power management unit (RPMU), complete FDOT Form Number 750-040-12 for all installed RPMU.

For the ITS cabinet, complete FDOT Form Number 750-040-13 for all installed ITS cabinets.

For ITS devices without official FDOT forms, evaluate ITS devices as per Contract Documents and as approved by the Engineer.

Complete approved data forms and turn them over to the Engineer for approval. Provide a minimum notice of 10 calendar days prior to all tests to permit the Engineer or their representative to observe each test.

If any unit fails to pass its stand-alone test, correct the unit, or substitute another unit in its place, then repeat the test.

If a unit has been modified as a result of a stand-alone test failure, prepare a report describing the nature of the failure and the corrective action taken and submit it to the Engineer prior to re-testing the unit. If a failure pattern develops, the Engineer may direct that modification be made to all units without additional cost to the Department or an extension of the Contract Time.

ACCEPTANCE PROCEDURES FOR TRAFFIC CONTROL SIGNALS, DEVICES, AND INTELLIGENT TRANSPORTATION SYSTEM DEVICES.**(REV 7-11-23)**

SUBARTICLE 611-4.2 is deleted and the following substituted:

611-4.2 Intelligent Transportation System Device Installation: Test all stand-alone functions of the ITS devices as detailed in the Contract Documents and as approved by the Engineer.

For the managed field Ethernet switch (MFES), complete FDOT Form Number 750-040-07 for all installed field switches.

For the closed-circuit television (CCTV) camera, complete FDOT Form Number 750-040-08 for all installed CCTV cameras.

For microwave vehicle detection system (MVDS), complete FDOT Form Number 750-040-09 for all installed MVDS sensors.

For the camera lowering device (CLD), complete FDOT Form Number 750-040-10 for all installed CLDs.

For the dynamic message sign (DMS), complete FDOT Form Number 750-040-11 for all installed DMS.

For the remote power management unit (RPMU), complete FDOT Form Number 750-040-12 for all installed RPMU.

For the ITS cabinet, complete FDOT Form Number 750-040-13 for all installed ITS cabinets.

For ITS devices without official FDOT forms, evaluate ITS devices as per Contract Documents and as approved by the Engineer.

Complete approved data forms and turn them over to the Engineer for approval. Provide a minimum notice of 10 calendar days prior to all tests to permit the Engineer or their representative to observe each test.

If any unit fails to pass its stand-alone test, correct the unit, or substitute another unit in its place, then repeat the test.

If a unit has been modified as a result of a stand-alone test failure, prepare a report describing the nature of the failure and the corrective action taken and submit it to the Engineer prior to re-testing the unit. If a failure pattern develops, the Engineer may direct that modification be made to all units without additional cost to the Department or an extension of the Contract Time.