

THERMOPLASTIC PAVEMENT MARKINGS.

(REV 3-31-22)

ARTICLE 711-9 is deleted and the following substituted:

711-9 Method of Measurement.

711-9.1 Thermoplastic Pavement Markings: The certified quantities, authorized and acceptably applied, under this Section will be paid as follows:

1. The length, in gross miles, of solid, 10'-30'skip, 3'-9'dotted, 6'-10'dotted, 2'-2'dotted, and 2'-4'dotted lines.

2. The length, in linear feet, of transverse lines, diagonal lines, chevrons, and parking spaces.

3. The number of pavement messages, symbols, arrows and raised crosswalk markings. Each arrow is paid as a complete marking, regardless of the number of "points" or directions. Each vertical deflection marking includes all arrows within the set, and each advance warning marking includes all lines within the set, as shown in the Developmental Standard Plan Index D520-030.

4. The area, in square feet, for removal of existing thermoplastic pavement markings acceptably removed. Payment for removal of thermoplastic pavement markings will only be made for locations where the existing pavement surface is to remain.

The gross mile measurement will be taken as the distance from the beginning of the thermoplastic line to the end of the thermoplastic line and will include the unmarked gaps for skip and dotted lines. The gross mile measurement will not include designated unmarked lengths at intersections, turn lanes, etc. Final measurement will be determined by plan dimensions or stations, subject to 9-1.3.1.

711-9.2 Removal of Existing Thermoplastic Markings: The quantity for removal of existing thermoplastic pavement markings to be paid will be the area, in square feet, acceptably removed. Payment for removal of thermoplastic pavement markings will only be made for locations where the existing pavement surface is to remain.

ARTICLE 711-10 is deleted and the following substituted:

711-10 Basis of Payment.

Prices and payments will be full compensation for all work specified in this Section, including, all cleaning and preparing of surfaces, furnishing of all materials, application, curing and protection of all items, protection of traffic, furnishing of all tools, machines and equipment, and all incidentals necessary to complete the work. Final payment will be withheld until all deficiencies are corrected.

Payment will be made under:

Item No. 711	Thermoplastic Pavement Markings
	Solid - per gross mile.
	Solid - per linear foot.
	Skip - per gross mile.
	Dotted - per gross mile.
	Message or Symbol - each.

Arrows - each.

Vertical Deflection Marking - each.

Vertical Deflection Advance Warning Marking - each.

Yield Line - per linear foot.

Railroad Dynamic Envelope - per linear foot.

Remove - per square foot.

Do Not Use Without
CO Specs Authorization