



LAYOUT FOR 1, 2 AND 3 DIGIT NUMBERS AND LETTERS



MESSAGE SIZE AND SPACING



NOTES:

1. Messages shall meet requirements of Specification Section 971-7 and Section 711.
2. The thickness of the preformed message shall be 125 mils.
3. The message shall consist of white letters and numbers with black contrasting material. The black material shall meet the mat dimensions shown and have a minimum skid resistance value of 55 BPN.
4. The "EXIT NUMBER" position remains the same (117'-8" from the beginning of taper regardless of the number of lines of information.