NOTES:

- 1. For Sections D-D, E-E, & F-F see Index Nos. 20612, 20614, 20618, 20620, 20624 or 20630 for applicable concrete pile size and Pile Splice Reinforcement Details.
- 2. Prestressing strands, spiral ties and/or reinforcement are not shown for clarity.
- In cases where pile splices are desired due to length limitations in shipping and/or handling, the "Drivable Preplanned Prestressed Precast Splice Detail" shall be used. Mechanical Pile Splices contained on the Approved Products List (APL) may also be used.
- When preformed dowel holes are utilized, the 1" spiral tie pitch shall be continued to 4'-0" below the head of the pile, See Index Nos. 20618, 20620 & 20624. Preformed holes shall utilize either removable preforming material or stay-in-place corrugated galvanized steel ducts. Stay-in-place ducts shall be fabricated from galvanized sheet steel meeting the requirements of ASTM A653, Coating Designation G90, 26 gauge. Ducts shall be 2" diameter with a minimum corrugation (rib) height of 0.12 in. Ducts shall be fabricated with either welded or interlocked seams. Galvanizing of welded seams will not be required.
- 5. For tension piles where top of Prestressed Pile is less than 3 feet below Pile Cut-off Elevation, extend No. 10 Dowels into cap beyond Pile Cut-off Elevation to achieve development as approved by the Engineer.

 $\parallel \parallel \parallel \parallel \parallel$

M

(Typ.)

D

1" Cover

at End

No. 10 Dowels


Mini

Full length of


Build-up


D

Detail A









NONDRIVABLE UNFORESEEN REINFORCED PRECAST PILE BUILD-UP DETAIL

. U U'U U

DRIVABLE UNFORESEEN PRESTRESSED PRECAST PILE SPLICE DETAIL

. U U'U U.

E

_ No. 10

Ε

Dowels

Detail A

Ö

section

Splice

pile

sed

Driven prestres

extension

Dowe!

DRIVABLE PREPLANNED PRESTRESSED PRECAST PILE SPLICE DETAIL

ΙE

No. 10

Dowels

See

Detail A

Preformed holes,

See Section F-F.

Ε

REVISION 07/01/14

UNFORESEEN

REINFORCED C-I-P

PILE BUILD-UP DETAIL

DESCRIPTION: