



SECTION C-C
(RAILS NOT SHOWN)

POST "D" DETAILS FOR SPECIAL HEIGHT BICYCLE RAILING
ON CONCRETE PARAPET (INDEX 820)



SECTION D-D
(RAILS NOT SHOWN)


POST "B" DETAILS FOR SPECIAL HEIGHT BICYCLE RAILING ON
TRAFFIC RAILINGS (INDEX 423 AND 821)
AND FOR PEDESTRIAN/BICYCLE
RAILING ON CONCRETE PARAPETS (INDEX 820)




SECTION E-E
(RAIL NOT SHOWN)

POST "C" DETAILS FOR PEDESTRIAN/BICYCLE RAILING
ON TRAFFIC RAILINGS (INDEX 423 AND 821)


NOTE: After nuts have been tightened, the bolt threads shall be deformed to prevent removal of nuts. Tack welding of nuts to anchor bolts, to prevent theft, is permitted. Coat deformed or tack welded threads with a galvanizing compound in accordance with Specification Section 562.



DETAIL "A"
ALTERNATE ANCHOR BOLT
(Concrete Parapet Shown,
Traffic Railings Similar)



SECTION F-F
BASE PLATE DETAIL



RAIL TO POST CONNECTION DETAIL

CROSS REFERENCES:

- For Post "B" and Post "D" spacing see Index 820.
- For Post "B" & Post "C" spacing see Index 423 or 821.
- For Rail Details see Sheet 2.
- For Railing Notes and Tapered End Transition Details see Sheet 3.

12/17/2015 11:39:28 AM

LAST REVISION
07/01/15

REVISION

DESCRIPTION:




FY 2016-17
DESIGN STANDARDS


BRIDGE ALUMINUM PEDESTRIAN/BICYCLE
BULLET RAILING DETAILS

INDEX NO.
822


SHEET NO.
1 of 3




SECTION A-A
TYPICAL SECTION THRU RAIL



SECTION B-B - RAIL SPLICE/EXPANSION BAR
(Rail not shown for clarity)




SECTION C-C
RAIL SPLICE/EXPANSION
BAR ASSEMBLY




INSERT BAR DETAIL (TYPE 1)


* Use of either Type 1 or Type 2 Insert Bars is at the option of the Contractor.



RAIL SPLICE/EXPANSION ASSEMBLY DETAIL




VIEW D-D




RAIL END CAP DETAIL

NOTE: Provide for drive fit.

CROSS REFERENCE:
For Notes and Tapered End Transition Details,
See Sheet 3.



VIEW E-E




RAIL CLAMP BAR DETAIL


Drill & tap hole to accept 3/8 inch Ø Stainless Steel Fasteners

12/17/2015 11:39:29 AM

LAST REVISION 07/01/14	REVISION	DESCRIPTION:	FY 2016-17 DESIGN STANDARDS	BRIDGE ALUMINUM PEDESTRIAN/BICYCLE BULLET RAILING DETAILS	INDEX NO. 822	SHEET NO. 2 of 3
---------------------------	----------	--------------	--------------------------------	--	------------------	---------------------




DOUBLE MITER TRANSITION (OPTION 1)




COMPOUND MITER TRANSITION (OPTION 2)


PARTIAL PLAN OF TAPERED END TRANSITIONS
(Single Rail Shown, Double or Triple Rail Similar)



VIEW G-G TRANSITION BASE PLATE
(Bullet Rail not shown for Clarity)



VIEW H-H TRANSITION BASE PLATE
(Bullet Rail not shown for Clarity)



ELEVATION OF TAPERED END TRANSITION
(Single Rail Shown, Double or Triple Rail Similar)

RAILING NOTES:

PAYMENT: Payment for the railing includes Rails, Posts, Rail Splice/Expansion Assemblies, Rail Clamp Bars, Rail End Caps, Anchor Bolts, Nuts, Resilient Pads, Screws and Washers and all incidental materials and labor required to complete the installation.

POST ASSEMBLY: Fabricated wrought aluminum; Post - ASTM B221, alloy 6061-T6, or alloy 6351-T5; Base Plate - ASTM B209, alloy 6061-T6.

WELDING: Welding of aluminum components shall be in accordance with ANSI and AWS D1.2 "Structures Welding Code - Aluminum".

RAIL AND RAIL SPLICE/EXPANSION ASSEMBLIES: Aluminum; ASTM B221, alloy 6061-T6, or alloy 6351-T5. Stop Pins shall be press-fit Aluminum or Stainless Steel pins or tubes, unless otherwise approved by the Engineer.

RAIL CLAMP BAR: Aluminum; ASTM B221, alloy 6061-T6, or alloy 6351-T5.

STAINLESS STEEL FASTENERS: 3/8" Ø Hex Cap Screws and Washers shall be ASTM F-593, alloy group 2 (316).

ANCHOR BOLTS: Anchor bolts shall be in accordance with ASTM A36 or ASTM F1554, Grade 36. Anchor Bolts, Nuts, and Washers shall be hot dip galvanized in accordance with Specification Section 962.

RAIL END CAP: ASTM B26 sand cast aluminum alloy 356.0-F.

RAIL INSTALLATION: Set Rail Posts normal to Profile Grade longitudinally and vertical transversely. Post spacings that land on barrier or parapet obstacles such as armor expansion plates etc. shall be adjusted to clear obstacles by 9" without exceeding maximum post spacing. Post shall be uniformly spaced with reasonable consistency. Set Posts on 1/8" thick resilient or neoprene pads in accordance with Specification Section 932. The pad dimension shall be the same as the post base plate. Provide rail expansion assembly in panels between posts on either side of Bridge Expansion Joints. Rail expansion assembly is similar to the rail splice assembly with increased space at assembly to allow for movement equal to 1.5 times the bridge joint opening or 1" greater than the expected joint movement. Take care to ensure rails are set with the proper openings. Remove any burrs or sharp edges on rails and posts to prevent injury.

RAIL SPLICE ASSEMBLIES: Rails shall be continuous over a minimum of 3 posts, except that lengths less than 12' need only be continuous over 2 posts. Space splices at 40'-0" maximum on centers. Splice all rails in any railing section about the same center line.

RESILIENT AND NEOPRENE PADS: Resilient and Neoprene Pads shall be in accordance with the Specifications except that testing of the finished pads is not required. Neoprene pads shall be durometer hardness 60 or 70.


SHOP DRAWINGS: Submit typical details for straight alignments and complete details for end terminations or curved alignments with radii < 40', including post and rail splice/expansion assembly locations of the proposed railing for the Engineer's approval prior to fabrication.

CROSS REFERENCE:

For Post Details see Sheet 1.

For Rail Details see Sheet 2.

12/17/2015 11:39:29 AM

LAST REVISION 07/01/15	REVISION	DESCRIPTION:	 FY 2016-17 DESIGN STANDARDS	BRIDGE ALUMINUM PEDESTRIAN/BICYCLE BULLET RAILING DETAILS	INDEX NO. 822	SHEET NO. 3 of 3
---------------------------	----------	--------------	--	--	-------------------------	----------------------------