


*The 45" Ø Void in the pile shall be positively vented to water or air after the final pile installation. If the 3 1/2" Ø vents are included in the pile cut-off section, then venting shall be provided by the use of a 1" Ø PVC conduit through the substructure cap or column.

ELEVATION



Maximum Pile Length (Feet)	Required Storage and Transportation Detail	Pick-Up Detail
122	2, 3, or 4 point	1 Point
174	2, 3, or 4 point	2 Point

NOTES

DESIGN SPECIFICATIONS:

Florida Department of Transportation (FDOT) "Structures Design Guidelines", current edition.
 American Association of State Highway and Transportation Officials (AASHTO) "LRFD Bridge Design Specifications", current edition.

SPIRAL TIES:

One full wrap of spirals is required at both the head and tip of pile. One half turn required for spiral splices.

CONCRETE CLASS:

Concrete for all piles shall be Class V (Special). Concrete for pile splices shall be Class IV. See "GENERAL NOTES" in Structures Plans for any specific locations where the use of Silica Fume is required for stainless steel reinforcing.

CONCRETE STRENGTH:

The cylinder strength shall be 4,000 psi minimum at time of transfer of the Prestressing Force.

SPLICE BONDING MATERIAL:

The material to form the joint between pile sections shall be a Type B Epoxy Compound in accordance with Specification Section 926. The bonding agent used on internal pile surfaces shall be a Type A Epoxy Compound in accordance with Specification Section 926. Epoxy Compounds used shall be contained on the Approved Products List (APL). Use Epoxy Bonding Compound or Epoxy Mortar as recommended by the Manufacturer. For Epoxy Mortar only use sand or other filler material supplied by the manufacturer and in the proportions recommended.

PICK-UP POINTS:

Piles shall be marked at the pick-up points to indicate proper points for attaching handling lines.

REINFORCING BARS:

Stainless Steel: All reinforcing steel shall meet the requirements of Specification Section 931 for Type 304, Grade 75.
 Carbon FRP: All reinforcing bars shall be CFRP meeting the requirements of Specification Section 932.


PRESTRESSING STRAND:

Stainless Steel: Prestressing steel shall be seven-wire strand HSSS, UNS S32205 (Type 2205) or UNS S31803 strand meeting the requirements of Specification Section 933.
 Carbon FRP: Prestressing strand shall be CFRP Strand meeting the requirements of Specification Section 933.


PILE DRIVING AFTER SPLICING:

Pile splices shall reach a minimum strength of 5500 psi before driving is resumed.

12/17/2015 2:18:04 PM




DRIVABLE UNFORESEEN FIELD SPLICE DETAIL
(Cast in Place Plug)




SECTION A-A

ALTERNATE STRAND PATTERNS

- 0.5" \emptyset , CFRP Single-Strand, at 39 kips
- 0.6" \emptyset , CFRP 7-Strand, at 40 kips



SECTION B-B



DETAIL "A"

CFRP POST-TENSIONED PILE DETAILS

12/17/2015 2:18:05 PM


LAST REVISION 01/01/16	REVISION	DESCRIPTION:
---------------------------	----------	--------------

FDOT
FY 2016-17
DESIGN STANDARDS


60" PRESTRESSED CFRP & SS CONCRETE
CYLINDER PILE

INDEX NO.
22660

SHEET NO.
2 of 3





DRIVABLE UNFORESEEN FIELD SPLICE DETAIL
(Cast in Place Plug)



ALTERNATE STRAND PATTERNS

- 44 ~ 0.6" \emptyset , HSSS Strand, at 36 kips
- 36 ~ 0.6" \emptyset , HSSS Strand, at 36 kips



SS POST-TENSIONED PILE DETAILS

12/17/2015 2:18:05 PM

LAST REVISION 01/01/16	DESCRIPTION:
---------------------------	--------------