



**GENERAL NOTES**


1. Poles are designed to support the following:
  - A. Luminaire Effective Projected Area (EPA): 1.55 SF
  - B. Weight: 75 lb.
2. Shop Drawings: This Index is considered fully detailed, only submit shop drawings for minor modifications not included in the Plans.
3. Materials:
  - A. Pole, Pole Connection Extrusions and Arm Extrusions: ASTM B221, Alloy 6063-T6
  - B. Bars, Plates, Stiffeners and Backer Ring: ASTM B221, Alloy 6063-T6
  - C. Caps and Covers: ASTM B-26, Alloy 319-F
  - D. Steel Bearing Plate: ASTM A709 or ASTM A36 Grade 36
  - E. Aluminum Weld Material: ER 4043
  - F. Transformer and Frangible Base Materials: ASTM B26 or ASTM B108, Alloy 356-T6
  - G. Bolts, Nuts and Washers:
    - a. Shoe Base Bolts: ASTM F3125, Grade A325, Type 1
    - b. Nuts: ASTM A563 Grade DH Heavy-Hex
    - c. Washer: ASTM F436 Type 1
  - H. Anchor Bolts, Nuts, and Washers:
    - a. Anchor Bolts: ASTM F1554 Grade 55
    - b. Nuts: ASTM A563 Grade A Heavy-Hex
    - c. Plate Washer: ASTM A36
  - I. Stainless Steel Fasteners: ASTM F593 Alloy Group 2, Condition A, CW1 or SH1
  - J. Nut Covers: ASTM B26 (319-F)
  - K. Concrete: Class 1
  - L. Reinforcing Steel: Specification Section 415
4. Fabrication:
  - A. Weld Arm and Pole (Alloy 6063) in the T4 temper using 4043 filler. Age the Arm and Pole artificially to the T6 temper after welding.
  - B. Upright Splices: Not Allowed. Transverse welds are only allowed at the base.
  - C. Roadway Light Pole Taper: Taper as required to provide a round top O.D. of 6" and a base O.D. of 10". Portions of the pole near the base shoe and at the arm connections may be held constant at 10" and 6" respectively to simplify fabrication.
  - D. Median Barrier Mounted Light Pole Taper: Taper as required to provide a 6" O.D. round top with an 11" x 7" O.D. oblong base. Portions of the pole near the base and at the arm connections may be held constant at 11" x 7" oblong and 6" round respectively to simplify fabrication.
  - E. Provide 'J', 'S' or 'C' hook at top of pole for electrical wires.
  - F. Equip poles located on bridges, walls and concrete median barriers/Traffic Railings with a vibration damper.
  - G. Perform all welding in accordance with AWS D1.2.
  - H. Embedded Junction Boxes (EJB):
    - a. Weld all seams continuously and grind smooth.
    - b. Hot Dip Galvanize after Fabrication.
    - c. Provide a watertight cover with neoprene gasket and secure cover with galvanized screws.
  - I. For Median Barrier Mounted Aluminum Light Poles, the fabricator must demonstrate the ability to produce a crack free pole. The fabricator's Department-approved QC Plan must contain the following information prior to fabrication:
    - a. Tests demonstrating a pole with a 1/4" wall thickness achieves and ultimate moment capacity of 36 kip\*ft in the strong axis and 30 kip\*ft in the weak axis.
    - b. Tests demonstrating a pole with a 5/16" wall thickness achieves an ultimate moment capacity of 44 kip\*ft in the strong axis and 37 kip\*ft in the weak axis.
    - c. Test results showing the pole does not buckle at the shape transition area under the ultimate moment capacity loads.
    - d. Complete details and calculations for the reinforced 4"x 6" (Min.) handhole located 1'-6" above the base plate.
  - J. Identification Tag: (Submit details for approval.)
    - a. 2" x 4" (Max.) aluminum identification tag.
    - b. Locate on the inside of the transformer base and visible from the door opening.
    - c. Secure to transformer base with 1/8" diameter stainless steel rivets or screws.
    - d. Include the following information on the ID Tag:
      1. Financial Project ID
      2. Pole Height
      3. Manufacturer's Name
5. Coatings/Finish:
  - A. Pole and Arm Finish: 50 grit satin rubbed.
  - B. Galvanize Steel Bolts, Screws, Nuts and Washers: ASTM F2329
  - C. Hot Dip Galvanize EJB and other steel items including poles: ASTM A123
6. Construction:
  - A. Foundation: Specification Section 455, except payment for the foundation is included in the cost of the pole.
  - B. Frangible Base, Base Shoe, and Clamp:
    - a. Certify that the Clamp, Frangible Transformer Base, and Base Shoe Design are capable of providing the required capacity.
    - b. Certify the Base conforms to the current FHWA required AASHTO Frangibility Requirements, tested under NCHRP Report 350 Guidelines (e.g. Akron Foundry TB1-17).
    - c. Do not erect pole without Luminaire attached.
7. Payment Note: Include the cost of the EJB in the cost of the median barrier or Traffic Railing it is embedded in.

10/14/2016 10:57:21 AM


LAST REVISION 11/01/16	REVISION	DESCRIPTION:	 <b>FY 2017-18 DESIGN STANDARDS</b>	<b>STANDARD ALUMINUM LIGHTING</b>	INDEX NO. 17515	SHEET NO. 1 of 8
---------------------------	----------	--------------	--	-----------------------------------	--------------------	---------------------



STANDARD ROADWAY ALUMINUM LIGHT POLE W/ARM



MEDIAN BARRIER MOUNTED ALUMINUM LIGHT POLE ON CYLINDRICAL FOUNDATION



MEDIAN BARRIER MOUNTED ALUMINUM LIGHT POLE ON SPREAD FOOTING FOUNDATION

ELEVATIONS


10:57:24 AM  
10/14/2016

LAST REVISION	DESCRIPTION:
11/01/16	


**FY 2017-18**  
**DESIGN STANDARDS**


**STANDARD ALUMINUM LIGHTING**

INDEX NO.	SHEET NO.
17515	2 of 8




ARM CONNECTION DETAIL

ARM SECTION




SECTION A-A  
(Connection At Lower Arm Similar)




VIBRATION DAMPER ELEVATION

DIMPLE DETAIL



ARM ELEVATION



VIEW B-B

VIEW C-C

HIGH TEMP VINYL CAP DETAIL

ARM TABLE					
Wind Speed (mph)	Arm Length (ft)	Upper Arm		Lower Arm	
		O.D. (in)	Weld (in)	O.D. (in)	Weld (in)
120	8	3.63	0.125	3.63	0.188
120	10	3.63	0.188	3.63	0.188
120	12	3.63	0.188	3.63	0.188
120	15	4.63	0.188	4.63	0.188
140	8	3.63	0.188	3.63	0.188
140	10	3.63	0.188	3.63	0.188
140	12	3.63	0.250	3.63	0.250
140	15	4.63	0.250	4.63	0.250
160	8	3.63	0.188	3.63	0.188
160	10	3.63	0.250	3.63	0.250
160	12	4.63	0.250	4.63	0.250
160	15	4.63	0.313	4.63	0.313

ARM TUBE EXTRUSIONS NOTES:





At the pole connections, provide arm tube extrusions with dimensions as shown in the ARM SECTION and as tabulated in the ARM DATA Tables. Uniformly transition elliptical section to a cylindrical section at the arm connection.

The fabricator may substitute elliptical cross sections other than those tabulated, provided the section properties about the vertical axis and the area of the section equal or exceed that of the required section, and provide minimum wall thickness of 1/8" nominal and within the Aluminum Association Tolerances.



The outside diameter about the minor axis should be held at 2 3/8" at the upper and lower arms.

\* Increase Member Wall Thickness as Necessary to Meet Minimum Requirements of the Welding Code for the Connection Weld Sizes Shown in the Arm and Pole Tables.

10/14/2016 10:57:27 AM




Wind Speed (mph)	Arm Length (ft)	Design Mounting Height (ft)	Pole wall (in)	Upper Weld (in)	Lower Weld (in)
120	8,10,12,15	30	0.125	0.125	0.125
120	8,10,12,15	35 & 40	0.188	0.125	0.188
120	8,10	45	0.250	0.125	0.25
120	12,15	45	0.250	0.188	0.250
120	8	50	0.313	0.125	0.250
120	10,12,15	50	0.313	0.188	0.250
140	8,10,12,15	30	0.188	0.125	0.188
140	8,10	35	0.188	0.125	0.188
140	12, 15	35	0.250	0.125	0.250
140	8,10,12,15	40	0.250	0.125	0.250
140	8,10	45	0.313	0.125	0.250
140	12,15	45	0.313	0.188	0.250
140	8,10,12	50	0.375	0.188	0.313
140	15	50	0.375	0.250	0.313
160	8,10,12,15	30	0.188	0.125	0.188
160	8,10,12,15	35	0.25	0.125	0.250
160	8,10,12,15	40	0.313	0.188	0.250
160	8,10	45	0.375	0.188	0.313
160	12,15	45	0.375	0.250	0.313



Wind Speed (mph)	Design Mounting Height (ft)	Pole wall (in)	Upper Weld (in)	Lower Weld (in)
120	30 & 35	0.125	0.125	0.125
120	40	0.188	0.125	0.188
120	45	0.188	0.125	0.188
120	50	0.250	0.125	0.250
140	30	0.125	0.125	0.125
140	35 & 40	0.188	0.125	0.188
140	45	0.250	0.125	0.250
140	50	0.313	0.188	0.250
160	30	0.125	0.125	0.125
160	35	0.188	0.125	0.188
160	40	0.250	0.125	0.250
160	45	0.313	0.188	0.250
160	50	0.375	0.250	0.313

**NOTE:**  
Pole wall thicknesses shown in the POLE TABLE are nominals and shall be within the Aluminum Association Tolerances. Thicker walls are permitted and tapered walls may be used provided the minimum Aluminum Association thicknesses are not violated.




Wind Speed (mph)	Design Mounting Height (ft)	Total Depth (FT)**
120	30 & 35	6
120	40 & 45	7
120	50	8
140	30, 35 & 40	7
140	45 & 50	8
160	30 & 35	7
160	40 & 45	8

Wind Speed (mph)	Design Mounting Height (ft)	Total Depth (FT)**
120	30, 35 & 40	6
120	45 & 50	7
140	30 & 35	6
140	40 & 45	7
140	50	8
160	30	6
160	35 & 40	7
160	45 & 50	8


\* #4 Tie Bars @ 12" centers (max.) or D10 (or W10) spiral @ 6" pitch, 3 flat turns top and 1 flat turn bottom.

\*\* Depths shown in table are for grades flatter than 1:4, for grades up to 1:2 add 2'-6" to foundation depths shown in table.


10/11/2019 1:19:06 PM




STIFFENER PLATE DETAIL



BASE PLATE PLAN



BASE PLATE ELEVATION




DETAIL 'A'

POLE TABLE				
WIND SPEED (MPH)	ARM LENGTH (FT)	DESIGN MOUNTING HEIGHT (FT)	POLE WALL (IN)	FILL HEIGHT (FT)
120	8, 10, 12	40	0.25	Up to 70'
140	8, 10, 12	40	0.25	Up to 70'
160	8, 10, 12	40	0.313	Up to 70'

NOTE:  
Pole wall thicknesses shown in the POLE TABLE are nominals and shall be within the Aluminum Association Tolerances. Thicker walls are permitted and tapered walls may be used provided the minimum Aluminum Association thicknesses are not violated.

NOTE:

1. For locations of Bearing Plates, Base Plates and Detail 'A' see Sheets 6 & 7.
2. Double Nuts: The bottom hex nut may be substituted by a half height 'Jam' nut.
3. Provide individual nut covers (not shown) for each bolt.




BEARING PLATE ELEVATION

BEARING PLATE PLAN


BASE PLATE DETAILS FOR MEDIAN BARRIER MOUNTED ALUMINUM LIGHT POLE

11/1/2016 11:16:18 AM


LAST REVISION	DESCRIPTION:
11/01/16	




Provide dowel bars @ construction joint  
**PLAN**  
(Reinforcing steel not shown)




**EMBEDDED JUNCTION BOX DETAILS**



**ELEVATION**  
(For Roadway Concrete Barrier Wall reinforcing steel see Roadway Plans)



**END VIEW**








**BAR BENDING DIAGRAMS**

- NOTES:
1. For Bearing Plate Details, see Sheet 5.
  2. Dowel Construction Joint per Index 410.
  3. For adjacent Concrete Barrier Details, see Index 410

**SPREAD FOOTING DETAILS FOR MEDIAN BARRIER MOUNTED ALUMINUM LIGHT POLE**

10/14/2016 10:57:35 AM

LAST REVISION 11/01/16	DESCRIPTION:		FY 2017-18 DESIGN STANDARDS	STANDARD ALUMINUM LIGHTING	INDEX NO. 17515	SHEET NO. 6 of 8
REVISION						



\* #4 Tie Bars @ 12" centers (max.) or D10 (or W10) spiral @ 6" pitch, 3 flat turns top and 1 flat turn bottom.


- NOTES:
1. For Base Plate Details, Bearing Plate Detail, and Detail 'A', see Sheet 5.
  2. Dowel Construction Joint per Index 410
  3. For adjacent Concrete Barrier Details, See Index 410.

FOUNDATION TABLE		
WIND SPEED (MPH)	DESIGN MOUNTING HEIGHT (FT)	FOUNDATION DEPTH (FT)
120	40	8
140	40	9
160	40	9


CYLINDRICAL FOUNDATION DETAILS FOR MEDIAN BARRIER MOUNTED ALUMINUM LIGHT POLE

10/26/2016 1:18:39 PM


LAST REVISION 11/01/16	DESCRIPTION:	FY 2017-18 DESIGN STANDARDS	INDEX NO. 17515	SHEET NO. 7 of 8
---------------------------	--------------	--------------------------------	--------------------	---------------------




**PLAN**  
(Reinforcing steel not shown)



**BAR BENDING DIAGRAMS**  
(See Note 2)



**ELEVATION**  
(Longitudinal and transverse deck reinforcing steel not shown)



**END VIEW**

(Longitudinal and transverse deck reinforcing steel not shown)

**NOTES:**

1. For Base Plate Details, Bearing Plate Details, and Detail 'A', see Sheet 5.
2. See Index 421 for details of adjacent Traffic Railing (Median 32" F-Shape) and for angles  $\odot A$  and  $\odot B$ .

**DETAILS FOR TRAFFIC RAILING (MEDIAN 32" F-SHAPE) MOUNTED ALUMINUM LIGHT POLE**

10/14/2016 10:57:39 AM

LAST REVISION 11/01/16	DESCRIPTION:
---------------------------	--------------

**FDOT** FY 2017-18  
DESIGN STANDARDS

STANDARD ALUMINUM LIGHTING

INDEX NO.  
**17515**

SHEET NO.  
**8 of 8**