


**PLAN**  
(Reinforcing Steel not shown for clarity)

BARRIER DELINEATOR SPACING	
Distance - Edge of Travel Lane to Face of Railing	Spacing (Ft.)
< 4'	40'
4' to 8'	80'
> than 8'	None Required



**ELEVATION OF INSIDE FACE OF RAILING**  
(Reinforcing Steel not shown for clarity)  
(Railing on Bridge Deck and Approach Slab shown, Railing on Retaining Wall similar)

**CROSS REFERENCE:**  
For Section A-A, View B-B and Detail "A", see Sheet 2.  
For Detail "B", see Sheet 4.

**TRAFFIC RAILING NOTES**

This railing has been structurally evaluated to be equivalent or greater in strength to other safety shape railings which have been crash tested to NCHRP Report 350 TL-4 Criteria.

**CONCRETE AND REINFORCING :** See Structures Plans General Notes and Specification Section 415 and 932.

**GUARDRAIL :** For Guardrail connection details see Index 400.

**SUPERELEVATED BRIDGES :** At the option of the Contractor the Traffic Railing on superelevated bridges may be constructed perpendicular to the roadway surface. If an adjoining railing is constructed plumb, transition the end of the Traffic Railing from perpendicular to plumb over a minimum distance of 20'-0". The cost of all modifications will be at the Contractor's expense.

**PEDESTRIAN AND BICYCLE RAILING :** See Index 821 and 822 for Notes, Details and post spacings for Traffic Railings with Aluminum Pedestrian /Bicycle Bullet Railings.

**V-GROOVES :** Construct 1/2" V-Grooves plumb. Space V-Grooves equally between 3/4" Open Joints and/or Deck Joints and at V-Groove locations on Retaining Wall footings.

**NAME, DATE AND BRIDGE NUMBER :** The Name and Bridge Number shall be placed on the Traffic Railing so as to be seen on the driver's right side when approaching the bridge. The Date shall be placed on the driver's left side when approaching the bridge. The Name shall be as shown in the General Notes in the Structures Plans. The Date shall be the year the bridge is completed. For a widening when the existing railing is removed, use both the existing date and the year of the widening. Black plastic letters and figures 3" in height may be used, as approved by the Engineer, in lieu of the letters and figures formed by 3/8" V-Grooves. V-Grooves shall be formed by preformed letters and figures.


**BARRIER DELINEATORS :** Barrier Delineators shall meet Specification Section 993. Install Barrier Delineators on top of the Traffic Railing 2" from the face on the traffic side at the spacing shown in the table above. Barrier Delineator color (white or yellow) shall match the color of the near edgeline. The cost of the Barrier Delineators shall be included in the Contract Unit Price for the Traffic Railing.

**JOINTS :** See Plans, Superstructure, Approach Slab and Retaining Walls Sheets for actual dimensions and joint orientation. Provide open Railing Joints at Deck Expansion Joint locations matching the dimensions of the Deck Joint. For treatment of Railings on skewed bridges see Sheet No. 3.


Provide 3/4" Intermediate Open Joints at :

- (1) - Superstructure supports where slab is continuous.
- (2) - Ends of approach slabs when adjacent to retaining walls and at expansion joints on retaining wall junction slabs.


SDATES

LAST REVISION 06/01/17	REVISION	DESCRIPTION:	 <b>DEVELOPMENTAL DESIGN STANDARDS</b>	<b>TRAFFIC RAILING - (32" F SHAPE - GFRP REINFORCED)</b>	INDEX NO. D22420	SHEET NO. 1 of 4
---------------------------	----------	--------------	--	--	---------------------	---------------------


\* Where railings of adjacent bridges are to be built back to back, the outside vertical plane of the railing and deck/approach slab may coincide along a plane centered 1'-6" from each gutter line. A bond breaker will be required. See Structures Plans, Superstructure Sheets for Details.



**SECTION A-A**  
**TYPICAL SECTION THRU TRAFFIC RAILING**  
 (Section thru Bridge Deck shown, Section thru Approach Slab and Retaining Walls similar)




**OPTIONAL HEADED ANCHOR SECTION**  
**USING BAR 5V1 CONFIGURATION**  
 (Bars 5V3 Similar)




**VIEW B-B**  
 (Section thru Approach Slab shown, Section thru Retaining Walls similar)

**NOTES:**  
 Rotate Bars 5V in Railing End Transition to maintain cover. Begin placing Railing Bars 5P and 5V on Approach Slab at the barrier end and proceed toward Begin or End Bridge to avoid conflict with guardrail bolt holes. If required, adjustments to the bar spacing for Bars 5P and 5V shall be made immediately adjacent to Begin or End Bridge.

**CROSS REFERENCE:**  
 For locations of Section A-A and View B-B see Sheet 1.



**PLAN - Railing End Transition**  
 (Showing Bars 5V and 5S, Bars 5V1 or 5V3, & 5V2 similar)




**PLAN - Railing End Transition**  
 (Showing Bars 5P and 5S)

**DETAIL "A"**  
 (Railing on Approach Slab shown, Railing on Retaining Wall similar)

**NOTE:** Omit Railing End Transition and Guardrail if Index 410 Concrete Barrier Wall is used beyond the Approach Slab or Retaining Wall. See Structures Plans, Plan and Elevation Sheet and Roadway Plans. If Railing End Transition is omitted, extend Typical Section to end of the Approach Slab or limiting station on Retaining Wall, and space Bars 5P and 5V at 6" (Typ.)

SDATES


LAST REVISION 06/01/17	REVISION	DESCRIPTION:	 <b>DEVELOPMENTAL DESIGN STANDARDS</b>	<b>TRAFFIC RAILING -</b> <b>(32" F SHAPE - GFRP REINFORCED)</b>	INDEX NO. D22420	SHEET NO. 2 of 4
---------------------------	----------	--------------	---	--	---------------------	---------------------



**PARTIAL PLAN VIEW OF SKEWED BRIDGE DECK AND APPROACH SLAB WITH SIDEWALK, F SHAPE TRAFFIC RAILING AND PEDESTRIAN/BICYCLE RAILING INDEX NO. 820, 825 or 826, OTHER TRAFFIC RAILINGS SIMILAR**

**NOTES:**

- 1) Concrete Parapet reinforcement is not effected by skew angle, see Index No. 820 for details.
- 2) Parapet expansion joint shall match the deck expansion joint which shall be turned perpendicular or radial to the gutter line. See Structures Plans, Superstructure Sheets for details.
- 3) Traffic Railing reinforcement vertical Bars 5V & 5P may be shifted up to 1" (Max.) and rotated up to 10 degrees as required to allow proper placement. Bars 5V adjacent to expansion joints shall be field adjusted to maintain clearance and spacing, extra Bars 5V will be required. Bars 5V bottom horizontal portion shall be cut so as to maintain maximum bottom horizontal length of bar to each vertical leg being placed, the remainder of bar shall be discarded. Cut Bars 5V may be rotated to maintain clearance.
- 4) Railing ends at deck expansion joints shall follow the deck joint with allowance for joint movement. Expansion joint at the inside face of parapet shall be turned perpendicular or radial to this line. See Structures Plans, Superstructure and Approach Slab Sheets for details.
- 5) 3/4" Intermediate Open Joints and V-Grooves in railing and parapet shall be placed perpendicular or radial to the gutter line or inside face of parapet line. See Structures Plans, Superstructure Sheets for locations.
- 6) At begin or end approach slab extend slab at the railing ends 3" (gutter side or back face of railing as required) as shown to provide a base for casting of the railing.
- 7) Begin placing Railing Bars 5P and 5V on Approach Slab at the railing end and proceed toward Begin or End Bridge to ensure placement of guardrail bolt holes. If required, adjustments to the bar spacing for Bars 5P and 5V shall be made immediately adjacent to Begin or End Bridge.



**PARTIAL PLAN VIEW OF SKEWED BRIDGE DECK AND APPROACH SLAB WITH F SHAPE TRAFFIC RAILING, OTHER TRAFFIC RAILINGS SIMILAR**


**NOTES:**

- 1) Railing expansion joint shall match the deck expansion joint which shall be turned perpendicular or radial to the gutter line. See Structures Plans, Superstructure Sheets for details.
- 2) 3/4" Intermediate Open Joints and 1/2" V-Grooves in railing shall be placed perpendicular or radial to the gutter line. See Structures Plans, Superstructure and Approach Slab Sheets for locations.
- 3) Begin placing Railing Bars 5P and 5V on Approach Slab at the railing end and proceed toward Begin or End Bridge to ensure placement of guardrail bolt holes. If required, adjustments to the bar spacing for Bars 5P and 5V shall be made immediately adjacent to Begin or End Bridge.

**GENERAL NOTES:**

- 1) Work this Sheet with Traffic Railing, Pedestrian/Bicycle Railing, and Approach Slab Indexes as applicable.
- 2) Deck Expansion Joint at begin or end bridge shown. Deck Expansion Joints at  $\phi$  Pier or Intermediate Bents are similar.
- 3) Partial Plan Views shown are intended as guides only. See Structures Plans, Superstructure and Approach Slab Sheets for skew angles, joint orientation, dimensions and details.
- 4) Railings on Raised Sidewalks shall be treated similar to the Partial Plan View of Bridge Deck with Traffic Railing.

SDATES

LAST REVISION 06/01/17	REVISION	DESCRIPTION:	 <b>DEVELOPMENTAL DESIGN STANDARDS</b>	<b>TRAFFIC RAILING - (32" F SHAPE - GFRP REINFORCED)</b>	INDEX NO. D22420	SHEET NO. 3 of 4
---------------------------	----------	--------------	---	--	---------------------	---------------------



ALTERNATE REINFORCING BAR DETAILS

GFRP REINFORCING BAR BENDING DIAGRAMS


ROADWAY CROSS-SLOPE	LOW GUTTER		HIGH GUTTER	
	∅A	∅B	∅A	∅B
0% to 2%	90°	90°	90°	90°
2% to 6%	93°	87°	87°	93°
6% to 10%	96°	84°	84°	96°

BILL OF REINFORCING STEEL		
MARK	SIZE	LENGTH
P	5	5'-7"
S	5	As Req'd.
V	5	5'-2"


∅A and ∅B shall be 90° if Contractor elects to place railing perpendicular to the deck and approach slabs.



**BAR 5V1 (Headed Anchor)**      **BAR 5V2**      **BAR 5V3 (Adhesive Anchor)**      **BAR 5P1 (Closed Stirrup or Spiral 5P1 at 6" Pitch)**




**SPIRAL LAYOUT & LONGITUDINAL SPLICE DETAIL**



See Note 2  
See Note 1 & 2

ALTERNATE REINFORCING NOTES:


- At the option of the Contractor Headed Anchor Bars 5V1, 5V2, and/or Spirals 5P1 may be utilized in lieu of all Bars 5V, and 5P. Anchor Bars must be submitted to the Engineer for approval and supported by successful independent testing. Bar 5V2 may be cast-in-place or adhesive bonded dowels.
- Adhesive Anchor Bars 5V3 and 5V2 must be installed in accordance with Specification Section 416 and 937.



**STIRRUP BAR 5P**      **STIRRUP BAR 5V**      **END STIRRUP BAR 5V To Be Field Cut (One Required per Railing End Transition)**

REINFORCING BAR NOTES:


- All bar dimensions in the bending diagrams are out to out.
- The 9" and the 2'-4" vertical dimensions shown for Bar 5V are based on a bridge deck without a raised sidewalk. If a raised sidewalk is to be provided, increase these dimensions to achieve a 6" minimum embedment into the bridge deck. See Structures Plans, Superstructure and Approach Slab Sheets.
- The reinforcement for the railing on a retaining wall shall be the same as detailed above for a 8" deck with ∅A = ∅B = 90°
- All reinforcing bars at the open joints shall have a 2" minimum cover.
- Bars 5S may be continuous or spliced at the construction joints. Bar splices for Bars 5S shall be a minimum of 2'-2".



**DETAIL "B" - SECTION AT INTERMEDIATE OPEN JOINT**

INTERMEDIATE JOINT SEAL NOTES:

- At Intermediate Open Joints, seal the lower 6" portion of the open joint with Pre-cured Silicone Sealant in accordance with Specification Section 932.
- Apply sealant prior to any Class V finish coating and remove all curing compound and loose material from the surface prior to application of bonding agent.
- The cost of the Pre-cured Silicone Sealant shall be included in the Contract Unit Price for the Traffic Railing.



**SECTION THRU RECESSED "V" GROOVE TO FORM INSCRIBED LETTERS AND FIGURES**

ESTIMATED TRAFFIC RAILING QUANTITIES		
ITEM	UNIT	QUANTITY
Concrete	CY/LF	0.104
Reinforcing	LF	Varies

(The above quantities are based on a 2% deck cross slope; railing on low side of deck.)

SDATES

LAST REVISION 06/01/17	DESCRIPTION:
---------------------------	--------------



**TRAFFIC RAILING - (32" F SHAPE - GFRP REINFORCED)**

INDEX NO. D22420	SHEET NO. 4 of 4
---------------------	---------------------