

STRUCTURES STANDARDS



JANUARY 1984

17P 8-9-85


TABLE OF CONTENTS

INDEX	TITLE
	BEARING PADS
12037	COMPOSITE NEOPRENE BEARING PADS
	HANDRAIL
12087	ALUMINUM HANDRAIL (SIDEWALK)
13857	CONCRETE HANDRAIL BARRIER
11460	SIDEWALK BARRIER
12931	BICYCLE BARRIER
	PILES
3400	12", 14" AND 18" PRESTRESSED CONCRETE PILES
10289F	20", 24" AND 30" PRESTRESSED CONCRETE PILES
	REINFORCING STEEL
10587	STANDARD BAR BENDING DETAILS
	COMPOSITE DECK PANELS
12641 (1 of 3)	PRECAST PRESTRESSED PANELS
12641 (2 of 3)	FLAT PRECAST PANELS
12641 (3 of 3)	RIBBED PRECAST PANELS
12642 (1 of 3)	PRECAST PRESTRESSED PANELS
12642 (2 of 3)	FLAT PRECAST PANELS
12642 (3 of 3)	RIBBED PRECAST PANELS
	STANDARD BRIDGE DETAILS (SUPERSTRUCTURE, PRECAST SLAB UNITS)
12661	GENERAL & CONSTRUCTION NOTES
12662	END BENT, ZERO DEGREE SKEW
12663	END BENT, 12½ DEGREE SKEW
12664	END BENT, 25 DEGREE SKEW
12665	END BENT WING DETAILS
12666	INTERMEDIATE BENT, ZERO DEGREE SKEW
12667	INTERMEDIATE BENT, 12½ DEGREE SKEW
12668	INTERMEDIATE BENT, 25 DEGREE SKEW
12669 (1 of 2)	SUPERSTRUCTURE
12669 (2 of 2)	SUPERSTRUCTURE
12670 (1 of 3)	PRESTRESSED SLAB UNITS
12670 (2 of 3)	PRESTRESSED SLAB UNITS
12670 (3 of 3)	PRESTRESSED SLAB UNITS


NOTE: Numbers in parentheses in block with index number,
When shown, indicates revision number.

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION
STRUCTURES


BRIDGE DESIGN STANDARDS



PLAN




TYPICAL SECTION




STRAIGHT BRIDGE


STRAIGHT BRIDGE



PLAN




TYPICAL SECTION




SKewed BRIDGE


SKewed BRIDGE



PLAN




TYPICAL SECTION




TYPICAL PAD DETAIL
INTERIOR BEAM

TYPICAL PAD DETAIL
EXTERIOR BEAM

* Unless otherwise noted on Beam Sheets.



PLAN



TYPICAL SECTION

COMPOSITE PAD
For Type V & VI Beams

GENERAL NOTES

Neoprene in all Bearing Pads shall have a Grade 50 durometer hardness.



Steel plates in composite pads shall conform to A.S.T.M. A-36 or A-245 Grade C or D, or A-570 Grade C or SAE 1010, SAE 1020. Variations in pad dimensions will be allowed provided revised pads will meet the current specifications and are approved by the Engineer.

Bearing seat shall be finished parallel to the bottom of Beam.

Steel Bearing Plates, Anchor Bolts, Nuts and Washers shall be hot dip galvanized in accordance with A.S.T.M. Specification A-123. Payment for steel bearing plate assemblies shall be included in the Contract Unit Price for Prestressed Beams or Structural Steel. For location and details of Bearing Plates see Beam sheets.


STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION STRUCTURES				
COMPOSITE NEOPRENE BEARING PADS				
REVISED		ROAD NO.	COUNTY	PROJECT NO.
Date	Description			
		Drawn by	W.E.H.	9-76
		Checked by	DEK	9-76
		Quantity by		
		Checked by		
		Supervised by	S.H.N.	1 of 1
		Approved by		12037

1. The cost of all materials in Parapet shall be included in Concrete (Superstructure) and Reinforcing Steel (Superstructure) .
2. Aluminum Rail shall be paid for per linear foot and shall be measured along the centerline of the top surface of the Rail. Payment includes Anchor Bolts, Nuts, Resilient Pads, all incidental materials and labor required to complete the installation .
3. For details of Rail Alignment and Post Spacing see Superstructure and End/Bent Details


[illegible]

RAIL SPLICE AND EXPANSION JOINT


NOTE "A"-Rough Cut Ends and Edges of Aluminum Rods shall be Ground or Filed Smooth to Remove All Sharp Edges, Nicks or Burrs that would be injurious to the Human Touch.



VIEW C-G



RAIL CLAMP BAR



SECTION F - F

— Polychloroprene Compression Seats used in $\frac{3}{4}$ " Open Joints shall be 1" wide minimum. All contacting surfaces between the Compression Seal and the Concrete shall be thoroughly coated with a lubricating adhesive. See 1975 Supplement.

SPECIFICATIONS FOR BRIDGE RAIL

POST: Aluminum A.S.T.M B221, alloy 6061-T6 or alloy 6351-T5
with welding using filler wire 4043.

RAIL & RAIL SPLICE: Aluminum; A.S.T.M B221, alloy 6061-T6 or alloy 6351-T5.

RAIL CLAMPBAR: Aluminum; A.S.T.M B221, alloy 6061-T6 or alloy 6351-T5.

ANCHOR BOLTS: Anchor Bolts shall be in accordance with A.S.T.M. A-36 or A-307. Anchor Bolts, nuts and washers shall be hot-dip galvanized in accordance with A.S.T.M. Designation A-153.

RAIL END CAP: A.S.T.M. B 26 sand cast aluminum alloy, 5670A-F
(Alum Assoc. alloy designation A-356-F).


RAIL INSTALLATION. Rail Post shall be normal to Profile Grade. Posts shall be seated on $\frac{1}{2}$ " thick resilient pads in accordance with Article 932-2.1. The dimension shall be the same as the post base. Rail expansion joints shall occur in the panel between post on either side of Bridge expansion joints. Rail expansion joints shall be similar to rail splices with provision for movement equal to 1.5 times the bridge joint opening.

SHOP DRAWINGS: Complete details and description of materials of the proposed bridge rail shall be submitted by the contractor for the Engineers' approval prior to fabrication.


STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION
STRUCTURES

ALUMINUM HANDRAIL (SIDEWALK)


REVISIONS		ISSUE NO.	COUNTY	PROJECT NO.
Date	Description	Initials	Date	APPROVED BY
1-4-79	Change curb from 9' to 1-5'			
1-21-79	Change note to "Till Space And Expansion Joint"	W.L.D./A.F.E.	9/76	
3-14-79	Change Space Bar Dept. & Note "A"	R.D.S.	9/76	
8-13-81	Change Space Bar Division			
9-7-82	Rev. Section C-E			
	Checked by	Drawing No.		Index No.
	Supervised by	1 of 1		12087




PLAN




ELEVATION




PLAN OF WING FOR SLAB TYPE SUPERSTRUCTURE




ELEVATION OF WING FOR SLAB TYPE SUPERSTRUCTURE



PLAN OF WING FOR SLAB AND GIRDER TYPE SUPERSTRUCTURE



ELEVATION OF WING FOR SLAB AND GIRDER TYPE SUPERSTRUCTURE




VIEW A-A

NOTES

The Name and Bridge Number to be placed on the Barrier shall be seen on the drivers right when approaching Bridge. The Date to be placed on the drivers left when approaching Bridge. The Date shall be the Year the Bridge is constructed

Block Plastic Letters and Figures 3" in height as approved by the Engineer may be used in lieu of Letters and Figures formed by $\frac{3}{8}$ " V Grooves. "V" Grooves shall be formed by preformed Letters and Figures.




ANCHOR BOLT DETAIL

NOTE: Cost of Anchor Bolts to be included in the Contract Unit Price for Guardrail

**BENDING DIAGRAMS
TABLE OF VARIABLE DIMENSIONS**


RDWY X-SLOPE	DIM "A" (Bars V1 & V3)	DIM "B" (Bars V2 & V4)
0.00 to 0.02%	0"	0"
0.02 < to 0.06%	$\frac{1}{2}$ "	$\frac{1}{2}$ "
0.06 < to 0.10%	1"	1"



BAR 4V1 BAR 4V2 BAR 4V3 BAR 4V4

NOTE: Bars #12-#14 are for low-side pour. NOTE: Bars #13-#14 are for high-side pour.
 1. Adjust length of bars #4's as required for slab thickness. (Dimensions shown are based on a 7" slab, see Superstructure Drawings. For thicker slabs adjust the 1'-8" vertical and the 2'-0" horizontal dimensions as follows. Add the amount that the slab depth exceeds 7" to the 1'-8" vertical dimension and add 1/4 of its excess to the 1'-2" horizontal dimension.
 Example: 12" Slab
 Excess = 12" - 7" = 5"
 Vertical Dimension = $1'-8" + \frac{5"}{4} = 2'-1"$
 Horizontal Dimension = $1'-2" + \frac{5"}{4} \times .4 = 1'-4"$


CLL
 REF:
 for S



TYPICAL BARRIER QUANTITIES

NOTE: Quantities based on 7" slab and .02' ft. Roadway Cross Slope.
CLASS II CONCRETE: 0.07594 C.Y. per linear ft. of Barrier
REINFORCING STEEL = 15.26 lbs. per linear ft. of Barrier
for slab, 14.55 lbs. per linear ft. of Barrier for Wall.
NOTE: All bar dimensions are out-to-out

NOTE: See sheet No 1 of 5
Index No. 13356 for Retaining
Wall Barrier Details.



TYPICAL SECTION THRU BARRIER

NOTE #1: Place normal bottom slab longitudinal Reinforcing Steel at each position as shown above to facilitate tying anchor bars in Concrete Handrail Barrier. Do not add Reinforcing Steel for tie purposes. For Precast Slab Units place Bars 4V on top of the prestressed strands and tie.

SECTION C-C

NOTE: When using fixed forms to construct the barrier the vertical face of the gutter-side shall be filled (3" above the roadway surface) either by forming or by filling the bottom 3" height of the opening for a width of 3' minimum, as shown above with mortar in accordance with Article 400-15.1. When barriers are slip-formed the opening shall be constructed for the limits described above for forming.

REINFORCING STEEL NOTES:

All Reinforcing Steel in Barrier shall be No. 4's. Bars 4P, 4R, & 4V shall be spaced at 9" c/c. At all open joints all reinforcing steel shall have 2" minimum cover. At all construction joints Bars 4S may be either continuous or spliced. All splices in Bars 4S shall be 1'-4" minimum.

GENERAL NOTES

CONCRETE: Class II Concrete shall be used in Barrier.
REINFORCING STEEL: Reinforcing Steel shall be Grade 60.
PAYMENT: Barrier shall be paid for per linear foot, which shall include all Concrete and Reinforcing Steel.
Barrier shall be measured along the centerline of the top surface of the Barrier.
CYLINDER STRENGTH: The Cylinder Strength of the Concrete shall be 3,400 p.s.i. minimum at 28 days.
MARKERS: Markers recording the Elevation shall be placed on top of the Barrier at End Bents On Bridges longer than 100 ft, one marker shall be placed at each end of Bridge. On Bridges less than 100 ft long, one marker shall be placed at one end of the Bridge only. Markers are to be furnished by the Department Of Transportation and installed by the Contractor. The Cost of installing the Markers shall be included in the Contract Unit Price for Concrete Barrier.
SLIP-FORMING: At the option of the Contractor, Barrier walls may be constructed by slip-forming subject to the following: the width may be increased a maximum of 2 inches provided that the front face of the concrete barrier intrudes on the clear roadway width no more than $\frac{1}{8}$ " and that any additional materials required are at the expense of the Contractor. The shape of the Barrier on the Roadway Side shall not be altered.
SUPERELEVATED BRIDGES: At the Option of the Contractor, Honarail Barriers and End Bent wingwalls on one side of Super-elevated Bridges, may be constructed perpendicular to the roadway surface. The cost of modifications shall be at the Contractors expense.
ANCHOR BOLTS: Anchor Bolts, Nuts, and Washers shall be hot dip galvanized in accordance with A.S.T.M. A-123.



HOLE FOR INCIDENTAL SIGNING

NOTE: Holes and grooves shall be placed on barrier type handrails of divided and undivided bridges as shown in the plans for designated type "C" single column, informational, guide, regulatory and warning sign locations (see signing plans) and at approximately 500' intervals along the right handrails of bridges between designated locations for future signs as directed by the Engineer. The cost of the signs holes and grooves shall be included in the contract unit price for Contract Handrail/Barrier. If Signing Plans are not available the Project Engineer should secure necessary information from the District Maintenance or Traffic Operations Office.


		STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION															
		STRUCTURES															
CONCRETE HANDRAIL BARRIER																	
REVISIONS		PG&I NO.	COUNTY														
Date	Description		PROJECT NO.														
		<table><tr><td>Number</td><td>Date</td></tr><tr><td>Designed by</td><td>1-2-52</td></tr><tr><td>Checked by</td><td>10-3-52</td></tr><tr><td>Drawn by</td><td></td></tr><tr><td>Checked by</td><td></td></tr><tr><td>Reviewed by</td><td></td></tr><tr><td>Supervised by</td><td></td></tr></table>	Number	Date	Designed by	1-2-52	Checked by	10-3-52	Drawn by		Checked by		Reviewed by		Supervised by		APPROVED BY
Number	Date																
Designed by	1-2-52																
Checked by	10-3-52																
Drawn by																	
Checked by																	
Reviewed by																	
Supervised by																	
		Design District Engineer, Structures															
		Drawing No.	Index No.														
		1 of 1	13857														

NOTE: For Barrier Transition at End Bents see Details below, this sheet.
* NOTE: See Superstructure Drawing for actual Dimensions.




NOTE: There shall be a Min. Open Joint at all Substructure Supports.

NOTE: Concrete Wing Post shall be paid for at the Contract Unit Price for Concrete (Substructure) and Reinforcing Steel (Substructure).

NOTE: Rail shall be continuous over a minimum of 3 Posts before splicing.



NOTE: All contacting surfaces between the Compression Seal and the concrete shall be thoroughly coated with a lubricating adhesive.



QUANTITIES Class II Concrete - 0.07594 Cu Yds. per linear ft. of Barrier (Based on Roadway Cross Slope of .02/ft.).
REINFORCING STEEL - 15.782 lbs. per linear ft. of Barrier.



GENERAL NOTES

CONCRETE: Class II Concrete shall be used in Barrier.
REINFORCING STEEL: Reinforcing Steel shall be Grade 60.
PAYMENT: Barrier shall be paid for per linear foot, which shall include all Rail, Concrete and Reinforcing Steel. Barrier shall be measured along the centerline of the top surface of the Barrier.
CYLINDER STRENGTH: The Cylinder Strength of the Concrete shall be 3400 psi, minimum, of 28 days.
MARKERS: Markers recording the Elevation shall be placed on top of the Barrier at End Bents. On Bridges longer than 100 ft., one marker shall be placed at each end of the Bridge. On Bridges less than 100 ft. long, one marker shall be placed at one end of the Bridge only. Markers are to be furnished by the Department of Transportation and installed by the Contractor. The Cost of installing the Markers shall be included in the Contract Unit Price for Concrete Barrier.
ANCHOR BOLTS: Anchor Bolts, Nuts and Washers shall be hot dip galvanized in accordance with A.S.T.M. A-123.


SPECIFICATIONS FOR BRIDGE RAIL

POST: Fabricated wrought aluminum A.S.T.M. B221, alloy 6061-T6 or alloy 6351-T5 with welding using filler wire 4043.
RAIL & RAIL SPLICE: Aluminum; A.S.T.M. B221, alloy 6061-T6 or alloy 6351-T5.
RAIL CLAMP BAR: Aluminum; A.S.T.M. B221, alloy 6061-T6 or alloy 6351-T5.
ANCHOR BOLTS: Anchor Bolts shall be in accordance with A.S.T.M. A-36 or A-307. Anchor Bolts, nuts and washers shall be hot dip galvanized in accordance with A.S.T.M. Designation A-153.
RAIL END CAP: A.S.T.M. B 26 sand cast aluminum alloy, S.G. 70A-F (Alum. Assoc. alloy designation A-356-F).
RAIL INSTALLATION: Rail Post shall be normal to Profile Grade. Posts shall be seated on 1/2" thick resilient pads in accordance with Article 932-2.1. The dimension shall be the same as the post base. Rail expansion joints shall occur in the panel between posts on either side of bridge expansion joints. Rail expansion joints shall be similar to rail splices with provision for movement equal to 1/2" times the bridge joint opening.
SH: DRAWINGS: Complete details and description of materials of the proposed bridge rail shall be submitted by the contractor for the Engineer's approval prior to fabrication.
NOTE: The Longitudinal Reinforcing Steel shown in Slab of Typical Section Thru Barrier shall be normal Longitudinal Slab Steel spaced as shown, do not add Reinforcing Steel for its purposes.



NOTE: At the option of the Contractor, Barrier Walls may be constructed by slip-forming subject to the following: the width may be increased a maximum of 2 inches provided that the front face of the base of each barrier infringes on the clear roadway width no more than 1/2" and that any additional materials required are at the expense of the Contractor. The shape of the Barrier on the Roadway side shall not be altered.




PLAN OF WING FOR SLAB TYPE SUPERSTRUCTURE
NOTE: For Reinforcing Steel in Transition Area on Slab Type Superstructure adjust and field bend as required for minimum cover, 3"-9".





ELEVATION OF WING FOR SLAB TYPE SUPERSTRUCTURE




PLAN OF WING FOR SLAB AND GIRDER TYPE SUPERSTRUCTURE
NOTE: For Reinforcing Steel in Transition Area on Slab Type Superstructure adjust and field bend as required for minimum cover, 3"-9".




ELEVATION OF WING FOR SLAB AND GIRDER TYPE SUPERSTRUCTURE



PLAN OF WING FOR SLAB AND GIRDER TYPE SUPERSTRUCTURE
NOTE: For Reinforcing Steel in Transition Area on Slab Type Superstructure adjust and field bend as required for minimum cover, 3"-9".



ELEVATION OF WING FOR SLAB AND GIRDER TYPE SUPERSTRUCTURE



SECTION THRU RECESSED "V" GROOVE TO FORM INSCRIBED LETTERS AND FIGURES

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION STRUCTURES			
SIDEWALK BARRIER			
DESIGN NO.	COUNTY	PROJECT NO.	
9302	FLA.		
Drawn by: WHD	Date: 5-74	APPROVED BY: T. O'Connell	
Checked by: JLM	Date: 5-74		
Quantity by:		Drawing No. 1 of 1	
Checked by:		Scale: 11,460	
Approved by:			



DETAILS OF GUARDRAIL ATTACHMENT AT WING POSTS
NOTE: For Guardrail Shoe See Standard Drawing in Roadway Plans

NOTE: For Barrier Transition at End Bents see Details below. This sheet shows details for actual dimensions.

NOTE: There shall be a 1/2" Min. Open Joint at all Substructure Supports.


NOTE: Concrete Wing post shall be paid for at the Contract Unit Price for Concrete (Substructure) and Reinforcing Steel (Substructure).

NOTE: Rail shall be continuous over a minimum of 3 posts before splicing.



NOTE: All contacting surfaces between the Compression Seal and the concrete shall be thoroughly coated with a lubricating adhesive.

Provide extra 4" of Seal Cut away all but top of Shell to provide end flap. Bend down and seal with a lubricating adhesive.




SECTION F-F

REINFORCING STEEL NOTES

All Reinforcing Steel in Barrier shall be No. 4's. Bars 4R, 4T & 4U to be spaced at 8" O.C. At all open joints, Bars 4R, 4T, 4U and the ends of bars 4S shall have 2" Min. cover. At all construction joints, bars 4S may be either continuous or spliced. All splices in bars 4S shall be 1'-4" minimum.



VIEW C-C




QUANTITIES: Class II Concrete = 0.07594 Cu Yds. per linear ft. of Barrier (Based on Roadway Cross Slope of .02/ft.)
REINFORCING STEEL = 15.782 lbs. per linear ft. of Barrier.

GENERAL NOTES


CONCRETE: Class II Concrete shall be used in Barrier.
REINFORCING STEEL: Reinforcing Steel shall be Grade 60.
PAYMENT: Barrier shall be paid for per linear foot, which shall include all Rail, Concrete and Reinforcing Steel. Barrier shall be measured along the centerline of the top surface of the Barrier.
CYLINDER STRENGTH: The Cylinder Strength of the Concrete shall be 3,400 p.s.i. minimum at 28 days.
MARKERS: Markers recording the Elevation shall be placed on top of the barrier at End Bents. On Bridges longer than 100 ft. one marker shall be placed at each end of the Bridge. On Bridges less than 100 ft. long, one marker shall be placed at one end of the Bridge only. Markers are to be furnished by the Department of Transportation and installed by the Contractor. The Cost of installing the markers shall be included in the Contract Unit Price for Concrete Barrier.

SPECIFICATIONS FOR BRIDGE RAIL


POST: Fabricated wrought aluminum A.S.T.M. B221, alloy 6061-T6 or alloy 6351-T3 with welding using filler wire 4043.
RAIL: 8 RAIL PLICE: Aluminum; A.S.T.M. B221, alloy 6061-T6 or alloy 6351-T3.
RAIL CLAMP BAR: Aluminum; A.S.T.M. B221, alloy 6061-T6 or alloy 6351-T3.
ANCHOR BOLTS: Anchor Bolts shall be in accordance with A.S.T.M. A-36 or A-307 Anchor Bolts, nuts and washers shall be hot-dip galvanized in accordance with A.S.T.M. Designation A-153.
RAIL END CAP: A.S.T.M. B 26 and cast aluminum alloy, S G 70A-F140m. Assoc. alloy designation A-356-F1.
RAIL INSTALLATION: Rail Post shall be normal to Profile Grade. Posts shall be seated on 1/2" thick resilient pads in accordance with Article 532-2.1. The dimension shall be the same as the post base. Rail expansion joints shall occur in the panel between posts on either side of Bridge expansion joints. Rail expansion joints shall be similar to rail splices with provision for movement equal to 1.5 times the bridge joint opening.
SHOP DRAWINGS: Complete details and description of materials of the proposed bridge rail shall be submitted by the contractor for the Engineers approval prior to fabrication.




SECTION E-E




RAIL END CAP




SECTION D-D




RAIL SPLICE



RAIL CLAMP BAR




SECTION THRU RAIL




PLAN OF WING FOR SLAB TYPE SUPERSTRUCTURE

NOTE: For Reinforcing Steel in Transition Area on Slab Type Superstructure adjust and field bend as required for minimum cover.


ELEVATION OF WING FOR SLAB TYPE SUPERSTRUCTURE



DETAILS OF GUARDRAIL ATTACHMENT AT WING POSTS




PLAN OF WING FOR SLAB AND GIRDER TYPE SUPERSTRUCTURE




ELEVATION OF WING FOR SLAB AND GIRDER TYPE SUPERSTRUCTURE

NOTE: For Guardrail Shoe see Road Design Standards Booklet.



TYPICAL SECTION THRU BARRIER



SECTION THRU RECESSED 'V' GROOVE TO FORM INSCRIBED LETTERS AND FIGURES





Black Plastic Letters and Figures 3" in height as approved by the Engineer may be used in lieu of Letters and Figures formed by 'V' Grooves. 'V' Grooves shall be formed by preformed Letters and Figures.

The Name and Bridge Number to be placed on the Barrier shall be seen on the drivers right when approaching Bridge. The date to be placed on the drivers left when approaching Bridge. The date shall be the Year the Bridge is constructed.

Note: Place bottom slab longitudinal Reinforcing Steel at each position as shown to facilitate tying anchor bars in Concrete Handrail Barrier.

NOTE: The Longitudinal Reinforcing Steel shown in the slab of the Typical Section Thru Barrier shall be normal Longitudinal Slab Steel spaced as shown, do not add Reinforcing Steel for tie purposes.



STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION STRUCTURES			
BICYCLE BARRIER			
ROAD NO.	COUNTY	PROJECT NO.	
DESIGNED BY	CAC	CHECKED BY	DER
DATE	1-79	DATE	1-79
APPROVED BY		F. O. [Signature]	
QUANTITY	101	DATE	1-79
REVISIONS	SHN		



NOTE: Piles shall be marked at pick up points to indicate proper points for attaching handling lines.

8-#8 S.R. - $A_s = 0.109 \text{ in}^2$ - 250 K @ 18,900 Eo. Spaced $2\frac{1}{2}$ Ctrs.
4-#4 L.R.S. - $A_s = 0.153 \text{ in}^2$ - 270 K @ 30,100 Eo. Spaced 5 Ctrs.

SECTION A-A



EPOXY BONDED SPLICE

16-#8 S.R. - $A_s = 0.109 \text{ in}^2$ - 250 K @ 18,900 Eo. Spaced $2\frac{1}{2}$ Ctrs.
12-#8 S.R. - $A_s = 0.144 \text{ in}^2$ - 250 K @ 25,200 Eo. Spaced $3\frac{1}{2}$ Ctrs.
8-0.60" S.R. - $A_s = 0.215 \text{ in}^2$ - 270 K @ 41,000 Eo. Spaced $5\frac{1}{2}$ Ctrs.
16-#4 L.R.S. - $A_s = 0.085 \text{ in}^2$ - 270 K @ 18,700 Eo. Spaced $2\frac{1}{2}$ Ctrs.
12-#4 L.R.S. - $A_s = 0.118 \text{ in}^2$ - 270 K @ 22,600 Eo. Spaced $3\frac{1}{2}$ Ctrs.
8-#4 Special L.R.S. - $A_s = 0.167 \text{ in}^2$ - 270 K @ 32,800 Eo. Spaced $5\frac{1}{2}$ Ctrs.

SECTION A-A

GENERAL NOTES

SPIRAL TIES Each wrap of spiral shall be tied to at least two corner strands.

MATERIAL FOR SPIRAL TIES: Spiral may be manufactured from stock meeting requirements of any grade of reinforcing steel or hard drawn steel.

PILE CUTOFFS: In cutting off Concrete Piles an abrasive saw shall be used to score the Concrete at cut off elevation to the approximate depth of Reinforcing Steel.

CONCRETE STRENGTH: For Class III Concrete the Cylinder Strength shall be 3,000 psi minimum at 28 days and 4,000 psi minimum at transfer of the Prestressing Force.

WEBS: Webs of Wide Flange sections shall be in a vertical position when Composite Pile is cast.


NOTE: All Reinforcing Steel shall be Grade #40 or #60.

APPROVAL: Prior Approval in Writing By the Engineer is Required for Reinforced Concrete Build-Up in Excess of 2'-0". This will not be approved for piles in a coastal environment.

DUNNAGE: Place Dunnage under pick up points shown for double pick up. Where Pile Length exceeds that requiring double point pick up, place dunnage at pickup points called for in Triple Point Pick up.

OCTAGONAL PILES: Prestressed Octagonal Piles of equivalent strength may be substituted for square piles. Details of Pile shall be submitted to the Engineer for approval.

SPIRAL SPLICES: One turn required for spiral splices.




NOMENCLATURE

S.R. = Stress Relieved Strand
L.R.S. = Low Relaxation Strand

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION
STRUCTURES

12", 14" AND 18" PRESTRESSED CONCRETE PILES

REVISIONS	ROAD NO.	COUNTY	PROJECT NO.
1. 12-18-75 Revised 2. 12-22-75 Change Center 3. 12-22-75 Change Center 4. 12-22-75 Change Center 5. 12-22-75 Change Center 6. 12-22-75 Change Center 7. 12-22-75 Change Center 8. 12-22-75 Change Center 9. 12-22-75 Change Center 10. 12-22-75 Change Center	Desig. by S.A.B.	5-75	5-75
Checked by L.A.L.	5-75		
Drawn by			
Supervised by			



Bar Size	180° HOOKS		90° HOOKS	
	A or G	J	A or G	
#3	5	3	6	
#4	6	4	8	
#5	7	5	10	
#6	8	6	1-0	
#7	10	7	1-2	
#8	11	8	1-4	
#9	1-3	11 $\frac{3}{4}$	1-7	
#10	1-5	1-1 $\frac{1}{2}$	1-10	
#11	1-7	1-2 $\frac{3}{4}$	2-0	
#14	2-3	1-9 $\frac{3}{4}$	2-7	
#18	3-0	2-4 $\frac{1}{2}$	3-5	
STYLE	I		3	



STYLE 6 - NO HOOK
Hook Styles Detailed on this Sheet are for illustration
Only Actual Hook Style for any Particular Bar will be
Shown Under A or G Heading on Reinforcing Bar List
Sheet.
All Dimensions are Out To Out.

STANDARD BAR BENDING DETAILS

NOTE: For Bar Dimensions See Reinforcing Bar List Sheet

Figure 10-1: Details of Bridge Deck Construction. The figure consists of four cross-sectional diagrams of a bridge deck, labeled SECTION A-A, SECTION B-B, SECTION C-C, and SECTION D-D. Each diagram shows the internal structure of the bridge deck, including the bent, approach slab, construction joint, cast-in-place slab, precast panels, 1/2 inch thickness bearing material, and seal joints. A note at the bottom left states: "NOTE: Reinforcing Steel Not Shown for Clarity (Typ.)".

- SECTION A-A (AT SKIRMED BENT):** Shows a bent with an approach slab, construction joint, cast-in-place slab, precast panels, 1/2 inch thickness bearing material, and seal joints.
- SECTION B-B (AT SKIRMED BENT):** Shows a bent with a construction joint, cast-in-place slab, precast panels, 1/2 inch thickness bearing material, and seal joints.
- SECTION C-C (BENT PERPENDICULAR TO ROADWAY):** Shows a bent with a construction joint, cast-in-place slab, precast panels, 1/2 inch thickness bearing material, and seal joints.
- SECTION D-D (END BENT PERPENDICULAR TO ROADWAY):** Shows an end bent with a construction joint, cast-in-place slab, precast panels, 1/2 inch thickness bearing material, and seal joints.

NOTE: Reinforcing Steel Not Shown for Clarity (Typ.)

Figure 1 consists of three cross-sectional diagrams of beam types. Type II Beam shows a precast panel with a 1 1/2 inch gap, a 3 inch wide band, and a 1 1/2 inch gap, with a 1 1/2 inch gap between the panel and the beam. Type III Beam shows a precast panel with a 1 1/2 inch gap, a 3 inch wide band, and a 1 1/2 inch gap, with a 1 1/2 inch gap between the panel and the beam. Type III Beam shows a precast panel with a 1 1/2 inch gap, a 3 inch wide band, and a 1 1/2 inch gap, with a 1 1/2 inch gap between the panel and the beam.


Chemter Edges for Great Seal

Precast Panels

Casting Surface

Tight Fit

SECTION E-E




— PROFILE — DECK AND SUPPORT

Where beam center differs from that shown in the Plans, adjust thickness of bearing material. Maximum thickness of fibergord to be 1/2". When necessary to achieve a thickness greater than 1/2" fibergord may be set on an approved groud pad so that the Deck thickness conforms to the Plan dimension. Transitions in bearing thickness shall be accomplished by using layers of 55" roofing felt, fibergord and groud pads so placed as to control the bottom of the Panel Profile so that it is Parallel to the finished grade surface. The Panel Deck Thickness is Minimum. Adhesive is applied to the bottom of the Panel Profile and is sealed off contact surface between Precast, Prestressed Panels and Supporting Units. [See Enlarged Schematic]

- ## GENERAL NOTES
- 1- When Precast Prestressed Panels are Used on a Bridge Structure at the Option of the Contractor, it shall be the Sole Responsibility of the Contractor to Increase the Finished Grade Elevations and to make all Adjustments Required by this Increase.
 - 2- Contractor shall Instruct the Producers of Concrete Beams to Provide a 3" Wide Smooth Finish at the Outside Edges of the Top Flange for Precast Panel Bearing and Grout Seal.
 - 3- When Precast Prestressed Panels are Substituted, Payment shall be made at the Contract Unit Prices for Concrete and Steel. The Quantities to be Paid for will be those Quantities which would be Paid for if Conventional Construction was Utilized. The Contract Unit Price for Concrete shall Include the Cost of All Bearing Materials.
 - 4- Precast Prestressed Panels shall not be used on Steel Beams.
 - 5- Precast Prestressed Panels shall not be used under Barrier Walls with Reinforcing Steel Projecting Into The Deck Slab.
 - 6- Before Any Precast Prestressed Panels are Placed in Position in Any Span, the Contractor shall Establish the Finished Grade Elevations and make the Required Camber Adjustments in a minimum of TWO Spans Ahead of the Span to be Set.
 - 7- The Erected Precast Panels shall Bear Uniformly on Continuous Layers of an Approved Material Such as Macfie, Felt, or Board and a Grout Inlet will Provide a Mortar Tight Uniform Bearing. The Bearing Material Shall be Placed Along the Outer Edges of Each Beam and the Inside Edge of the End Diaphragms at Skewed Bents.
 - 8- After the Precast Prestressed Panels have been set to Proper Grade on Bearing Material, The remaining Space Between the end of the Panels and the Bearing Material (1/4" Min. Width) shall be filled with cement Grout. The Grout shall consist of one part portland cement to two parts clean sand with enough water to make a thick paste mixture. The Grout paste shall be placed by Trowel on Moisture Saturated Surfaces and Allowed to Set Before Placing Cast-In-Place Concrete. The Grout shall be Placed in a manner which will produce a leak-proof seal.
 - 9- Precast Panels in their Final Position shall be Mortar Tight at Both the Outer Edges and the Mating Surfaces. The Top Surface of the Precast Panels Must be Free of Any Foreign Material to Insure Full Bond with the Cast-In-Place Concrete. Immediately Prior to Placing the Cast-In-Place Concrete the Precast Panels shall be Saturated with Fresh Water.
 - 10- End Diaphragms Shown in Sections are not Dimensioned in Width, See Bridge Plan for Sizes. Add One (1) inch to Width of Diaphragms at Skewed Bents to Provide Bearing for Precast Panels. Reinforcing Steel in End Diaphragms will not Change.
 - 11- The Bearing Width of Type III and Type VII Precast Prestressed Beams shall be $2\frac{1}{2}$ " (1-1/2" + .0"1 Post the End of Transverse Reinforcing Steel in the Top Flange of the Beam.
 - 12- The Transverse Spacing of The Mechanical Interlock Reinforcing shall cover the Longitudinal Distribution Steel at the Poured in Place Concrete and the Transverse Spacing shall be Constant Thru Out Spans of Equal Beam Spacing.


TABLE "A"	
PANEL NO.	REMARKS
① ②	Fabricators Standard Width Panel
③	Fillet Panel: $\geq 0^{\circ}$ Minimum Width
④ ⑤	Fillet: Proport. of Equal Width Both $\geq 0^{\circ}$ or $\geq 10^{\circ}$
⑥ ⑦	Fillet Panels: One $\geq 0^{\circ}$ (Min. Width) and Other Panel Width as Required.
⑧ ⑨ ⑩ ⑪	Fillet Panel $\geq 10^{\circ}$ on Request of $\geq 2^{\circ} - 0^{\circ}$
⑫ ⑬	End Panels of Stowed Bents Not Cut from Rectangular Panel
⑭ ⑮	Panel: Stowed Edge $\geq 10^{\circ}$ Support
⑯	Permissible Only Where Required by Extreme Side Angle of Bent.

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION			
STRUCTURES			
PRECAST PANELS FOR COMPOSITE DECK WITH 1 1/2" CLEARANCE OF BOTTOM MAT OF STEEL			
REVISIONS		ROAD NO.	COUNTY
PROJECT NO.			
Date	Description		
		Names	DATES
		Designed by CK	9-82
		Checked by AJH	9-82
		Quotations by	
		Checked by	
		Supervised by AJH	
		APPROVED BY	
		Drawing No. 1 of 3	Issue No. 12641



DETAIL-TRAPEZOIDAL SHAPED PANELS AT SKEWED BENT
(SAW CUT FROM PRECAST PRESTRESSED RECTANGULAR PANEL)

DETAIL-PRECAST PRESTRESSED PANELS-RECTANGULAR



MINIMUM COVERAGE DETAILS

DESIGN TABLE "8"-3 1/2" FLAT PANELS					
CLEAR SPAN	DESIGN DECK THICKNESS	STRANDS	STRAND SPACING	STRANDS	STRAND SPACING
MINIMUM LENGTH UP TO AND INCLUDING	4'0"	7"	250K	9.5"	13"
	5'0"			9"	12"
	6'0"			8"	11"
	7'0"			7"	10"
	8'0"			6"	9"
	9'0"			5.5"	8"
	10'0"			5"	7"
	11'0"			4.5"	6"
	12'0"			4"	5"

Prestressing Pull for 3/8" # 250K Strands = 14,000 lbs. Each.
Prestressing Pull for 7/16" # 250K Strands = 18,900 lbs. Each.

GENERAL NOTES FOR PRECAST PANELS


- Shop Drawings shall be Submitted, Showing Complete Shop Details for the Precast Prestressed Panels. Details shall include Mechanical Interlock Reinforcing, Lifting Devices, Panel Dimensions, Clearances, Reinforcing Steel, Prestress Strand Size, Type and Pull, Material Specifications and a Detensioning Schedule that will be Symmetrical about the Vertical Centerline of the Panel. Method of Placement and Method of Consolidation of Concrete Around Mechanical Interlock Reinforcing.
- MATERIALS:**
 - Concrete shall be Class III ($f_c = 5,000$ p.s.i.) No Prestressing Strand shall be Released Until the Concrete has Reached a Minimum Compressive Strength of 4,000 p.s.i. Concrete shall meet the Requirements of Standard Specification Section 345.
 - Prestressing Strands shall be 3/8" or 7/16" # 250K Seven Wire Stress Relieved Strands that Conform to the Requirements of ASTM A 406. See Table.
 - All Other Metal Reinforcement shall Conform to the Requirements of Section 931. All Reinforcing Steel shall be Grade 40 or Grade 60.
 - Coarse Aggregate for Precast Panel Concrete shall be Grade 89, 7 and 57 and shall meet all other Requirements of Section 901.
 - The Prestressing Strands shall be Supported as Required by Either Reinforcing Steel Bar Supports (Stainless Steel - Class E) or Mortar Blocks, in Accordance with Section 415, Paragraph 415-5.10 and 415-5.13.
- Precast Prestressed Panels shall be Constructed Meeting all Applicable Requirements of Section 400 and Section 450.
- Mechanical Interlock Reinforcing of 0.60 Square Inches of Reinforcing Steel Per Ten (10) Sq. Ft. of Panel Surface shall be Provided. Alternate Designs will be Permitted, Subject to the Approval of the Engineer. Shop Drawings shall show Location of all Mechanical Interlock Reinforcing.
- Lifting Hooks or Devices will be Permitted But will be the Sole Responsibility of the Contractor. Any Hook or Device that Pulls Out of the Panel During Handling will be Cause for Rejection of the Panel. Lifting Devices shall not be Attached to or Hooked Under the Panel Reinforcing Steel or Prestressing Strands. Lifting Devices shall be shown on the Shop Drawings for the Approval of the Engineer.
- Prestressing Strands shall be Symmetrical and Uniformly Spaced about the Vertical Center Line of the Rectangular Panels.
- The Top Surface of the Precast Panels shall be Roughened at the Approximate Time of Initial Set by Brushing, Brooming, Burlap Drag or Other Approved Method. This Surface shall be Kept Free of all Contaminants Such as Oil, (Particularly Bond-Breaking Substances).
- Membrane Curing Compound Will Not be Used on the Top of the Precast Panels.
- Precast Prestressed Concrete Panels shall be Produced within the Following Tolerances:
Depth (Thickness of Panels) $\pm \frac{1}{4}"$ to $-\frac{1}{8}"$; Length of Panel $\pm 1"$
Position of Strands $\pm \frac{1}{4}"$, $-0"$ Vertically
 $\pm \frac{1}{4}"$ Horizontally
* Measured from Bottom of Panel.
- Precast Panel Lengths May be Set and Achieved by Using Headers in the Form or by Sawing to Length.
- Precast Panels shall be Properly Handled and Stored to Prevent Breakage. Any Damage Due to Handling and Shipping Will Be Cause for Rejection.
- Saw Cut Edges With Exposed Distribution Steel Must be Placed in Bearing On Top of the End Diaphragm in the Span. At No Other Place Within the Span Will a Saw Cut Edge With Exposed Distribution Steel Be Permitted.
- To Allow for all Tolerances in Fabricating the Precast Panels and Placing the Reinforcing Steel in the Cast-In-Place Portion, This 7" Design Plan Deck will be Poured 7 1/2" Thick in all cases in the field at No Additional Increase in Contract Price.
- To Allow for all Tolerances in Fabricating the Precast Panels and Placing the Reinforcing Steel in the Cast-In-Place Portion, This 7 1/2" Design Plan Deck will be Poured 8 1/2" Thick in all cases in the field at No Additional Increase in Contract Price.

FHWA APPROVED: 10-2-80



FLAT PRECAST PANELS
STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION
STRUCTURES
PRECAST PANELS FOR 7" AND 7 1/2" COMPOSITE DECK
1/4" CLEAR AT BOTTOM - 1/4" CLEAR AT TOP

REVISIONS		ROAD NO.	COUNTY	PROJECT NO.
Date	Description			
8-19	Added Tolerances & Revised Design			
8-20	Design Table Expanded			
Designed by	CK	5-78		
Checked by	CWB	6-78		
Quantity by				
Checked by				
Supervised by	AJH			
Drawing No.	2 of 3	Index No.	12641	

NOTE: Prestressing Strands Shown as Heavy Dashed Line in Plan and Side View for Clarity
Prestressing Strands May Be Placed Under Ribs Only in A Symmetrical Pattern About The Center Line.



DETAIL-TRAPEZOIDAL SHAPED PANELS AT SKEWED BENT
(SAW CUT FROM PRECAST PRESTRESSED RECTANGULAR PANEL)




DETAIL RIBBED-PRECAST PRESTRESSED PANELS-RECTANGULAR

DESIGN TABLE "C"-RIBBED PANELS					
CLEAR SPAN	DESIGN DECK THICKNESS	STRANDS	STRAND SPACING	STRANDS	STRAND SPACING
MINIMUM LENGTH UP TO AND INCLUDING	40"	7"	3/4" # 250K	9.5"	13"
50"	7"	3/4" # 250K	9"	12"	12"
60"	7"	3/4" # 250K	8"	11"	11"
70"	7"	3/4" # 250K	7"	10"	10"
80"	7"	3/4" # 250K	6"	9"	9"
90"	7"	3/4" # 250K	5.5"	8"	8"
100"	7"	3/4" # 250K	5"	7"	7"
110"	7"	3/4" # 250K	4.5"	6"	6"
60"	7 1/2"	3/4" # 250K	9"	12"	12"
70"	7 1/2"	3/4" # 250K	8"	10"	10"
80"	7 1/2"	3/4" # 250K	7"	9"	9"
90"	7 1/2"	3/4" # 250K	6"	8"	8"
100"	7 1/2"	3/4" # 250K	5.5"	7"	7"
110"	7 1/2"	3/4" # 250K	4.75"	6"	6"
120"	7 1/2"	3/4" # 250K	4"	5"	5"

Prestressing Pull for 3/4" # 250K Strands = 14,000 lbs. Each.
Prestressing Pull for 1/2" # 250K Strands = 18,900 lbs. Each.

GENERAL NOTES FOR PRECAST PANELS

- Shop Drawings shall be Submitted, Showing Complete Shop Details for the Precast Prestressed Panels. Details shall include Mechanical Interlock Reinforcing, Lifting Devices, Panel Dimensions, Clearances, Reinforcing Steel, Prestress Strand Size, Type and Pull, Material Specifications and a Detailing Schedule that will be Symmetrical about the Vertical Centerline of the Panel. Method of Placement and Method of Consolidation of Concrete Around Mechanical Interlock Reinforcing.
- MATERIALS:
 - Concrete shall be Class III (f'c=5,000 p.s.i.) No Prestressing Strand shall be Released Until the Concrete has Reached a Minimum Compressive Strength of 4,000 p.s.i. Concrete shall meet the Requirements of Standard Specification Section 345.
 - Prestressing Strands shall be 3/4" # 250K or 1/2" # 250K Seven Wire Stress Relieved Strands that Conform to the Requirements of A.S.T.M. A416. See Table.
 - All Other Metal Reinforcement shall Conform to the Requirements of Section 931. All Reinforcing Steel shall be Grade 40 or Grade 60.
 - Coarse Aggregate for Precast Panel Concrete shall be Grade 59, 7 and 57 and shall meet all other Requirements of Section 901.
 - The Prestressing Strands shall be Supported as Required by Either Reinforcing Steel Bar Supports (Stainless Steel - Class E) or Mortar Blocks, in Accordance with Section 415, Paragraph 415-5.10 and 415-5.13.
- Precast Prestressed Panels shall be Constructed Meeting all Applicable Requirements of Section 400 and Section 450.
- Mechanical Interlock Reinforcing of 0.50 Square Inches of Reinforcing Steel Per Ten (10) Sq. Ft. of Panel Surface shall be Provided. Alternate Designs will be Permitted, Subject to the Approval of the Engineer. Shop Drawings shall show Location of all Mechanical Interlock Reinforcing.
- Lifting Hooks or Devices will be Permitted But will be the Sole Responsibility of the Contractor. Any Hook or Device that Pulls Out of the Panel During Handling will be Cause for Rejection of the Panel. Lifting Devices shall not be Attached to or Hooked Under the Panel Reinforcing Steel or Prestressing Strands. Lifting Devices shall be shown on the Shop Drawings for the Approval of the Engineer.
- Prestressing Strands shall be Symmetrical and Uniformly Spaced about the Vertical Center Line of the Rectangular Panels.
- The Top Surface of the Precast Panels shall be Roughened at the Approximate time of Initial Set by Brushing, Brooming, Burlap Drag or Other Approved Method. This Surface shall be Kept Free of all Contaminants Such as Oil. (Particularly Bond-Breaking Substances)
- Membrane Curing Compound Will Not be Used on the Top of the Precast Panels.
- Precast Prestressed Concrete Panels shall be Produced within the Following TolerANCES.
Depth (Thickness of Panels) + 1/4" to - 1/4" #, Length of Panel ± 1"
Position of Strands + 1/4", - 0" Vertically #
+ 1/4" Horizontally
Measured from Bottom of Panel.
- Precast Panel Lengths May be Set and Achieved by Using Headers in the Form or by Sawing to Length.
- Precast Panels shall be Properly Handled and Stored to Prevent Breakage. Any Damage Due to Handling and Shipping Will be Cause for Rejection.
- Saw Cut Edges, With Exposed Distribution Steel, Must be Placed in Bearing on Top of the End Diaphragm in the Span. At No Other Place Within the Span Will a Saw Cut Edge With Exposed Distribution Steel be Permitted.
- To Allow for all Tolerances in Fabricating the Precast Panels and Placing the Reinforcing Steel in the Cast-In-Place Portion, This 7" Design Plan Deck will be Poured 7 1/2" Thick in all cases in the field of No Additional Increase in Contract Price.
- To Allow for all Tolerances in Fabricating the Precast Panels and Placing the Reinforcing Steel in the Cast-In-Place Portion, This 7 1/2" Design Plan Deck will be Poured 8 1/2" Thick in all cases in the field of No Additional Increase in Contract Price.
- The Fabricator May Elect to Fill One Valley on Each Side of the Center Line Symmetrically to Provide Coverage so that He Can Use a "Z", "C" or other Type of Mechanical Interlock Bar. See Sheet 2 of 3 for Details.



MECHANICAL INTERLOCK REINFORCING

(NOTE: Bottom Leg of # 4 Bar shall have a Minimum Embedment of 1 1/2" in Precast Panel and shall have a Minimum Cover of 1 1/2" (+ 1/4", - 0") from the Bottom of the Panel. However the Top of the Bar shall not be Higher than 1 1/2" (+ 1/4", - 0") Above the Top of the Panel.


FHWA APPROVED: 10-2-80

RIBBED PRECAST PANELS



STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION
STRUCTURES

PRECAST PANELS FOR 7" AND 7 1/2" COMPOSITE DECK
1 1/2" CLEAR AT BOTTOM 1 1/2" CLEAR AT TOP


REVISED	DESCRIPTION	FOAD NO.	COUNTY	PROJECT NO.
5-79	Added Tolerances & Revised Design			
5-80	Revised Table Expanded			
Designed by	JMG	5-78		
Checked by	CK	6-78		
Observed by				
Checked by				
Supervised by	AUH			
APPROVED BY				
Drawing No.				
Issued No.				
3 of 3				12641




PLAN OF DECK PANELS
(SEE TABLE 'A')




PANEL NO.	REMARKS
① ②	Fabricator's Standard Width Panel
③	Filler Panel, 2'-0" Minimum Width
④ ⑤	Filler Panels of Equal Widths Both 2'-0" or Wider
⑥ ⑦	Filler Panels - One 2'-0" (Min. Width) Unit, Other Panel Width as Required
⑧ ⑨ ⑩	Filler Panels - Width as Required > 2'-0"
⑪ ⑫	End Panels at Skewed Bents
⑬ ⑭	See Cut from Rectangular Panel
⑮ ⑯	See: Skewed Edge 1" or Support
⑰	Permissible Only Where Required by Extreme Skew Angle at Bent




PANEL BEARING CONDITIONS
FOR BEARING OR TYPE III BEAMS SEE GENERAL NOTE #11




STIRRUP EXTENDER BARS



REQUIRED FINISH OF TOP
FLANGE OF CONCRETE BEAM




SECTION E-E



SKETCH SHOWING RELATIONSHIP
OF BEAM AND DECK SLAB

PROFILE - DECK AND SUPPORT
Where beam camber differs from that shown in the Plans, adjust thickness of bearing material. Maximum thickness of fiberboard to be 1 1/2". When necessary to achieve a thickness greater than 1 1/2", fiberboard may be set on an approved grout pad so that the Deck thickness conforms to the Plan dimension. Transitions in bearing thickness shall be accomplished by using layers of 55# roofing felt, fiberboard and grout pads so placed as to control the bottom of the Panel Profile so that it is Parallel to the finished grade profile, and the Plan Deck Thickness is Maintained. Adequate measures shall be taken to ensure the sealing of all contact surfaces between Precast, Prestressed Panels and Supporting Units. (See Enlarged Schematic)



SCHEMATIC - CAMBER ADJUSTMENT

GENERAL NOTES

- When Precast Prestressed Panels are Used on a Bridge Structure at the Option of the Contractor, it shall be the Sole Responsibility of the Contractor to increase the Finished Grade Elevations and make all Adjustments Required by this Increase.
- Contractor shall instruct the Producers of Concrete Beams to provide a 3" Wide Smooth Finish at the Outside Edges of the Top Flange for Precast Panel Bearing and Grout Seal.
- When Precast Prestressed Panels are Substituted, Payment shall be made of the Contract Unit Prices for Concrete and Steel. The Quantities to be Paid for will be those Quantities which would be Paid for if Conventional Construction was Utilized. The Contract Unit Price for Concrete shall include the Cost of All Bearing Materials.
- Precast Prestressed Panels shall not be used on Steel Beams.
- Precast Prestressed Panels shall not be used under Barrier Walls with Reinforcing Steel Projecting into the Deck Slab.
- Before Any Precast Prestressed Panels are Placed in Position in Any Span, the Contractor shall Establish the Finished Grade Elevations and make the Required Camber Adjustments in a minimum of TWO Spans Ahead of the Span to be Set.
- The Erected Precast Panels shall Bear Uniformly on Continuous Layers of an Approved Material Such as Mastic, Felt, Fiberboard and/or Grout that will Provide a Mortar Tight Uniform Bearing. The Bearing Material shall be Placed Along the Outer Edges of Each Beam and the Inside Edge of the End Diaphragms at Skewed Bents.
- After the Precast Prestressed Panels have been set to Proper Grade on Bearing Material, the remaining Space Between the end of the Panels and the Bearing Material (1/4" Min. Width) shall be filled with cement Grout. The Grout shall consist of one part Portland cement to two parts clean sand with enough water to make a thick paste mixture. The Grout paste shall be placed by Trowel on Moisture Saturated Surfaces and Allowed to Set Before Placing Cast-In-Place Concrete. The Grout shall be Placed in a manner which will produce a leakproof seal.
- Precast Panels in their Final Position shall be Mortar Tight at Both the Outer Edges and the Mating Surfaces. The Top Surface of the Precast Panels Must be Free of Any Foreign Material to insure Full Bond with the Cast-In-Place Concrete. Immediately Prior to Placing the Cast-In-Place Concrete the Precast Panels shall be Saturated with Fresh Water.
- End Diaphragms Shown in Sections are not Dimensioned in Width. See Bridge Plan for Sizes. Add One (1) Inch to Width of Diaphragms at Skewed Bents to Provide Bearing for Precast Panels. Reinforcing Steel in End Diaphragms will not Change.
- The Bearing Width on Type IX and Type XII Precast Prestressed Beams shall be 2 1/2" (-1/2", +0") Past the End of Transverse Reinforcing Steel in the Top Flange of the Beam.
- The Transverse Spacing of the Mechanical Interlock Reinforcing shall clear the Longitudinal Distribution Steel of the Poured in Place Concrete and the Transverse Spacing shall be Constant Thru Out Spans of Equal Beam Spacing.

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION STRUCTURES PRECAST PANELS FOR COMPOSITE DECK WITH 1 1/2" CLEARANCE OF BOTTOM MAT OF STEEL


REVISIONS	ROAD NO.	COUNTY	PROJECT NO.
Date: Description:			
Designed by: CK	9-82	APPROVED BY:	
Checked by: AJH	9-82	Drawn by: [Signature]	
Quantities by:		Checked by:	
Supervised by: AJH		1 of 3	12642

REVISONS		ROAD NO.	COUNTY	PROJECT NO.
Station	Description			
6-79	Adding Topobases & Revised Drainage	Normal	5-78	AS PROVIDED BY
8-80	Drainage Table Expanded	CWB	6-78	<i>T. all</i>
		Checked by		Drawn: <i>James E. Hume, Jr.</i>
		Subserved by	AJH	2 of 3
				12642


GENERAL NOTES FOR PRECAST PANELS

- Shop Drawings shall be Submitted, Showing Complete Shop Details for the Precast Prestressed Panels. Details shall include Mechanical Interlock Reinforcing, Lifting Devices, Panel Dimensions, Clearances, Reinforcing Steel, Prestress Strand Size, Type and Pull, Material Specifications and a Detailing Schedule that will be Symmetrical about the Vertical Centerline of the Panel. Method of Placement and Method of Consolidation of Concrete Around Mechanical Interlock Reinforcing.
- MATERIALS:**
 - Concrete shall be Class IV ($f_c=5,000$ p.s.i.) No Prestressing Strand shall be Released Until the Concrete has Reached a Minimum Compressive Strength of 4,000 p.s.i. Concrete shall meet the Requirements of Standard Specification Section 345.
 - Prestressing Strands shall be $\frac{3}{8}"$ or $\frac{7}{16}"$ ϕ 250 K or 270 K Seven Wire Stress Relieved Strands that Conform to the Requirements of A.S.T.M. A 416. See Table.
 - All Other Metal Reinforcement shall Conform to the Requirements of Section 931. All Reinforcing Steel shall be Grade 40 or Grade 60.
 - Coarse Aggregate for Precast Panel Concrete shall be Grade 89, 7 and 57 and shall meet all other Requirements of Section 901.
 - The Prestressing Strands shall be Supported as Required by Either Reinforcing Steel Bar Supports (Stainless Steel-Class E) or Mortar Blocks, in Accordance with Section 415, Paragraph 415-5.10 and 415-5.13.
- Precast Prestressed Panels shall be Constructed Meeting all Applicable Requirements of Section 400 and Section 450.
- Mechanical Interlock Reinforcing of 0.60 Square Inches of Reinforcing Steel Per Ten (10) Sq. Ft. of Panel Surface shall be Provided. Alternate Designs will be Permitted, Subject to the Approval of the Engineer. Shop Drawings shall show Location of all Mechanical Interlock Reinforcing.
- Lifting Hooks or Devices will be Permitted But will be the Sole Responsibility of the Contractor. Any Hook or Device that Pulls Out of the Panel During Handling will be Cause for Rejection of the Panel. Lifting Devices shall not be Attached to or Hooked Under the Panel Reinforcing Steel or Prestressing Strands. Lifting Devices shall be shown on the Shop Drawings for the Approval of the Engineer.
- Prestressing Strands shall be Symmetrical and Uniformly Spaced about the Vertical Center Line of the Rectangular Panels.
- The Top Surface of the Precast Panels shall be Roughened at the Approximate time of Initial Set by Brushing, Brooming, Burlap Drag or Other Approved Method. This Surface shall be Kept Free of all Contaminants Such as Oil. (Particularly Bond-Breaking Substances)
- Membrane Curing Compound Will Not be Used on the Top of the Precast Panels.
- Precast Prestressed Concrete Panels shall be Produced within the Following Tolerances.
Depth (Thickness of Panels) $\pm \frac{1}{4}"$ to $-\frac{1}{8}"$ *; Length of Panel $\pm 1"$
Position of Strands $\pm \frac{1}{4}"$, $-0"$ Vertically *
 $\pm \frac{1}{4}"$ Horizontally
*Measured from Bottom of Panel.
- Precast Panel Lengths May be Set and Achieved by Using Headers in the Form or by Sawing to Length.
- Precast Panels shall be Properly Handled and Stored to Prevent Breakage. Any Damage Due to Handling and Shipping Will Be Cause for Rejection.
- Saw Cut Edges, With Exposed Distribution Steel, Must be Placed in Bearing On Top of the End Diaphragm in the Span. At No Other Place Within the Span Will a Saw Cut Edge With Exposed Distribution Steel Be Permitted.
- To Allow for all Tolerances in Fabricating the Precast Panels and Placing the Reinforcing Steel in the Cast-In-Place Portion, This $7\frac{1}{2}"$ Design Plan Deck will be Poured $8\frac{1}{2}"$ Thick in all cases in the field at No Additional Increase in Contract Price.
- To Allow for all Tolerances in Fabricating the Precast Panels and Placing the Reinforcing Steel in the Cast-In-Place Portion, This $8"$ Design Plan Deck will be Poured $8\frac{1}{2}"$ Thick in all cases in the field at No Additional Increase in Contract Price.
- The Fabricator May Elect to Fill One Valley on Each Side of the Center Line Symmetrically to Provide Coverage so that He Can Use A "Z", "C" or other Type of Mechanical Interlock Bar. See Sheet 2 of 3 for Details.

NOTE: Prestressing Strands Shown as Heavy Dashed Line in Plan and Side View for Clarity
Prestressing Strands May Be Placed Under Ribs Only in A Symmetrical Pattern About The Center Line.




DETAIL-TRAPEZOIDAL SHAPED PANELS AT SKEWED BENT
(SAW CUT FROM PRECAST PRESTRESSED RECTANGULAR PANEL)



DETAIL RIBBED-PRECAST PRESTRESSED PANELS-RECTANGULAR

DESIGN TABLE "C"- RIBBED PANELS					
CLEAR SPAN	DESIGN DECK THICKNESS	STRANDS	STRAND SPACING	STRANDS	STRAND SPACING
MINIMUM LENGTH	40"	7 $\frac{1}{8}"$ ϕ 250K	9.5"	13"	13"
UP TO AND INCLUDING	50"	8 $\frac{1}{8}"$ ϕ 270K	8.75"	10"	10"
	60"		6"	7.5"	7.5"
	70"		5"	5.5"	5.5"
	80"		4"	4.5"	4.5"
	90"		3"	3.75"	3.75"
	100"		2.5"	3"	3"
	70"	8"	7"	8.25"	8.25"
	80"		6"	7"	7"
	90"		5"	5.75"	5.75"
	100"		4.5"	5.25"	5.25"
	110"		4"	4.5"	4.5"
	120"		3.5"	4"	4"
	130"		3"	3.5"	3.5"

Prestressing Pull for $\frac{3}{8}"$ ϕ 250K Strands=14,000lbs. Each; Prestressing Pull for $\frac{7}{16}"$ ϕ 250K Strands=10,900lbs. Each.
Prestressing Pull for $\frac{3}{8}"$ ϕ 270K Strands=16,100lbs. Each.



(NOTE: Bottom Leg of #4 Bar shall have a Minimum Embedment of $1\frac{1}{2}"$ in Precast Panel and shall have a Minimum Cover of $1\frac{1}{2}"$ ($1\frac{1}{2}" + 0"$) from the Bottom of the Panel. However the Top of the Bar shall not be Higher than $1\frac{1}{2}"$ ($1\frac{1}{2}" + 0"$) Above the Top of the Panel.


FHWA APPROVED 10-2-80

RIBBED PRECAST PANELS

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION
STRUCTURES

PRECAST PANELS FOR $7\frac{1}{2}"$ AND $8"$ COMPOSITE DECK
 $1\frac{1}{2}"$ CLEAR AT BOTTOM - $2"$ CLEAR AT TOP

ROAD NO.	COUNTY	PROJECT NO.
REVISIONS		
No.	Description	Date
1-79	Added Tolerances & Revised Design	
8-80	Design Table Expanded	
Designed by	JMG	5-78
Checked by	CK	6-78
Quantity by		
Checked by		
Supervised by	AJH	
Drawing No.	3 of 3	Index No.
		12642



$7\frac{1}{2}"$ DESIGN PLAN DECK
(SEE GENERAL NOTE #13-THIS SHEET)

$8"$ DESIGN PLAN DECK
(SEE GENERAL NOTE #14-THIS SHEET)

MINIMUM COVERAGE DETAILS

GENERAL NOTES

CONSTRUCTION SPECIFICATIONS: State of Florida Department of Transportation Standard Specifications for Road and Bridge Construction, Current Edition with approved Supplements thereto.

DESIGN SPECIFICATIONS: American Association of State Highway and Transportation Officials (AASHTO) Standard Specifications for Highway Bridges, Current Edition with Approved Revisions thereto.

DESIGN LOADING: Designed in accordance with HS20-44 loading.

FUTURE WEARING SURFACE: An allowance of 15 lbs. per sq. ft. is included for future wearing surfaces.

REINFORCING STEEL: All reinforcing steel shall conform to ASTM A-615 Grade 40 or Grade 60 unless otherwise noted.

PILING: Piling shall be 18" sq. Prestressed Concrete Piles. For Quantities see Summary of Bridge Pay Items. Maximum pile loads shall be as follows:

BRIDGE WIDTH	SPAN LENGTH (FT)	LOCATION	PILE LOAD (TONS)
40 FT. ROADWAY	25 To 35	End Bent	30
	25 @ 27.5	Intermediate Bent	40
	30 @ 32.5	Intermediate Bent	45
	35	Intermediate Bent	50
44 FT. ROADWAY	25 To 35	End Bent	30
	25	Intermediate Bent	40
	27.5 @ 30	Intermediate Bent	45
	32.5	Intermediate Bent	50
	35	Intermediate Bent	55

CONCRETE: Class II Concrete ($f'_c = 3400$ psi) shall be used throughout the Substructure. Class II Concrete ($f'_c = 3400$ psi) shall be used for field cast concrete in the Superstructure. Class III Concrete ($f'_c = 5000$ psi) shall be used for prestressed members.

CONCRETE FINISH: Concrete shall be finished in accordance with Specifications. All exposed top, inside and outside surfaces of End Bent Wingwalls, and Concrete Handrail Barrier and outside surfaces of Slab Units shall receive a "Class 5 Applied Finish Coating."

ENVIRONMENT: These plans shall only apply to structures located in noncorrosive (Non Coastal) environments.

LIMITATIONS FOR USE: These drawings shall not be used for Structures located in Superelevation Transition or for Structures on alignments where the slope (Camber not used) of the slab unit on the bearing is greater than 0.04 feet per foot.

BITUMINOUS MATERIAL: For Type of Bituminous Material, Estimated Quantities, and payment See Roadway Plans.

ALTERNATE SECTIONS: At the option of the Contractor, wider units may be furnished provided the amount of prestressing per foot of width is maintained.

PRESTRESSED MEMBERS

FINISH: The top of prestressed units shall be finished smooth by floating or brooming. All other surfaces of the units shall receive a "Class 3" surface finish. The edges of the top surface of the units shall be finished by use of a small radius tool.

CONCRETE STRENGTH: At transfer of the prestressing load, the cylinder strength of the concrete shall be 4000 psi.

HANDLING & STORAGE: During handling and storage, the prestressed units must be maintained in an upright position at all times. The units must be picked up at the ends of the units to prevent damage.

FORMS & PALLETS: All prestressed units shall be cast on concrete based pallets and in metal forms.

STRANDS: At the option of the Contractor, stabilized strands may be used in lieu of stress relieved strands. Calculations are to be submitted showing the substitution meets the following requirements:

1. The strands meet all requirements of ASTM A-416 Grade 270.
2. The net compressive stress in the concrete after all losses is at least as large as that provided by the 270K stress relieved strands.
3. The ultimate strength of the structure meets the requirements of the applicable AASHTO Specifications.

At the option of the Contractor, 250K stress relieved strands may be substituted in lieu of the 270K strands shown provided that calculations are submitted showing compliance with the requirements of Items 2 and 3 above. Where alternate strands are proposed, the required calculations shall be submitted with the Shop Drawings.

STRAND EXTENSION: All strands shall extend $2\frac{1}{2}$ " beyond the ends of the prestressed units.

TIE BARS: Tie bars shall be $\frac{1}{2}$ " # Bars for post-tensioning and shall comply with the requirements of Section 933 of the Specifications. The tie bars shall be stressed and anchored at 125,000 lbs. per post-tensioned bar.

SHOP DRAWINGS: The contractor shall submit 7 sets of shop drawings, showing complete details of the proposed prestressed units. The drawings shall include reinforcing steel, prestressing steel, prestressing bed layout, tensioning and detensioning schedules, and all computations required to control the work.

BEARING PADS: Neoprene bearing pads shall be $\frac{1}{2}$ " X 6" strips in accordance with section 932-2 of the Specifications. The pads may be continuous strips or multiple lengths of 2'-0" minimum length. The pads may be cut from commercially available sheets and shall be Grade 50.

PAYMENT: The contract unit price for the precast-prestressed units shall include the units, prestressed strands, reinforcing steel shipped with the units, tie bars and anchorages, neoprene bearing pads, premolded expansion material, and epoxy mortar.

TIE BAR ANCHORAGES: The fabricator shall submit details of the Tie Bar Anchorage and Anchorage Reinforcement details for approval with the Shop Plans.

CONSTRUCTION NOTES

EQUIPMENT ON UNITS: Before heavy construction equipment is permitted on the structure during construction, sketches showing the axle spacing and anticipated loadings shall be submitted to and approved by the Engineer.

FILLING KEYWAYS: During placement of the units, or prior to filling the joints between the units and keyways with epoxy mortar, the bottom of the openings shall be sealed to prevent leakage during placement of the epoxy mortar. The seal shall extend upward from the bottom of the unit a maximum of 1 inch. The material proposed for the seal shall be shown on the shop plans for approval by the Engineer. After the seals are in place for the entire superstructure, the joints and keyways shall be filled with epoxy mortar (See Epoxy Mortar Note below). Careful attention shall be given to the areas where the tie bars and anchorages for the tie bars are to be installed to avoid filling these holes.

TIE BARS: The transverse post-tensioned tie bars shall not be tensioned until the epoxy mortar in the joints and keyways has been cured for a minimum of 72 hours. The bars shall be installed, post-tensioned and anchored to 125,000 lbs. each.

GROUTING BARS: The tie bars shall be grouted in accordance with section 450-II of the Specifications. The grouted tie bars shall not be disturbed, nor shall appreciable loads be placed on the span for a period of 72 hours following grouting.

FILLING ANCHORAGE BLOCKOUTS: All recesses and blockouts for post-tensioned tie bars shall be filled with non-shrinking grout.

"CONTINUED"

PLACING BARRIER WALLS & SURFACING: After all tie bars have been grouted and the minimum 72 hours have passed for all tie bars, the barrier walls and wearing course shall be placed.

SAWED JOINTS: A control crack shall be provided by sawing of all supports a joint, the depth of the wearing surface, from gutter to gutter. The joint shall be centered over the centerline of the concrete joint and shall be sawed upon completion of the surfacing.

EPOXY MORTAR MIX: The epoxy mortar shall be composed of a mixed epoxy binder and sand as follows:

(a) BINDER

The binder shall be a two component (1:1 ratio hydro-ester) material meeting the following requirements:

- (1) The material shall be insensitive to moisture.
- (2) The material shall adhere to wet concrete.

(b) SAND

The sand filler shall be kiln dried silica sand meeting these gradation requirements:

STANDARD	SAND
U.S. Sieve Size	% Passing
No. 4	100
No. 16	90-100
No. 30	30-50
No. 50	0-10
No. 100	0-5

ALTERNATE	SAND
U.S. Sieve Size	% Passing
No. 4	100
No. 10	90-100
No. 20	0-5
No. 40	0

(c) MIXING

The epoxy mortar shall be machine mixed in strict accordance with the manufacturer's directions.

- (1) One part of binder shall be combined with a maximum of three parts of sand filler.
- (2) No more filler shall be mixed than can be placed into the joints and keyways in a period of 20 min. Any material so mixed and not used within the 20 minutes immediately following shall be discarded.
- (3) For joints where the above mix will not flow into the voids, the mix may be thinned by adding additional binder to the mix.

(d) STRENGTH


The strength of the epoxy mortar shall be considered acceptable provided that 2 inch cubes of the material demonstrate a compressive strength of 6500 psi when tested. The mix proportions for the test cubes shall consist of one part binder to one part sand filler. The specimen shall be cured at a temperature of 66°F to 74°F and shall be tested in accordance with Section 926-3.2(b) of the Specifications.

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION
STRUCTURES



GENERAL & CONSTRUCTION NOTES

REVISIONS	ROAD NO.	COUNTY	PROJECT NO.
Dates	Revisions	Dates	APPROVED BY
10/80 Revised Environment			
11/80 Concrete Finish	Designed by C.W.	7/78	
5/82 Concrete Finish	Checked by J.L.M.	7/78	
6/82 Revised Strength Note	Reviewed by		
9/82 Added Bearing Pad Grade	Submitted by J.L.M.		
		Drawing No. 1 OF 1	12661


REVISIONS		FOCAL NO.		COUNTY	PROJECT NO.
Date	Description	Name	Date	APPROVED BY	
		Designed by <i>R. N.</i>	<i>7/78</i>	<i>7- all</i> <i>LD</i> Deputy County Engineer, Structures Drawing No. <i>1 of 1</i> <i>12662</i>	
		Checked by <i>J. L. N.</i>	<i>7/78</i>		
		Quoted by <i>J. L. N.</i>	<i>7/78</i>		
		Checked by <i>P. D. S.</i>	<i>9/80</i>		
		Submitted by <i>J. L. N.</i>			



- ① Dimension shown is for Normal Crown Roadway 0% Grade. This dimension shall be adjusted in the field to match Bridge Barrier Curb Profile for Structures on grade or superelevated.
- ② This dimension shall be adjusted in the field to match Prestressed Slab Units.



STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION STRUCTURES			
END BENT WING DETAILS			
REVISIONS		ROAD NO.	COUNTY
Date	Description		
11/13/80	Sp Bars 4C		
Designed by	R.N.	Date	7/78
Checked by	J.L.M.	Date	7/78
Quantity by			
Checked by			
Submitted by	J.L.M.	Drawing No.	1011
		Project No.	12,665




ESTIMATED QUANTITIES		
WIDTH	CLASSIC CONC. CU. YDS.	REINF. STEEL LBS.
Spans = 25' 27.5' @ 30' Normal Cross Slope	12.9	1487
Spans = 32.5' @ 35' Normal Cross Slope	12.9	1487
Spans = 25' 27.5' @ 30' Super-elevated Slope	11.8	1491
Spans = 32.5' @ 35' Super-elevated Slope	11.8	1491
Spans = 25' 27.5' @ 30' Normal Cross Slope	14.2	1626
Spans = 32.5' @ 35' Normal Cross Slope	14.2	1626
Spans = 25' 27.5' @ 30' Super-elevated Slope	12.9	1629
Spans = 32.5' @ 35' Super-elevated Slope	12.9	1629

REINFORCING STEEL					
MARK	40 FT. ROADWAY		44 FT. ROADWAY		BENDING
	No.	Length	No.	Length	
8A	10	43'-6"	10	47'-6"	Straight
4B	8	7'-9"	8	8'-9"	Straight
4C	1	5'-6"	1	5'-6"	See Diagram
4S1	40	9'-9"	44	9'-9"	See Diagram
4S2	5	7'-2"	5	7'-2"	See Diagram



NOTE: The Numeric Prefix of the Bar Mark Indicates the Bar Size, ie 8A is a Bar Size 8.

BENDING DIAGRAMS



NOTE: All bar dimensions are cut to cut

NOTE: Place Dowels "G" at Fixed (F) ends of Spans (See Superstructure Details and Plan and Elevation sheet).



This dimension shall be adjusted in the field for Structures super-elevated and shall apply only on the low side.







TABLE OF ELEVATIONS									
Bent No.	Elev. "A"	Elev. "B"	Elev. "C"	Elev. "D"	Elev. "E"	Elev. "F"	Elev. "G"	Elev. "H"	Elev. "J"

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION STRUCTURES			
INTERMEDIATE BENT ZERO DEGREE SKEW			
ROAD NO.	COUNTY	PROJECT NO.	
DESIGNED BY	CHECKED BY	DATE	APPROVED BY
R. M.	J. L. M.	7/78	
CHECKED BY	DATE		
J. L. M.	7/78		
CHECKED BY	DATE		
R. D. S.	9/80		
SUPERVISOR			
J. L. M.			
DRAWING NO.		SHEET NO.	
1 OF 1		12666	


[illegible]

NOTE The Numeric Prefix of the Bar Mark Indicates the Bar Size, ie 8A is a Bar Size 8.

[illegible]

NOTE Place Dowels "G" at Fixed (Ends of Spans) (See Superstructure Details and Plan and Elevation Sheet).

		STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION STRUCTURES			
		INTERMEDIATE BENT 12 1/2 DEGREE SKEW			
REVISIONS		ROAD NO.	COUNTY	PROJECT NO.	
Date	Description				
		Revised	Revised	APPROVED BY	
		Designed by R.W.	7/78	 District Engineer, Structures (Index No.)	
		Checked by J.L.M.	7/78		
		Quantities by J.L.M.	7/78		
		Checked by R.D.S.	9/80		
		Submitted by J.L.M.			
				Drawing No.	1 OF 1
				Index No.	12667



ESTIMATED QUANTITIES		
CLASS II CONC.	REINF. STEEL	
CU. YDS.	LBS.	
Spans + 25' 27.5' 30' Normal Cross Slope	14.3	1672
Spans + 32.5' 35' Normal Cross Slope	14.3	1672
Spans + 25' 27.5' 30' Super-elevated Slope	13.1	1676
Spans + 32.5' 35' Super-elevated Slope	13.1	1676
Spans + 25' 27.5' 30' Normal Cross Slope	15.7	1822
Spans + 32.5' 35' Normal Cross Slope	15.7	1822
Spans + 25' 27.5' 30' Super-elevated Slope	14.3	1826
Spans + 32.5' 35' Super-elevated Slope	14.3	1826

REINFORCING STEEL		
MARK	NO.	LENGTH
4A	10	48'-0"
4B	9	8'-11"
4C	1	5'-2"
4SI	44	9'-9"
4S2	5	7'-2"
4U	6	4'-8"
4S3	2	10'-3"

NOTE: The Numeric Prefix of the Bar Mark indicates the Bar size, i.e. 4A is a Bar size 4.










TABLE OF ELEVATIONS										
Bent No.	Elev. "A"	Elev. "B"	Elev. "C"	Elev. "D"	Elev. "E"	Elev. "F"	Elev. "G"	Elev. "H"	Elev. "J"	Elev. "K"

REVISIONS		POWD NO.	COUNTY	PROJECT NO.
Date	Description			



STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION
STRUCTURES
INTERMEDIATE BENT 25 DEGREE SKEW
1 of 1
12668



44 FT. ROADWAY ZERO DEGREE SKEW



44 FT. ROADWAY 12 1/2 DEGREE SKEW





















44 FT. ROADWAY 25 DEGREE SKEW

NOTE: For Details of Barrier Wall Transition at End Bents see Concrete Handrail Barrier Sheet.

NOTE: Details shown are for skew right bridge. Skew left bridge is opposite hand.

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION									
STRUCTURES									
SUPERSTRUCTURE									
ROAD NO.		COUNTY	PROJECT NO.						
<table border="1"> <tr> <th>REVISIONS</th> <th>DATE</th> <th>DESCRIPTION</th> </tr> <tr> <td>1-81</td> <td>7/78</td> <td>Wid. width changed</td> </tr> </table>				REVISIONS	DATE	DESCRIPTION	1-81	7/78	Wid. width changed
REVISIONS	DATE	DESCRIPTION							
1-81	7/78	Wid. width changed							
Designed by	A.M.	7/78	APPROVED BY						
Checked by	JLM	7/78							
Quantity by									
Checked by									
Submitted by	JLM								
Drawing No.		Sheet No.	Project No.						
of 2		12669							

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION STRUCTURES				
<i>SUPERSTRUCTURE</i>				
ROAD NO.	COUNTY		PROJECT NO.	
Designed by	Names	Dates	Approved by	
Checked by	JLM	7/78	 Deputy George E. Hester, Structures Index No.	
Quantities by	JLM/AMM	7/78		
Checked by	RDS	9/80		
Supervised by	JLM			
			Drawing No.	Index No.
			2 OF 2	12669



① Applies only where Roadway Drains are shown on Bridge Plan and Elevation sheet.

NOTE: Details Shown are for Skew Left Bridge. Skew Right Bridge is Opposite Hand.

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION STRUCTURES			
PRESTRESSED SLAB UNITS			
REVISIONS	DATE	COUNTY	PROJECT NO.
10-78 11-80 1-81	Revised Ends of All Units Bars S2 & Dim 3" Holes Dimensions changed for unit B Maximum spacing added, dimension for projection of Bar changed	FLA.	12,670
Designed by Checked by Quantity by Supervised by	R.N. J.L.M. J.L.M.	7/78 7/78	APPROVED BY 1 of 3 12,670



See Bending Diagram

BILL OF REINFORCING STEEL

Mark	Size	No. Req'd Per Unit			Length	Mark	Size	No. Req'd Per Unit			Length
A B A B C B C B D						A B A B C B C B D					
Span = 25'-0"						Span = 32'-0"					
A	3	3	3	2	25'-0"	A	3	3	3	2	32'-0"
B1	3	18	18	-	5'-7"	B1	3	21	21	-	5'-7"
B2	3	-	-	18	2'-7"	B2	3	-	-	21	2'-7"
C	3	10	10	8	4'-4"	C	3	10	10	8	4'-7"
D1	4	38	-	-	3'-0"	D1	4	48	-	-	3'-5"
D2	4	38	-	-	1'-9"	D2	4	48	-	-	1'-9"
S1	4	50	50	-	"	S1	4	62	62	-	"
S2	4	-	-	25	"	S2	4	-	-	31	"
T	4	16	16	12	1'-10"	T	4	16	16	12	2'-1"
Span = 27'-0"						Span = 35'-0"					
A	3	3	3	2	27'-0"	A	3	3	3	2	35'-0"
B1	3	18	18	-	5'-7"	B1	3	22	22	-	5'-7"
B2	3	-	-	19	2'-7"	B2	3	-	-	22	2'-7"
C	3	10	10	8	4'-4"	C	3	10	10	8	4'-7"
D1	4	40	-	-	3'-0"	D1	4	51	-	-	3'-5"
D2	4	40	-	-	1'-9"	D2	4	51	-	-	1'-9"
S1	4	54	54	-	"	S1	4	66	66	-	"
S2	4	-	-	27	"	S2	4	-	-	33	"
T	4	16	16	12	1'-10"	T	4	16	16	12	2'-1"







TABLE OF DIMENSIONS

Span	A	F	G	H	J	K	L	M	N	Span	A	F	G	H	J	K	L	M	N
25 FT. SPAN										32.5 FT. SPAN									
0"	24"	6"	0"	7.5"	6.1"	7.1"	4.1"	5.0"	6.1"	0"	24"	12"	11.5"	10.5"	9.5"	7.5"	7.6"	8.7"	9.5"
12"	24"	6"	0"	7.5"	6.1"	7.1"	4.1"	5.0"	6.1"	12"	24"	12"	11.5"	10.5"	9.5"	7.5"	7.6"	8.7"	9.5"
25"	24"	6"	0"	7.5"	6.1"	7.1"	4.1"	5.0"	6.1"	25"	24"	12"	11.5"	10.5"	9.5"	7.5"	7.6"	8.7"	9.5"
27.5 FT. SPAN										35 FT. SPAN									
0"	24"	6"	0"	7.5"	6.1"	7.1"	4.1"	5.0"	6.1"	0"	24"	12"	11.5"	10.5"	9.5"	7.5"	7.6"	8.7"	9.5"
12"	24"	6"	0"	7.5"	6.1"	7.1"	4.1"	5.0"	6.1"	12"	24"	12"	11.5"	10.5"	9.5"	7.5"	7.6"	8.7"	9.5"
25"	24"	6"	0"	7.5"	6.1"	7.1"	4.1"	5.0"	6.1"	25"	24"	12"	11.5"	10.5"	9.5"	7.5"	7.6"	8.7"	9.5"
30 FT. SPAN										35 FT. SPAN									
0"	24"	6"	0"	7.5"	6.1"	7.1"	4.1"	5.0"	6.1"	0"	24"	12"	11.5"	10.5"	9.5"	7.5"	7.6"	8.7"	9.5"
12"	24"	6"	0"	7.5"	6.1"	7.1"	4.1"	5.0"	6.1"	12"	24"	12"	11.5"	10.5"	9.5"	7.5"	7.6"	8.7"	9.5"
25"	24"	6"	0"	7.5"	6.1"	7.1"	4.1"	5.0"	6.1"	25"	24"	12"	11.5"	10.5"	9.5"	7.5"	7.6"	8.7"	9.5"

† All Units Except "D"
†† Unit "D" Only




Note 1: Exterior Units A shall receive a smooth finish within these limits.










TIE BAR LOCATION DETAILS

(Show Left Details Shown, Skew Right Details Opposite Hand.)

Mark	Size	Length	Mark	Size	Length
0	2"	5'-5"	2	2"	5'-6"
12	2"	5'-5"	2	10"	5'-7"
25	2"	5'-5"	3	0"	5'-9"
0	2"	5'-5"	2	9"	6'-0"
12	2"	5'-5"	2	10"	6'-1"
25	2"	5'-5"	3	0"	6'-3"



NOTE: Form Vent to Clear 1/2" Strands in Prestressed Shop Units.



25 FT. SPAN

27.5 FT. SPAN

30 FT. SPAN

32.5 FT. SPAN

35 FT. SPAN

UNITS A,B,B

UNITS C,D,D

PRESTRESSING STRAND LOCATIONS

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION
STRUCTURES

PRESTRESSED SLAB UNITS

REVISIONS

Date	Description
10-78	Original Showing Cover Between Voids & S.R. Strands Removed
11-80	Table of Dimensions
10-81	Optional Corner Detail added
5-82	Unit A Anchorage Recess

DESIGNED BY: R.H. 7/78

CHECKED BY: J.L.M. 7/78






QUANTITY BY: J.L.M.

SUPERVISOR BY: J.L.M.

ROAD NO. COUNTY PROJECT NO.

APPROVED BY: J.L.M.

2 of 3 12,670



DETAILS OF GUARDRAIL ATTACHMENT AT WING POSTS

NOTE: For Guardrail Shoe and Attachment See Standard Drawing in Roadway Plans.

NOTE: At the option of the Contractor, Barrier walls may be constructed by slip-forming subject to the following: the width may be increased a maximum of 2 inches provided that the Front Face at the Base of each Barrier, infringes on the clear Roadway width no more than 1/2 and that any additional materials required are at the expense of the Contractor. The shape of the Barrier on the Roadway side shall not be altered.

NOTE: At the Option of the Contractor Handrail Barriers and End Bent Wingwalls, on Super-elevated Bridges, may be constructed perpendicular to the roadway surface. The Cost of modifications shall be at the Contractors expense.

QUANTITIES: Class II Concrete - 0.0817 Cu Yds. per linear ft. of Barrier (Based on Roadway Cross Slope of 02/111) REINFORCING STEEL - 10.19 lbs per linear ft. of Barrier.

GENERAL NOTES

CONCRETE: Class II Concrete shall be used in Barrier. REINFORCING STEEL: Reinforcing Steel shall be Grade 60. PAYMENT: Barrier shall be paid for per linear foot, which shall include all Concrete and Reinforcing Steel. Barrier shall be measured along the centerline of the top surface of the Barrier. CYLINDER STRENGTH: The Cylinder Strength of the Concrete shall be 3,400 p.s.i. minimum at 28 days. MARKERS: Markers recording the Elevation shall be placed on top of the Barrier at End Bents. On Bridges longer than 100 ft one marker shall be placed at each end of the Bridge. On Bridges less than 100 ft long, one marker shall be placed at one end of the Bridge only. Markers are to be furnished by the Department of Transportation and installed by the Contractor. The Cost of installing the Markers shall be included in the Contract Unit Price for Concrete Barrier. ANCHOR BOLTS: Anchor Bolts, Nuts and Washes shall be hot dip galvanized in accordance with A.S.T.M. A-123.



REINFORCING STEEL NOTES

Bars D1 & D2 shall be cast in the prestressed Slab unit. Payment for Bars D1 & D2 shall be included in the Contract Unit Price for Prestressed Slab Units.

All reinforcing steel in Barrier shall be No. 4's. Bars 4U to be spaced at 8" c.c. (Spliced to Bars D1).


At all open joints Bars 4U and the ends of Bars 4S shall have 2" min. cover.

At all construction joints Bars 4S may be either continuous or lap spliced. All splices in Bars 4S shall be 1'-4" min.



HOLES FOR INCIDENTAL SIGNING

NOTE: Holes and grooves shall be placed on barrier type handrails of divided and undivided bridges as shown in the plans for designated type "C" single column, informational, guide, regulatory and warning sign locations (see signing plans) and of approximately 500' intervals along the right handrails of bridges between designated locations for future signs as directed by the Engineer. The cost of the extra holes and grooves shall be included in the contract unit price for Concrete Handrail (Barrier). If Signing Plans are not available the Project Engineer should secure necessary information from the District Maintenance or Traffic Operations Office.




SECTION THRU RECESSED "V" GROOVE TO FORM INSCRIBED LETTERS AND FIGURES

NOTES

The Name and Bridge Number to be placed on the Barrier shall be seen on the drivers right when approaching Bridge. The Date to be placed on the drivers left when approaching Bridge. The Date shall be the Year the Bridge is constructed.

Black Plastic Letters and Figures 3" in height as approved by the Engineer may be used in lieu of Letters and Figures formed by "V" Grooves.

"V" Grooves shall be formed by preformed Letters and Figures.



ANCHOR BOLT DETAIL

NOTE: Cost of Anchor Bolts to be included in the Contract Unit Price for Guardrail.

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION STRUCTURES			
CONCRETE HANDRAIL BARRIER			
REVISIONS	ROAD NO.	COUNTY	PROJECT NO.
Date: _____ Description: _____ By: _____ Checked by: _____ Approved by: _____ Supervised by: _____	Name: _____ Date: _____ Checked by: _____ Approved by: _____ Supervised by: _____	Name: _____ Date: _____ Checked by: _____ Approved by: _____ Supervised by: _____	Name: _____ Date: _____ Checked by: _____ Approved by: _____ Supervised by: _____
Drawing No. _____ Index No. _____		3 of 3 12,670	