

10/25/2023 7:57:10 AM RD960DL  
C:\Projects\Standards\Roadway\FDM\_900\_Exhibit\_Master.dgn

| VEGETATION REMOVAL TABLE |                                                                                                                                                                                           |                                     |                           |                     |                                                                                                  |
|--------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------|---------------------------|---------------------|--------------------------------------------------------------------------------------------------|
| AREA ID                  | WORK DESCRIPTION                                                                                                                                                                          | EST. % OF PRIMARY SPECIES TO TARGET | PRIMARY SPECIES TO TARGET | SPECIES TO PRESERVE | NOTES                                                                                            |
| 424                      | DESIGNATES AREAS WHERE CATEGORY #1 INVASIVE, EXOTIC VEGETATION AND NATIVE UNDERSTORY WILL BE SELECTIVELY REMOVED. LARGE DESIREABLE TREES TO REMAIN. ALL TREES UNDER 4" DBH TO BE REMOVED. | 75%                                 | AA, ST                    | PE, SP              | REMOVE LARGE TREE DEBRIS OR GRIND ON SITE AND SPREAD AS DIRECTED BY DISTRICT LANDSCAPE ARCHITECT |
| 426                      | DESIGNATES AREAS WHERE ALL NATIVE VEGETATION WILL BE MOWED FLUSH WITH THE GROUND AND ALL CATEGORY #1 INVASIVE, EXOTIC VEGETATION WILL BE TREATED WITH HERBICIDES.                         | 100%                                | AA, ST, TS                | NONE                | INCLUDES REMOVAL OF WILLOWS AND WAX MYRTLE                                                       |

WORK TABLE NOTES

1. "PRIMARY" SPECIES TO TARGET (REMOVE) OR PRESERVE ARE THOSE THAT WERE DETERMINED TO BE MOST PREVALENT IN THAT AREA, AND ARE NOT INTENDED TO BE THE ONLY SPECIES THAT OCCUR. THE FOLLOWING ADDITIONAL UNDESIREABLE NATIVE SPECIES WILL BE TARGETED FOR REMOVAL IN ALL AREAS LISTED IN THE WORK TABLE:  
BOTANICAL NAME (COMMON NAME)  
MYRICA CERIFERA (SOUTHERN WAX MYRTLE)  
TYPHA SPP. (CATTAILS)
2. THE FOLLOWING CATEGORY #1 INVASIVE SPECIES WILL NOT BE TARGETED FOR REMOVAL:  
BOTANICAL NAME (COMMON NAME)  
SOLANUM TAMPICENSE (WETLAND NIGHTSHADE)  
PANICUM REPENS (TORPEDO GRASS)

SPECIES LEGEND

| (SYM) | BOTANICAL NAME (COMMON NAME)                |
|-------|---------------------------------------------|
| (AA)  | ACACIA AURICULIFORMIS (EARLEAF ACACIA)      |
| (ST)  | SCHINUS TEREBINTHIFOLIUS (BRAZILIAN PEPPER) |
| (TS)  | TYPHA SPP. (CATTAILS)                       |
| (PE)  | PINUS ELLIOTTII (SLASH PINE)                |
| (SP)  | SABAL PALMETTO (SABAL PALM)                 |

ROOT AND BRANCH PRUNING TABLE

| TREE ID | LOCATION (Station/Offset or Coordinates) | BOTANICAL NAME     | COMMON NAME | WORK DESCRIPTION                              | NOTES                      |
|---------|------------------------------------------|--------------------|-------------|-----------------------------------------------|----------------------------|
| 1125    | 428+40 150' LT                           | QUERCUS VIRGINIANA | LIVE OAK    | TRIM CO-DOMINANT LEADER                       | INCLUDES REMOVAL OF DEBRIS |
| 1126    | 430+50 120' LT                           | QUERCUS VIRGINIANA | LIVE OAK    | PRUNE TO IMPROVE STRUCTURAL INTEGRITY OF TREE | INCLUDES REMOVAL OF DEBRIS |

TREE DISPOSITION TABLE

| SHEET NUMBER | TREE NO. | SYMBOL | BOTANICAL NAME     | COMMON NAME | DBH (IN.) FOR TREES/ CTH (FT.) FOR PALMS | HEIGHT (FT.) (APPROX.) | CANOPY SPREAD (FT.) (APPROX.) | LOCATION        |             | CONDITION | DISPOSITION                      | NOTES                                                          |
|--------------|----------|--------|--------------------|-------------|------------------------------------------|------------------------|-------------------------------|-----------------|-------------|-----------|----------------------------------|----------------------------------------------------------------|
|              |          |        |                    |             |                                          |                        |                               | STATION         | OFFSET/SIDE |           |                                  |                                                                |
| TD-1         | 1121     | QV     | QUERCUS VIRGINIANA | LIVE OAK    | 4                                        | 16                     | 7                             | 424+20          | 130' LT     | AVERAGE   | RELOCATE TO STA. 429+30, 145' LT | NURSEY MATERIAL PLANTED IN 2017 AS PART OF A LANDSCAPE PROJECT |
| TD-1         | 1122     | RR     | ROYSTONIA REGIA    | ROYAL PALM  | 19                                       | 19 GW                  |                               | 423+60          | 210' RT     | AVERAGE   | RELOCATE TO STA. 430+90, 130' LT |                                                                |
| TD-1         | 1123     | PC     | PINUS CLAUSA       | SAND PINE   |                                          |                        |                               | 430+70 - 434+95 | RT          | AVERAGE   | REMAIN                           | GROUP OF PINES                                                 |
| TD-1         | 1124     | QV     | QUERCUS VIRGINIANA | LIVE OAK    | 6                                        | 20                     | 25                            | 437+95          | 300' RT     | POOR      | REMOVE                           | SEE SELECTIVE CLEARING AND GRUBBING PLAN                       |

Exhibit 924-2  
Selective Clearing  
and Grubbing Detail  
Date: 1/1/2024

| REVISIONS |             |  |      | LANDSCAPE ARCHITECT | STATE OF FLORIDA<br>DEPARTMENT OF TRANSPORTATION |        |                      | SHEET NO. |
|-----------|-------------|--|------|---------------------|--------------------------------------------------|--------|----------------------|-----------|
| DATE      | DESCRIPTION |  | DATE |                     | ROAD NO.                                         | COUNTY | FINANCIAL PROJECT ID |           |
|           |             |  |      |                     | SR 91                                            | ORANGE | 123456-1-52-01       |           |

ARTURITO T. GOMEZ, L.A.  
LICENSE NUMBER: 99999  
LAND DESIGN, LLC.  
345 IVY LANE  
ORLANDO, FL 32801

SELECTIVE CLEARING AND GRUBBING DETAIL

1396

THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE DIGITALLY SIGNED AND SEALED UNDER RULE 61G10-11.011, F.A.C.