Chapter 2

Design Geometrics and Criteria

2.0	General		2-1
2.1	Lanes		2-7
	2.1.1	Through or Travel Lanes	2-7
	2.1.2	Other Lane Widths	2-8
	2.1.3	Ramp Traveled Way Widths	2-9
	2.1.4	Pedestrian, Bicycle and Public Transit Facilities	2-10
		2.1.4.1 Sidewalks	2-10
		2.1.4.2 Bicycle Facilities	2-10
		2.1.4.3 Public Transit Facilities	2-10
	2.1.5	Cross Slopes	2-11
	2.1.6	Roadway Pavement	2-14
		2.1.6.1 Alternative Roadway Paving Treatment	s2-14
	2.1.7	Transitions of Pavement Widths	2-14
	2.1.8	Number of Lanes on the State Highway System	2-15
2.2	Medians		2-17
	2.2.1	Median Width for Roadways	2-17
	2.2.2	Multilane Facility Median Policy	2-18
	2.2.3	Median Treatments on Bridges	2-18
2.3	Shoulder	rs	2-19
	2.3.1	Limits of Friction Course on Paved Shoulders	
	2.3.2	Shoulder Warning Devices (Rumble Strips)	2-27
2.4	Roadside	e Slopes	2-28
2.5	Borders.		2-29

	2.5.1	Limited A	ccess Facilities	2-32	
2.6	Grades			2-33	
2.7	Sight Distance				
2.8	Curves		2-39		
	2.8.1	Horizonta	I Curves	2-39	
		2.8.1.1	Supplemental Alignment Control (Mainline)	2-39	
		2.8.1.2	Supplemental Alignment Control (Intersections)	2-44	
		2.8.1.3	Roadway Transitions		
	2.8.2	Vertical C	Curves		
2.9	Superelev	vation		2-47	
2.10	Vertical Clearance2-5				
	2.10.1	Vertical C	learance Over Water	2-59	
	2.10.2	Airspace	Obstructions	2-60	
2.11	Horizontal Clearance2-				
2.12	Bridge Railings and Separators2-7				
2.13	Intersection	ons		2-81	
	2.13.1 Circular Intersections (Roundabouts)2-8				
	2.13.2	Queue Le	ength for Unsignalized Intersections	2-81	
	2.13.3	Offset Let	ft Turn Lanes	2-82	
2.14		-		2-85	
	2.14.1	Limited A	2_85		
	2.14.2		ges penings at Interchanges		
	2.14.3		dths		
		·····			

2.15	Lighting C	Criteria	2-89		
2.16	Four-Lane High-Speed Suburban Arterial Highways				
	2.16.1	Design Speed	2-93		
	2.16.2	Pedestrian and Bicycle Facilities	2-93		
	2.16.3	Medians	2-93		
	2.16.4	Friction Course	2-93		
	2.16.5	Border Width	2-93		
	2.16.6	Grades	2-93		
	2.16.7	Horizontal Curves	2-93		
	2.16.8	Superelevation	2-94		
	2.16.9	Horizontal Clearance	2-95		
	2.16.10	Monitoring	2-95		
2.17	High-Speed Urban Arterial Highways				
	2.17.1	Design Speed	2-97		
	2.17.2	Curbs	2-97		
	2.17.3	Pedestrian and Bicycle Facilities	2-97		
	2.17.4	Medians	2-98		
	2.17.5	Shoulders	2-98		
	2.17.6	Friction Course	2-98		
	2.17.7	Border Width	2-98		
	2.17.8	Grades	2-98		
	2.17.9	Horizontal Curves	2-99		
	2.17.10	Superelevation	2-99		
	2.17.11	Horizontal Clearance	2-99		
Standar	ds for Low	and High Volume Highways in Annual Average			
Daily Vo	lumes		2-101		

Tables Table 2.1.1	Lane Widths	2-7
Table 2.1.2	Lane Widths - Special	
Table 2.1.3	Ramp Widths	
Table 2.1.4	Maximum Algebraic Difference in Cross Slope at	
	Turning Roadway Terminals	.2-13
Table 2.2.1	Median Widths	.2-17
Table 2.3.1	Shoulder Widths and Slopes - Freeways	.2-21
Table 2.3.2	Shoulder Widths and Slopes - Arterials Divided	.2-22
Table 2.3.3	Shoulder Widths and Slopes - Arterials Undivided	.2-23
Table 2.3.4	Shoulder Widths and Slopes - Collectors Divided and Undivided	2-24
Table 2.4.1	Roadside Slopes	.2-28
Table 2.5.1	Highways with Flush Shoulders	.2-30
Table 2.5.2	Highways with Curb or Curb and Gutter in Urban Areas	.2-31
Table 2.6.1	Maximum Grades	
Table 2.6.2	Maximum Change in Grade Without Vertical	
	Curves	.2-34
Table 2.6.3	Criteria for Grade Datum	.2-35
Table 2.6.4	Grade Criteria for Curb and Gutter Sections	.2-35
Table 2.7.1	Minimum Stopping Sight Distance	.2-37
Table 2.7.2	Minimum Passing Sight Distance	.2-38
Table 2.8.1a	Maximum Deflections Without Horizontal Curves	.2-41
Table 2.8.1b	Maximum Deflection for Through Lanes Through Intersections	.2-41
Table 2.8.2a	Length of Horizontal Curves	.2-42

Table 2.8.2b	Arc Length (in feet) of Compound Curves with One-Half/Double Radii - Turning Roadways	2-42
Table 2.8.3	Maximum Curvature of Horizontal Curve (Using Limiting Values of "e" and "f")	2-43
Table 2.8.4	Maximum Horizontal Curvature Using Normal Cross Slopes (-0.02)	2-43
Table 2.8.5	Minimum Lengths of Crest Vertical Curves Based on Stopping Sight Distance	2-45
Table 2.8.6	Minimum Lengths of Sag Vertical Curves Based on Stopping Sight Distance and Headlight Sight Distance	2-46
Table 2.9.1	Superelevation Rates for Rural Highways, Urban Freeways and High Speed Urban Highways (e _{max} =0.10)	2-48
Table 2.9.2	Superelevation Rates for Urban Highways and High Speed Urban Streets (e _{max} = 0.05)	2-50
Table 2.9.3	Superelevation Transition Slope Rates for Rural Highways, Urban Freeways and High Speed Urban Highways	2-52
Table 2.9.4	Superelevation Transition Slope Rates for Urban Highways and High Speed Urban Streets	2-52
Table 2.10.1	Vertical Clearances for Bridges	2-57
Table 2.10.2	Minimum Vertical Clearances for Signs	2-58
Table 2.10.3	Minimum Vertical Clearances for Signals	2-58
Table 2.10.4	Minimum Vertical Clearances for Overhead Dynamic Message Signs (DMS)	2-58
Table 2.10.5	FAA Notification Requirements	2-61
Table 2.11.1	Horizontal Clearance for Traffic Control Signs	2-64
Table 2.11.2	Horizontal Clearance for Light Poles	2-64
Table 2.11.3	Horizontal Clearance for Utility Installations	2-65

Design Geometrics and Criteria

Table 2.11.4	Horizontal Clearance to Signal Poles and Controller Cabinets for Signals	2-66
Table 2.11.5	Horizontal Clearance to Trees	2-66
Table 2.11.6	Horizontal Clearance to Bridge Piers and Abutments	2-66
Table 2.11.7	Horizontal Clearance to Railroad Grade Crossing Traffic Control Devices	2-67
Table 2.11.8	Horizontal Clearance to Drop-off and Canal Hazards	2-67
Table 2.11.9	Horizontal Clearance to Other Roadside Obstacles	2-67
Table 2.11.10	Recoverable Terrain	2-68
Table 2.14.1	Ramp Widths - Turning Roadways	2-87
Table 2.15.1	Conventional Lighting - Roadways	2-89
Table 2.15.2	Highmast Lighting - Roadways	2-89
Table 2.15.3	Underdeck Lighting - Roadways	2-90
Table 2.15.4	Rest Area Lighting	2-90
Table 2.15.5	Mounting Height Restrictions	2-90

Figures		
Figure 2.0.1	Partial Bridge Sections *	2-3
Figure 2.0.2	Bridge Section *	2-4
Figure 2.0.3	Partial Bridge Sections *	2-5
Figure 2.0.4	Bridge Section *	2-6
Figure 2.1.1	Standard Pavement Cross Slopes	2-12
Figure 2.3.1	Shoulder Superelevation	2-25
Figure 2.3.2	Typical Paving Under Bridge	2-26
Figure 2.9.1	Superelevation Rate For Rural Highways, Urban Freeways and High Speed Urban Highways (e max =0.10)	2-49
Figure 2.9.2	Superelevation Rates for Urban Highways and High Speed Urban Streets (e _{max} = 0.05)	2-51
Figure 2.10.1	Clearances – Rural and Urban Interstates (Freewa Arterials and Collectors, with Projected 20-Year ADT of 1500 or Greater	
Figure 2.10.2	Clearances – Rural Arterials and Collectors with Projected 20-Year ADT of Less than 1500	2-54
Figure 2.10.3	Clearances – Urban Arterials and Collectors (Without Curb and Gutter)	2-55
Figure 2.10.4	Clearances – Urban Arterials and Collectors (Curb and Gutter)	2-56
Figure 2.11.1	Horizontal Clearance to Guardrail	2-69
Figure 2.12.1	Bridge Traffic Railings – "F" Shapes	2-72
Figure 2.12.2	Bridge Traffic Railings – Vertical Shapes	2-73
Figure 2.12.3	Bridge Traffic Railings – Other Shapes	2-74
Figure 2.12.4	Bridge Traffic Railings – Sound Barrier Combination	2-75

Figure 2.12.5	Bridge Railing and Separators – Median Traffic Railing and Separators	.2-76
Figure 2.12.6	Bridge Fencing for Traffic Railings	.2-77
Figure 2.12.7	Bridge Railing – Pedestrian / Bicycle Railing	.2-78
Figure 2.12.8	Bridge Fencing for Pedestrian Railing	.2-79
Figure 2.12.9	Enclosed Bridge Fencing for Pedestrian Railing	.2-80
Figure 2.13.1	Typical Opposing Left Turns (22' Median with Negative 10' Offset)	.2-82
Figure 2.13.2	Typical Opposing Left Turns (22' Median with Negative 1' Offset)	.2-83
Figure 2.13.3	Left Turn Offset Guidelines	.2-83
Figure 2.16.1	Curb and Gutter Section	.2-92
Figure 2.16.2	Flush Shoulder Section	.2-92
Figure 2.16.3	Superelevation Rates for High-Speed Urban or Suburban Sections	.2-94

Chapter 2

Design Geometrics and Criteria

2.0 General

The implementation of design criteria is outlined in the following text.

1. **Design Criteria:** The design criteria presented in this manual are intended as the principal source of criteria for the design of new construction or major reconstruction projects on the Florida State Highway System.

These criteria are presented by subject for major design elements as fixed values or a range of acceptable values as defined by qualifiers.

Where design criteria appear in the **Design Standards**, they will be consistent with the criteria in this manual. In addition, some criteria will remain in the other chapters of this manual. When conflicts are discovered, they should be brought to the attention of the State Roadway Design Engineer or State Structures Design Engineer, as applicable, for resolution.

On reconstruction projects, existing project features which were constructed to meet minimum metric design criteria, but are mathematically slightly less than equivalent minimum English design criteria, do not require design exceptions or variations to remain.

Design criteria for Resurfacing, Restoration, and Rehabilitation (RRR) are presented in *Chapter 25* of this volume and are applicable only on programmed RRR projects.

Facilities on the Florida Intrastate Highway System (FIHS) are subject to special standards and criteria for number of lanes, design speed, access, level of service, and other requirements. These are identified in *Topic No. 525-030-250, Procedure for the Development of the Florida Intrastate Highway System.*

Design Criteria for roads that are not part of the State Highway System should be obtained from the *Manual of Uniform Minimum Standards for Design, Construction and Maintenance for Streets and Highways* (commonly known as the *"Florida Greenbook"*), *Topic No. 625-000-015*.

2. **Design Controls:** Design controls are characteristics and conditions that influence or regulate the selection of the criteria for project standards. It is the designer's responsibility to recognize and apply those controls applicable to the project.

- 3. **Design Standards:** The specific values selected from the design criteria become the design standards for a design project. These standards will be identified and documented by the designer.
- 4. **Project Parameters:** The properties or specific conditions with limits which require modification of design standards within these limits. The designer is responsible for establishing and documenting any project parameters and their limits, as part of the justification for deviations from project standards.

Many design standard considerations are related directly to the design speed, including vertical and horizontal geometry and required sight distances. The minimum design values are very closely related to traffic safety and cannot be compromised without an approved design exception or design variation. See *Chapter 23* of this volume.

Roadway and bridge typical sections developed for projects must reflect the values and properties outlined in Items 1 - 4 of this section. These typical sections shall include the location and limits of such features as lanes, medians, shoulders, curbs, sidewalks, barriers, railings, etc. **Section 16.2.3** of this volume gives the requirements for approval and concurrence of typical section packages.

Coordination is of primary importance on projects that contain both roadway and bridge typical sections. The Roadway and Structures Offices must address the compatibility of the typical section features mentioned above, and provide for an integrated design and review process for the project.

Example roadway typical sections are included in the exhibits in the back of the manual. Partial bridge sections, *Figures 2.0.1 - 2.0.4*, provide criteria regarding lanes, medians, and shoulders for various facilities. Subsequent sections of this chapter contain specific information and criteria regarding these and other typical section elements, as well as geometric features of both roadways and bridges.




Figure 2.0.1 Partial Bridge Sections *







Figure 2.0.2 Bridge Section *



nc K









2.1 Lanes

Florida Department of Transportation (FDOT) criteria for lane widths and pavement slopes are given by highway type and area, through lanes, auxiliary lanes and other special lanes.

2.1.1 Through or Travel Lanes

Standard practice is to provide lane widths as wide as practical, up to 12 feet. See Table 2.1.1.

LANE WIDTHS (FEET)							
FACILI	ГҮ	THROUGH	AUXILIARY				
ТҮРЕ	AREA	OR TRAVEL	SPEED CHANGE	TURNING (LT/RT/MED)	PASSING	CLIMBING	
	Rural	12	12			12	
FREEWAY	Urban	12	12			12	
	Rural	12	12	12	12	12	
ARTERIAL	Urban	12 ₁	12 ₁	12 _{1,4}	12 ₁	12	
	Rural	12 ₆	11 ₂	11 _{2,4}	11 _{2,5}	12	
COLLECTOR	Urban	11 ₃	11 ₃	11 _{3,4}	11 ₃	12	

Table 2.1.1 Lane Widths

1. 11 ft. permitted on non-FIHS roads if one of these conditions exist:

- a. R/W and existing conditions are stringent controls
- b. Facility operates on interrupted flow conditions
- c. Design speed 40 mph or less
- d. Intersection capacity not adversely affected
- e. Truck volume 10% or less
- 2. 12 ft. lanes for all 2-lane rural.
- 3. 12 ft. lanes in industrial areas when R/W is available.
- 4. With severe R/W controls, 10 ft. turning lanes may be used where design speeds are 40 mph or less and the intersection is controlled by traffic signals. Median turn lanes shall not exceed 15 ft.
- 5. 12 ft. when truck volume more than 10%.
- 6. 11 ft. for low volume AADT.

2.1.2 Other Lane Widths

Collector-distributor lanes and auxiliary lanes for speed change, turning, storage for turning, weaving and other purposes supplementary to through-traffic movement should be of the same width as the through lanes. See *Table 2.1.2*.

LANE WIDTHS (FEET)							
FACILITY	/		SPECIAL				
ТҮРЕ	AREA	HOV₁	BICYCLE	OFF SYSTEM DETOUR	URBAN MULTI- PURPOSE ₅		
	Rural	12		11 ₄			
FREEWAY	Urban	12		11 ₄			
	Rural	12	5 ₂	11			
ARTERIAL	Urban	12	4 ₃	11	8 6		
	Rural		5 ₂	11			
COLLECTOR	Urban		4 ₃	11	8 ₆		

Table	212	I ane	Widths	- S	necial
Iane	Z . I. Z	Lane	WILLIIS	- 0	peciai

1. Separated or concurrent flow.

2. Designated or undesignated bike lane on shoulder pavement.

3. Designated or undesignated. See **Section 8.4.1** of this volume.

4. For Freeway detours, at least one 12 ft. lane must be provided in each direction.

- 5. Urban multi-purpose lanes are usually used as refuge lanes but may be used for loading zones, bus stops, emergency access and other purposes. Parking that adversely impacts capacity or safety is to be eliminated whenever practical. Standard parking width is measured from lip of gutter, with a minimum width of 8 ft. measured from face of curb.
- 6. 10 ft. to 12 ft. lanes for commercial and transit vehicles.

2.1.3 Ramp Traveled Way Widths

Ramp widths for tangent and large radii (500 ft. or greater) sections are given in **Table 2.1.3**. Ramp widths in other areas such as terminals are controlled by the curvature and the vehicle type selected as the design control and are given in **Table 2.14.1**, **Ramp Widths**. Typical details for ramp terminals are provided in the **Design Standards**.

RAMP WIDTHS (RAMP PROPER) FOR TANGENT AND LARGE RADII (≥ 500 ft.) SECTIONS						
ONE LANE RAMPS	15 ft.					
TWO LANE RAMPS	24 ft.					

For ramp widths at turning roadways see *Table 2.14.1*.

2.1.4 Pedestrian, Bicycle and Public Transit Facilities

2.1.4.1 Sidewalks

Sidewalks shall be considered on all projects in urbanized areas. Although the standard sidewalk width is 5 feet, it may be desirable to create wider sidewalks in business districts, near schools, transit stops, or where there are other significant pedestrian attractors. The District Pedestrian/Bicycle Coordinator shall be consulted during design to establish appropriate pedestrian elements on a project-by-project basis. *Chapter 8* of this volume contains additional guidelines for sidewalks.

2.1.4.2 Bicycle Facilities

Bicycle facilities shall be considered on all projects. Within an urbanized area or on projects with curb and gutter, the bicycle facility shall be either designated or undesignated bike lanes. Bicycle lanes on the approaches to bridges should be continued across the structure. On projects in areas without curb, either a bike lane or a paved shoulder shall be provided as a bicycle facility. When a project includes an intersection with a right turn lane, a bike lane is to be included between the through lane and the right turn lane. When a project includes a bus bay, a bike lane is to be included between the through lane and the bus bay.

The District Pedestrian/Bicycle Coordinator should be consulted during design to establish appropriate bike elements, if any, on a project-by-project basis.

Chapter 8 of this volume contains definitions for designated and undesignated bicycle lanes as well as additional guidelines for the accommodation of bicycles.

2.1.4.3 Public Transit Facilities

Coordinate with the District Modal Development Office and local transit agency for the need for public transit facilities. *Chapter 8* of this volume contains additional guidelines for street side bus stop facilities, location and design.

2.1.5 Cross Slopes

For roadways, the maximum number of travel lanes with cross slope in one direction is three lanes. This maximum may be increased to four lanes for curb and gutter roadways with four travel lanes in the same direction (See *Figure 2.1.1*). The algebraic difference in cross slope between adjacent through lanes should not exceed 0.04. The maximum algebraic difference in cross slope between a through lane and an auxiliary lane at a turning roadway terminal is given in *Table 2.1.4*. *Chapter 4* on *Roadside Safety* and *Chapter 8* on *Pedestrian, Bicycle and Public Transit Facilities* (this volume) contain additional procedures and guidelines on slope design.

Cross slopes on bridges shall be on a uniform, straight-line rate, typically 0.02, in each traffic direction, with no break in slope. The straight-line slope shall be applied uniformly over all travel lanes and required shoulders in each direction of travel. Bridges with one-way traffic shall have one, uniform cross slope, while bridges with two-way traffic may be designed with a crowned bridge deck section.

This cross slope criteria applies to all bridge decks whether of cast-in-place concrete, precast concrete, or open steel decking.

Transitions shall be used to adjust for differences in cross slope between the approach roadway section and the required straight-line slope for bridge decks. Whenever possible the transition should be accomplished on the roadway section, outside the limits of the bridge and approach slabs. This will require detailing of the transition(s) in the roadway plans. Coordination between the Roadway, Drainage and Structures designers in the development of transitions is required to ensure compatibility and harmonizing at bridge approaches.




Figure 2.1.1 Standard Pavement Cross Slopes




Table 2.1.4 Maximum Algebraic Difference inCross Slope at Turning Roadway Terminals

2.1.6 Roadway Pavement

The type of pavement usually is determined by analysis of the volume and composition of traffic, the soil conditions, the availability of materials, the initial cost and the estimated cost of maintenance.

Criteria and procedures for selecting the type of pavement and the structural design of the various surfacing courses are discussed in the Department's pavement design manuals.

2.1.6.1 Alternative Roadway Paving Treatments

Alternative paving treatments such as patterned/textured pavement may be used to accent the roadway in accordance with the *FDOT Specifications*. Architectural pavers, however, shall not be used on the traveled way of the State Highway System.

Patterned/textured pavement treatments may be applied to asphalt or concrete pavements. Patterns are defined as visible surface markings while imprinted textures are defined as palpable surface markings. The location, pattern/texture type (brick, stone, etc.), and coating color shall be shown in the plans if any patterned and/or textured treatment is used. When the use of any of these treatments is desirable for aesthetic purposes, they should be limited to low speed facilities.

All alternative roadway paving treatments must meet *ADA* requirements. Architectural pavers are restricted to local side streets (35 mph or less), medians and islands, curb extensions, sidewalks, borders, etc.

2.1.7 Transitions of Pavement Widths

When new pavement widths are not substantially greater than the joining pavement, grade differentials are slight and future widening is expected, striped transitions may be considered. An alternative approach is an abrupt change in width, with appropriate pavement markings, reflectors and rumble strips. The **Design Standards** contain additional criteria and details.

2.1.8 Number of Lanes on the State Highway System

For the number of lanes to be provided on the State Highway System, see the *Florida Intrastate Highway System Program Development Procedure* (*Topic No. 525-030-255*), and *Section 335.02(3)* of the *Florida Statutes*.

Nothing in **s. 335.02(3)**, **F.S**., precludes a number of lanes in excess of ten lanes. However, before the Department may determine the number of lanes should be more than that, the availability of right of way and the capacity to accommodate other modes of transportation within existing rights of way must be considered.

Exceptions to this Procedure (*Topic No.: 525-030-255; s. 335.02(3), F.S.*) will be addressed on a case-by-case basis, with final approval resting with the Secretary of Transportation.

THIS PAGE LEFT BLANK INTENTIONALLY

2.2 Medians

2.2.1 Median Width for Roadways

Median widths for roadways are given in *Table 2.1.1*.

MEDIAN WIDTHS (FEET)						
TYPE FACILITY	WIDTH					
FREEWAYS						
Interstate, Without Barrier	64 ₁					
Other Freeways, Without Barrier						
Design Speed ≥ 60 mph	60					
Design Speed < 60 mph	40					
All, With Barrier, All Design Speeds	26 ₂					
ARTERIAL AND COLLECTORS						
Design Speed > 45 mph	40					
Design Speed ≤ 45 mph	22 ₃					
Paved And Painted For Left Turns	12 4					

Median width is the distance between the inside (median) edge of the travel lane of each roadway.

- 1 88 ft. when future lanes planned.
- 2. Based on 2 ft. median barrier and 12 ft. shoulder.
- 3. On reconstruction projects where existing curb locations are fixed due to severe right of way constraints, the minimum width may be reduced to 19.5 ft. for design speeds = 45 mph, and to 15.5 ft. for design speeds ≤ 40 mph.
- 4. Restricted to 5-lane sections with design speeds ≤ 40 mph. On reconstruction projects where existing curb locations are fixed due to severe right of way constraints, the minimum width may be reduced to 10 ft. These flush medians are to include sections of raised or restrictive median for pedestrian refuge and to conform to *Section 2.2.2* of this volume and the Access Management Rules.

2.2.2 Multilane Facility Median Policy

All multilane facilities shall be designed with a raised or restrictive median except four-lane sections with design speeds of 40 mph or less. Facilities having design speeds of 40 mph or less are to include sections of raised or restrictive median for enhancing vehicular and pedestrian safety, improving traffic efficiency, and attainment of the standards of the Access Management Classification of that highway system.

2.2.3 Median Treatments on Bridges

For divided highways, the District will determine the desired distance between structures. *Figures 2.0.1* and *2.0.3* in this chapter, indicate that a full deck is recommended if the open space between the bridges is 20 ft. or less and required when less than 10 ft. For structures with less than 20 ft. of clearance, consult with District Structures Design and Facilities Maintenance before making a final decision.

Each District Office, in deciding on a single structure deck or twin bridges, must take into account the inspection and maintenance capabilities of its personnel and equipment. If the total width for a single structure exceeds the capacity of district maintenance equipment (approximately 60 ft. reach), twin structures may be specified and the open distance between structures determined by the practical capability of the maintenance and inspection equipment. This is particularly important for girder superstructures because those areas that cannot be reached by topside equipment might require catwalks, ladders or other access features. Such features will add to the cost of superstructures and must be accounted for in the initial selection of alternates.

2.3 Shoulders

Roadway shoulder width, slope and superelevation criteria are provided in the criteria tables and figures. Paved outside shoulders, 5 ft. in width, are required on all new construction, reconstruction and lane addition projects for all highways except freeways, which generally require a 10 ft. paved outside shoulder.

Specific widths have also been adopted for interstate, expressway, single and double lane ramps and collector-distributor road shoulders. Total shoulder widths, paved shoulder widths, and widths of paved shoulder separations between through pavement edge and the near edge of any shoulder gutter are given for both right (outside) and left (inside) edges of the roadway. See **Tables 2.3.1 – 2.3.4** and **Figures 2.3.1 – 2.3.2**.

The Design Standards, Index 104, provides additional details for paved shoulders.

Figures 2.0.1 and *2.0.2* include criteria for shoulder widths on various bridge sections. Where these widths differ from those required for roadways or ramps, decisions about the final values chosen for the project must be coordinated between the Roadway and Structures Design Offices.

Generally, the outside shoulder width for bridges should be the same width as the approach roadway shoulder up to a maximum of 10 feet. On roadway alignments having 12 ft. shoulders with continuous barrier walls and closely spaced bridges, a 12 ft. bridge shoulder width may be considered. The decision to use 12 ft. bridge shoulder widths should be coordinated with the District Design Engineer.

For shoulder cross slope criteria on bridges see **Section 2.1.5** of this chapter.

It is recommended to pave the median section and a 10 foot outside shoulder under overpass bridges. In addition, miscellaneous asphalt should be placed from the paved shoulder to the slope pavement. This pavement will provide additional safety, enhance drainage, reduce maintenance and improve appearance. See *Figure 2.3.2*.

For paved shoulders at railroad crossings see the Design Standards, Index 560.

THIS PAGE LEFT BLANK INTENTIONALLY

	WIDTH (FEET)								SLO	PES	
		WITHO	UT SHOU	JLDER G	UTTER	WITH	SHOUL	TTER			
HIGHWAY TYPE		FULL WIDTH PAVED WIDTH		FULL	FULL WIDTH PAVED WIDTH			NOR	IAL 1		
		Outside	Median or Left	Outside	Median or Left	Outside	Median or Left	Outside	Median or Left	Outside	Media or Left
	4-Lane or More	12	12	10	10	15.5	15.5	8	8		0.06
	3-Lane	12	12	10	10	15.5	15.5	8	8	0.06	0.05
	2-Lane	12	8	10	4	15.5	13.5	8	6		0.05
	HOV Lane	N/A 4	14	N/A 4	10	N/A 4	N/A 4	N/A 4	N/A 4	N/A 4	0.05
	1-lane Barrier- Separated HOV Lane ₅	6	4 5	6	4 5	N/A 4	N/A 4	N/A 4	N/A 4	Same as Lane	Same as Lane s
	2-lane Barrier- Separated HOV Lane ₅	10	6 ₅	10	6 ₅	N/A 4	N/A 4	N/A 4	N/A 4	Same as Lane	Same as Lane
F	1-Lane Ramp	6	6	4	2	11.5	11.5	4 ₃	4	0.06	0.05
R E	2-Lane Ramp Non-Interstate	10	8	8	4	15.5	13.5	8	6		
E W	2-Lane Ramp Interstate	12	8	10	4	15.5	13.5	8	6		
A Y	C-D Road 1-Lane	6	6	4	2	11.5	11.5	4	4		0.05
S Lanes	C-D Road 2-Lane	12	8	10	4	15.5	13.5	8	6		
One Way)	C-D Road 3-Lane	12	12	10	10	15.5	15.5	8	8		
- *	C-D Road > 3-Lane	12	12	10	10	15.5	15.5	8	8		0.06
	Auxiliary Lane Climbing & Weaving	12	N/A 4	10	N/A 4	15.5	N/A 4	8	N/A 4		N/A 4
	Auxiliary Lane Mainline Terminal: 1-Lane Ramp 2-Lane Ramp	12 12	N/A 4 N/A 4	10 10	N/A 4 N/A 4	15.5 15.5	N/A 4 N/A 4	8 8	N/A 4 N/A 4		N/A 4 N/A 4
	Frontage Road	For local	roads an		ee the FD	OT Manu treets and			num Stan	dards for	

Table 2.3.1 Shoulder Widths and Slopes - Freeways

3. Shoulder pavement less than 6 ft. in width that adjoins shoulder gutter shall be the same type, depth and slope as the ramp pavement.

This does not mean that a shoulder is unnecessary; rather, shoulder is not typically present at this location (i.e., it is not required 4. when adjacent to the through lane).

5. If median side of HOV lane is not barrier-separated, use median shoulder requirements for a standard HOV lane. Refer to AASHTO's Guide for High-Occupancy Vehicle Facilities for additional information.

					WIDTH (
		WITHOUT SHOULDER GUTTER					WITH SHOULDER GUTTER				PES
HIG	GHWAY TYPE	FULL	WIDTH	PAVED	PAVED WIDTH		WIDTH	PAVED			MAL 1
			Median		Median		Median		Median		Median
		Outside	or Left	Outside 2	or Left	Outside	or Left	Outside	or Left	Outside	or Left
	4-Lane	12 10 8	12 10 8	5 5 5	4 4 4	15.5 15.5 15.5	15.5 15.5 13.5	8 8 6	8 8 6	0.06	0.06
	3-Lane	12 10 8	12 10 8	5 5 5	0 4 0 4 0 4	15.5 15.5 13.5	15.5 15.5 13.5	8 8 6	8 8 6	0.00	0.05
_	2-Lane	12 10 8	8 8 6	5 5 5	0 4 0 4 0 4	15.5 15.5 13.5	13.5 13.5 11.5	8 8 6	6 6 4		
A	1-Lane Ramp	6	6	5	2	11.5	11.5	4 ₃	4		
R T	2-Lane Ramp	10	6	5	2	15.5	13.5	8	6		
E R	C-D Road 1-Lane	6	6	5	2	11.5	11.5	4	4		
I A	C-D Road 2-Lane	8	6	5	0	13.5	11.5	6	4		
L S Divideo	Auxiliary Lane Climbing & Weaving d	Same As Travel Lanes	N/A 5	Same As Travel Lanes	N/A 5	Same As Travel Lanes	N/A ₅	Same As Travel Lanes	N/A 5		N/A 5
(Lanes One Way)	Mainline Terminal:	8 12	N/A ₅ N/A ₅	5 10	N/A 5 N/A 5	11.5 15.5	N/A ₅ N/A ₅	4 8	N/A 5 N/A 5		N/A 5 N/A 5
	Auxiliary Lane At-Grade Intersection	Same As Travel Lanes	Same As Travel Lanes	5	0	11.5	N/A 5	4	N/A 5		0.05 - 0.06
	Frontage Road	For local	ectors Tab roads and ction and N	streets see					num Stand	dards for	Design,
1. Sh	noulders shall extend 4	4 ft. bevond	the back o	f shoulder o	outter and	have a 0	.06 slope	back towa	rd the autt	er.	
2. Sh	noulder shall be paved the crossing measure	full width th	hrough rail-h	nighway at-g	grade cros	ssings, ext	ending a i	minimum o	distance of	50 ft. on e	
	noulder pavement less avement.	than 6 ft. i	n width and	adjoining s	shoulder g	utter shal	l be the sa	ame type,	depth and	slope as t	the ramp
lov	aved 2 ft. wide where to w point, and (b) on the e PC and PT.										
	LEGENI FOR VALUES	Х	High Vo Normal Low Vol	Volume Hig	ghways						
	nis does not mean that nen adjacent to throug		is unnecess	sary; rather,	, shoulder	is not typi	cally prese	ent at this	location (i.e	e., it is not	required

Table 2.3.2 Shoulder Widths and Slopes - Arterials Divided

			WIDTH	S (FEET)		SLOPES					
HIGHW	ΑΥ ΤΥΡΕ		IOUT R GUTTER	W SHOULDE	NORMAL 1						
		FULL WIDTH	PAVED WIDTH 2	FULL WIDTH	PAVED WIDTH						
	Multilane 3	12 10 8	5 5 5	15.5 15.5 13.5	8 8 6						
	2-Lane	12 10 8	5 5 5	15.5 15.5 13.5	8 8 6						
ARTERIALS Undivided (lanes Two-Way)	Auxiliary Lane At-Grade Intersections	Same As Travel Lanes	5	11.5	4	0.06					
	Frontage Road	Road See COLLECTORS Table 2.3.4. For local roads and streets see the FDOT Manual of Uniform Minimum Standards for Design, Construction and Maintenance for Streets and Highways.									
1.	Shoulders shall extreme toward the gutter		ond the back of	shoulder gutte	er and have a 0.0	06 slope back					
2.	Shoulder shall be paved full width through rail-highway at-grade crossings, extending a minimum distance of 50 ft. on each side of the crossing measured from the outside rail. For additional information see the Design Standards, Index No. 560 and 17882.										
3.	All multilane facili	ties shall confo	orm with Secti	on 2.2.2 of this	s volume.						
	FOR X	Normal Volu	ime Highways		FOR XNormal Volume Highways						

Table 2.3.3 Shoulder Widths and Slopes - Arterials Undivided

		(FEET)									
		WITHO	UT SHO	ULDER G	WITH	SHOUL	TTER	SLOPES			
HIGHWAY TYPE		FU WID			PAVED WIDTH		FULL WIDTH		/ED DTH	NORMAL 1	
		Outside	Median Or Left	Outside ₂	Median Or Left	Outside	Median Or Left	Outside	Median Or Left	Outside	Median Or Left
C O L L	3-Lane	12 10 8	12 10 8	5 5 5	0 3 0 3 0 3	15.5 15.5 13.5	15.5 15.5 15.5	8 8 6	8 8 6		
E C T O R S Divided (Lanes One-Way)	2-lane	12 10 8	8 8 6	5 5 5	0 ₃ 0 ₃ 0 ₃	15.5 15.5 13.5	13.5 13.5 11.5	8 8 6	6 6 4	0.06	0.05
	Auxiliary Lane At-Grade Intersection	Same As Travel Lanes	Same As Travel Lanes	5	4	11.5	N/A 5	4	N/A 5		
C O L L	Multilane 4	1: 1/ 8	0	5 5 5	5	15	5.5 5.5 5.5	8 8 6			
E C T O	2-Lane	1: 1) 8	0	5 5 5		15.5 15.5 13.5		8 8 6		0.06	
R S Undivided (Lanes Two-Way)	Auxiliary Lane At-Grade Intersection	Saı A Tra Lar	s vel	Sar A: Tra Lan	s vel	11.5		4			


Table 2.3.4 Shoulder Widths and Slopes - Collectors Divided and Undivided

3. The median shoulder may be paved 2 ft. wide in areas of the State where establishing and maintaining turf is difficult; however, shoulders shall be paved 4 ft. wide (a) in sag vertical curves, 100 ft. minimum either side of the low point, and (b) on the low side of superelevated traffic lanes, extending through the curve and approximately 300 ft. beyond the PC and PT.

4. All multilane facilities shall conform with **Section 2.2.2** of this volume.

LEGEND	XHigh Volume Highways
FOR	XNormal Volume Highways
VALUES	XLow Volume Highways

5. This does not mean that a shoulder is unnecessary; rather, shoulder is not typically present at this location (i.e., it is not required when adjacent to through lane).








Figure 2.3.2 Typical Paving Under Bridge

2.3.1 Limits of Friction Course on Paved Shoulders

Friction courses on limited access facilities shall be extended 8 inches onto both the median and outside paved shoulders of roadways.

Friction courses shall be extended the full width of the paved shoulder on non-limited access highways to accommodate bicyclist usage.

2.3.2 Shoulder Warning Devices (Rumble Strips)

The safety of freeways and other limited access facilities on the State highway system is to be enhanced by the installation of shoulder warning devices in the form of rumble strips. Projects on limited access facilities shall include the construction of ground-in rumble strips. Several types of applications have been tested. The ground-in strips provide the desired warning to the driver and consistency in application has been possible using this construction process.

These ground-in strips are installed using two patterns. The skip array is the standard array. These are used on both inside and outside shoulders on divided highway sections. The continuous array shall be constructed in advance of bridge ends for a distance of 1000 ft. or back to the gore recovery area for mainline interchange bridges. Other areas may be specified in plans.

Methods and types of application other than described above and in the **Design Standards, Index 518**, shall not be used unless concurred in by the State Roadway Design Engineer. Approval will be considered only with sufficient documented justification for deviation from the standard.

The **Design Standards, Index 518**, has been prepared to provide all needed details. This index also gives standards for raised rumble strips for use at structures where the bridge shoulder width is less than the width of the useable shoulder on the approach roadway. Notes for locations of raised rumble strip applications are also included on the index.

2.4 Roadside Slopes

Criteria and details are included in *Table 2.4.1* and in *Chapter 4* of this volume.

RURAL & URBAN FREEWAYS, RURAL ARTERIALS AND COLLECTORS, WITH PROJECTED 20 YEAR AADT OF 1500 OR GREATER			RURAL COLLEC PROJEC LESS TH LOCALS AND CO	ARTERIALS AND CTORS WITH CTED 20 YR. AADT HAN 1500 AND RURAL S, URBAN ARTERIALS OLLECTORS WITHOUT	URBAN ARTERIALS AND COLLECTORS WITH CURB & GUTTER		
	-	GIGN SPEED		ALL SPEEDS	-	IGN SPEED ph OR LESS	
	Height of Fill (feet) *	Rate	Height of Fill (feet) *	Rate	Height of Fill (feet) *	Rate	
Front Slope	0.0 - 5 5 - 10 10 - 20 >20	1:6 1:6 to edge of CZ and 1:4 1:6 to edge of CZ and 1:3 1:2 (with guardrail)	0.0 - 5 5 - 20	1:6 except where R/W is insufficient, then 1:6 to edge of CZ and 1:3 will be permitted 1:6 to edge of CZ and 1:3 except where R/W is insufficient then 1:2 will be permitted	All	1:2 or to suit property owner, not flatter than 1:6. R/W cost must be considered for high fill sections in urban areas	
Back Slope	All	1:4 or 1:3 with a standard width trapezoidal ditch and 1:6 front slope	All	1:4 when R/W permits or 1:3	All	1:2 or to suit property owner. Not flatter than 1:6.	
Transverse Slopes	All	1:10 or flatter (freeways) 1:4 (others)	All	1:4	All	1:4	

* Height of Fill is the vertical distance from the edge of the outside travel lane to the toe of front slope.

2.5 Borders

Border widths for new construction or major reconstruction where R/W acquisition is required are provided in the criteria tables and figures:


On highways with flush shoulders, the border is measured from the shoulder point to the right of way line. This border width accommodates (1) roadside design components such as signing, drainage features, guardrail, fencing and clear zone, (2) the construction and maintenance of the facility and (3) permitted public utilities. See *Table 2.5.1*.

On highways with curb or curb and gutter where clear zone is being provided, border width is to be based on flush shoulder requirements, but is measured from the lip of the gutter (or face of curb when there is not a gutter) to the right of way line. This border width accommodates (1) roadside design components such as signing, drainage features, guardrail, fencing and clear zone, (2) the construction and maintenance of the facility and (3) permitted public utilities. See **Table 2.5.1**.

On highways with curb or curb and gutter in urban areas, the border is measured from the lip of the gutter (or face of curb when there is not a gutter) to the right of way line. This border provides space for a buffer between vehicles and pedestrians, sidewalks with ADA provisions, traffic control devices, fire hydrants, storm drainage features, bus and transit features, permitted public utilities and space for aesthetic features such as sod and other landscape items. See **Table 2.5.2**.

Projects involving bridges will require coordination to match the features of the roadway with those of the bridge.

On existing streets and highways where R/W cannot be acquired or where the decision has been made to simply maintain and preserve the facility, the border area must be reserved for the functional and safety needs of the facility. Extraordinary design effort will be required to meet ADA requirements, driveway construction and the other essential features. Spot R/W acquisitions may be required along the corridor to accommodate these essential components. The absolute minimum border under these conditions is 8 feet.





1. Measured from the edge of the outside traffic lane to the R/W. Width may be reduced in area of crossroad terminal as long as design meets requirements for clear zone, horizontal clearance, drainage, maintenance access, etc.

R/W Bord Buffer	ler	Face of Curb *					
Strip Sidewalk	Buffer Strip						
]						
* Border width measured fron there is not a gutter.	n lip of gutter (shown) or fr	om face of curb when					
	BORDER						
	MINIMUM WIDTH (FEET)						
TYPE FACILITY	TRAVEL LANES AT CURB OR CURB AND GUTTER	BIKE LANES OR OTHER AUXILIARY LANES AT CURB OR CURB AND GUTTER					
ARTERIALS COLLECTORS Design Speed = 45 mph	14	12					
ARTERIALS COLLECTORS Design Speed ≤ 40 mph	12	10					
URBAN COLLECTOR STREETS Design Speed ≤ 30 mph	10	8					

Table 2.5.2 Highways with Curb or Curb and Gutter in Urban Areas

2.5.1 Limited Access Facilities

On Limited Access Facilities, the border is measured from the edge of the outside traffic lane to the right of way line. This width may be reduced in the area of a crossroad terminal, as long as the design meets the requirements for clear zone, horizontal clearance, drainage, maintenance access, etc.

Limited access facilities shall be contained by fencing, or in special cases, walls or barriers. These treatments shall be continuous and appropriate for each location. Treatment height and type may vary under special conditions. The treatment is typically placed at or near the limited access right of way line, but location may be adjusted based on site-specific conditions (i.e., ponds, trees, bridges, etc.). Placement information and additional data is included in the **Design Standards, Indexes 450, 451, and 452**.

2.6 Grades

The profile grade line defines the vertical alignment for roadway and bridge construction. As with other design elements, the characteristics of vertical alignment are influenced greatly by basic controls related to design speed, traffic volumes, functional classification, drainage and terrain conditions. Within these basic controls, several general criteria must be considered. See **Tables 2.6.1 – 2.6.4**.

Minimum clearances for structures over railroads are given in *Table 2.10.1*. Additional information, including at-grade crossings, is given in *Chapter 6* of this volume.

The Department's minimum for structure clearance over all highways is given in the criteria tables and figures. Exceptions to this policy shall be permitted only when justified by extenuating circumstances and approved as a variation or exception.

The clearance required for the roadway base course above the Base Clearance Water Elevation is given in the criteria tables and figures.

The limiting relationship between the pavement elevation and the Design Flood Elevation is discussed in *Section 4.4* of the *FDOT Drainage Manual (Topic No. 625-040-002)*.

Grades for structures over water shall be designed to provide the desirable vertical clearance as stipulated in *Section 2.10* of this chapter.

The **Design Standards** lists utility clearances and minimum covers and maximum fill heights for all types of culverts.

	MAXIMUM GRADES IN PERCENT												
		DESIGN SPEED (mph)											
TYPE OF HIGHWAY	AREA		F	LAT T	ERRA	IN			ROI	LING	TERF	RAIN	
		30	40	45	50	60	70	30	40	45	50	60	70
FREEWAYS 1	Rural Urban			4	4	3	3				5	4	4
	Rural		5	5	4	3	3		6	6	5	4	4
, u (1 E (1) (E O)	Urban	8	7	6	6	5		9	8	7	7	6	
	Rural	7	7	7	6	5	4	9	8	8	7	6	5
COLLECTORS 3	Urban	9	9	8	7	6	5	11	10	9	8	7	6
	Industrial 2	4	4	4	3	3		5	5	5	4	4	
FRONTAGE ROADS				Requ	ire sa	me crit	eria as	s Colle	ctors.				
RAMPS	DESIGN	SPEE	D (mp	h)	< 2	20	25	to 30 35 to 40		0	45 to	50	
	GRA	DES	(%)		6 to	8	5	to 7		4 to 6		3 to	5
	One-way descending grades on Ramps may be 2% greater, in special cases.												
1. Inters	1. Interstate designed to 70 mph will be restricted to 3% maximum grade.												
2. Areas with significant (10% or more) heavy truck traffic.													
	lane highways te the speeds							ceedeo	d. Critio	cal leng	ths are	those	which

Table 2.6.1 Maximum Grades

DESIGN SPEED (mph)	20	30	40	45	50	60	65	70
MAXIMUM CHANGE IN GRADE IN PERCENT	1.20	1.00	0.80	0.70	0.60	0.40	0.30	0.20

٦

Table 2.6.3 Criteria for Grade Datum

CLEARANCE FOR THE ROADWAY BASE COURSE ABOVE THE BASE CLEARANCE WATER ELEVATION								
TYPE FACILITY REQUIRED CLEARANC								
Freeways and Rural Multilane Mainline	3 ft.							
Ramps (proper)	2 ft.							
Low Point on Ramps at Cross Roads	1 ft.							
Rural Two-lane with Design Year ADT Greater than 1500 VPD	2 ft.							
All Other Facilities Including Urban	1 ft.							

Table 2.6.4 Grade Criteria for Curb and Gutter Sections

GRADES ON CURB AND GUTTER SECTIONS							
Minimum Distance Required between VPI's	250 ft.						
Minimum Grade (%)	0.3 %						

(See Table 2.6.1 for Maximum Grades)

THIS PAGE LEFT BLANK INTENTIONALLY

2.7 Sight Distance

Minimum stopping and passing sight distances are given in *Tables 2.7.1 – 2.7.2*.

	Table 2.7.1 Minimum Stopping Sight Distance													
	MINIMUM STOPPING SIGHT DISTANCE (FEET) (For application of stopping sight distance, use an eye height of 3.5 feet and an object height of 0.5 feet above the road surface)													
DESIGN						GRAD	ES OF	2% OR	LESS					
SPEED (mph)			h	nterstat	te					All Ot	her Fac	cilities		
15											80			
20											115			
25											155			
30											200			
35											250			
40											305			
45											360			
50											425			
55		570									495			
60		645							570					
65		730						645						
70				820				730						
	ADJUSTMENT IN DISTANCE FOR GRADES GREATER THAN 2%													
DESIGN	INCR	EASE II	N LENG	TH FO	r dow	NGRAD	DE (ft.)	DECREASE IN LENGTH FOR UPGRADE (ft.)						
SPEED				Grades	;			Grades						
(mph)	3%	4%	5%	6%	7%	8%	9%	3%	4%	5%	6%	7%	8%	9%
15	0	0	1	2	3	4	5	5	5	6	6	7	7	7
20	1	2	3	5	6	8	10	6	7	8	8	10	10	11
25	3	5	7	10	12	15	18	8	9	11	12	13	14	16
30	5	8	11	15	18	22	27	10	12	14	16	18	20	21
35	7	11	16	21	26	31	37	13	16	19	21	24	26	28
40	10	15	21	28	34	41	49	16	20	24	27	30	33	36
45	18	25	32	40	48	57	67	16	21	25	29	33	37	40
50	21	29	39	49	59	70	82	20	26	32	37	42	46	50
55	25	35	46	58	70	84	98	26	33	39	45	52	57	62
60	28	40	53	68	82	99	116	32	40	48	55	62	69	75
65	37	51	67	83	101	120	140	33	43	52	61	69	77	84
70	41	58	76	95	115	137	161	40	52	62	72	82	91	99

_ _ ----

	Table 2.7.2 Minimum Passing Sight Distance										
	MINIMUM PASSING SIGHT DISTANCE (FEET) (For application of passing sight distance, use an eye height of 3.5 feet and an object height of 3.5 feet above the road surface)										
DESIGN SPEED (mph)	DESIGN SPEED 20 25 30 35 40 45 50 55 60 65 70										
2-Lane, 2-Way Facilities	710	900	1090	1280	1470	1625	1835	1985	2135	2285	2480

Table 2.7.2 Minimum Passing Sight Distance

2.8 Curves

2.8.1 Horizontal Curves

Design speed is the principal factor controlling horizontal alignment. Several geometric standards related to design speed are very specific. Other criteria cannot be defined as specifically and require that judgments be made by designers in consideration of local conditions.

2.8.1.1 Supplemental Alignment Control (Mainline)

On projects which include roadways and bridges, coordination between the Roadway and Structures Design Offices may be necessary for those horizontal alignment issues affecting the location or geometry of the structure(s).

If possible, horizontal curves, PI's and superelevation transitions should not be placed within the limits of a structure or approach slabs. Because of the impact on the structure framing, spiral curves or alignments that result in skews greater than 45 degrees should be avoided. When skews greater than 45 degrees and/or spirals are necessary, specific justification shall be submitted to the District Design Engineer for concurrence, prior to proceeding with the alignment. For alignments that result in skews greater than 45 degrees, alternate framing concepts that relieve the severe skew effect should be considered. This may consist of longer bridges, placing framing members normal to the skew, etc.

Placement of stationing equations within the limits of a structure should be avoided on contract plans. Such equations unnecessarily increase the probability of error in both the design and construction phase.

Further guidelines have been established by the Department for lengths of horizontal curves, maximum deflections without curves, redirection of through lanes at intersections and minimum transition lengths between reverse curves. The criteria given are intended for use in establishing minimum lengths for both rural and urban conditions. See **Tables 2.8.1** – **2.8.4**.

For small deflection angles (5° or less), curves should be suitably lengthened to avoid the distracting appearance of a kink. Curves should be at least 500 ft. long for a central angle of 5° and the minimum increased 100 ft. for each 1° decrease in the central angle (900 ft.

for a 1° central angle). This treatment may not be practical in developed or environmentally sensitive areas or for major modifications of existing facilities.

For design, the aesthetic control given above should be considered where practical, but may be compromised where other considerations warrant such action. Discernment of alignment changes in an urban setting is normally minimal due to the masking effects of development, traffic signs, various items of interest and similar distracting stimuli.

For information on the maximum deflection without a curve, see Table 2.8.1.

When superelevation is required for curves in opposite directions on a common tangent, a suitable distance is required between the curves. This suitable tangent length should be determined as follows:

- 1. 80% of the transition for each curve should be located on the tangent.
- 2. The suitable tangent length is the sum of the two 80% distances, or greater.
- 3. Where alignment constraints dictate a less than desirable tangent length between curves, an adjustment of the 80/20 superelevation transition treatment is allowed (where up to 50% of the transition may be placed on the curve).

The use of compound curves in horizontal alignment should be avoided where simple curves can be used. When compound curves are necessary on open highways, the ratio of the flatter radius to the sharper radius should not exceed 1.5:1. For turning roadways and intersections a ratio of 2:1 (where the flatter radius precedes the sharper radius in the direction of travel) is acceptable.


The length of compound curves for turning roadways when followed by a curve of one-half radius or preceded by a curve of double radius should be as shown in *Table 2.8.2b*.

Table 2.8.1a Maximum Deflections without Horizontal Curves								
MAXIMUM DEFLECTION WITHOUT CURVE (DMS)								
TYPE FACILITY $V \ge 45$ mph $V \le 40$ mph								
Free	eways	0° 45' 00"	N/A					
Arterials and	Without Curb & Gutter	0° 45' 00"	2° 00' 00"					
Collectors	With Curb & Gutter	1° 00' 00"	2° 00' 00"					
Where V=Design Speed (mph)								

Table 2.8.1a Maximum Deflections Without Horizontal Curves

Table 2.8.1b	Maximum I	Deflection
for Through Lane	s Through I	ntersections

Design speed (mph)	20	25	30	35	40	45
Maximum Deflection	16° 00'	11° 00'	8° 00'	6° 00'	5° 00'	3° 00'



LENGTH OF C	URVE (FEET)						
Freeways	30V ₁						
Arterials	15V ₂						
Collectors	15V ₂						
Where V=Design Speed (mph)							
 When 30V cannot be attain used, but not less than 1 	ed, the greatest attainable length shall be 5V.						
 When 15V cannot be attained, the greatest attainable length shall be used, but not less than 400 ft. 							
Curve length shall provide full superelevation within the curve of not less than 200 ft. (Rural) or 100 ft. (Urban).							

Table 2.8.2a Length of Horizontal Curves

Table 2.8.2bArc Length (in feet) of Compound Curveswith One-Half/Double Radii - Turning Roadways

Radius (ft.)	100	150	200	250	300	400	≥ 500
Minimum Length	40	50	65	85	100	115	150
Desirable Length	65	65	100	115	150	180	200

		/ATURE (Degrees)			
Design Speed		URBAN ENVIRONMENT (e max=0.05)			
(mph)	ENVIRONMENT (e max=0.10)	Without Curb And Gutter	With Curb And Gutter		
30	24° 45'	20° 00'	20° 00'		
35	17° 45'	14° 15'	14° 15'		
40	13° 30'	10° 45'	10° 45'		
45	10° 15'	8° 15'	8° 15'		
50	8° 15'	6° 30'	6° 30'		
55	6° 30'	5° 00'			
60	5° 15'				
65	4° 15'				
70	3° 30'				

Table 2.8.3 Maximum Curvature of Horizontal Curve (Using Limiting Values of "e" and "f")

Table 2.8.4 Maximum Horizontal CurvatureUsing Normal Cross Slopes (-0.02)

M	MAXIMUM CURVATURE (Degrees)					
Design Speed (mph)	Curvature (e max = 0.10)	Curvature (e max = 0.05)				
30	1° 30'	7° 00'				
35	1° 30'	5° 00'				
40	1° 00'	3° 45'				
45	0° 30'	2° 45'				
50	0° 30'	2° 00'				
55	0° 30'					
60	0° 15'					
65	0° 15'					
70	0° 15'					

2.8.1.2 Supplemental Alignment Control (Intersections)

For redirection or offset deflection of through lanes through intersections, see the values given in *Table 2.8.1b*. Curves are not required for these angular breaks. However, short curves may be desirable at each end, especially if pavement markings are used through the intersection to provide positive guidance to the motorist.

2.8.1.3 Roadway Transitions

Transition details have been developed and included in the **Design Standards**. Transitions on curved alignment will require special design details in the contract plans.

2.8.2 Vertical Curves

Minimum lengths for crest and sag vertical curves are provided in **Tables 2.8.5 – 2.8.6**. K values for crest vertical curves are based on an eye height of 3.5' and an object height of 6".

	K VALUES FOR CREST CURVES						
Design Speed (mph)		Interstate			All Other Facilities		
15					5		
20					10		
25					19		
30					31		
35					47		
40					70		
45					98		
50					136		
55	245				185		
60	313				245		
65	401 313						
70		506			401		
		Where	Length, L = e: L = Minimu K = Consta A = Algebra	m Length (fe nt	eet) e In Grades (perc	ent)	
K valu	les for crest ver	tical curves ar	e based on an e	ye height of	3.5' and an objec	t height of 6".	
Interstates:		Lengths of crest vertical curves on Interstate mainlines are not to be less than 1000 ft. for open highways and 1800 ft. within interchanges.					
Service Inte	erchanges:	less than the	e Interstate K va	lues. K valu	t interstate termines for other ramples for All Other F		
System Inte	System Interchanges:		K values for all crest vertical curves on systems interchanges are not to be less than the K values of the higher system.				
Arterials an	Arterials and Collectors: The minimum lengths of crest vertical curves for highways with design speeds of 50 mph or greater are as follows:			s with design			
Design Spe Minimum L		50 300	55 350	60 400	65 450	70 500	
All Facilities	S:		of crest vertical ed (mph) express		not to be less that	n 3 times the	

Table 2.8.5 Minimum Lengths of Crest Vertical CurvesBased on Stopping Sight Distance

	K VALUES FOR SAG CURVES						
Design Speed (mph)		Interstate	All Other Facilities				
15					10		
20					17		
25					26		
30					37		
35					49		
40					64		
45					79		
50					96		
55		136			115		
60		157	136				
65		181	157				
70		206	181				
		Length, L = K Where: L = Minimum K = Constant A = Algebraic	Length (feet		es (perce	ent)	
Interstat	tes:	Lengths of sag vertical curves or	Interstate ma	inlines a	are not to	be less t	han 800 ft.
Service	Interchanges:	K values for ramp sag vertical curves at interstate terminals are not to be less than the interstate K values. K values for other ramp sag vertical curves are not to be less than the K values for All Other Facilities.					
System	Interchanges:	K values for all sag vertical curves on systems interchanges are not to be less than the K values of the higher system.					
Arterials	s and Collectors:	The minimum lengths of sag vertical curves for highways with design speeds on mph or greater are as follows:				eeds of 50	
		Design Speed (mph) Minimum Length (ft.)	50 200	55 250	60 300	65 350	70 400
All Facil	lities:	The lengths of sag vertical curve (mph) expressed in feet.	s are not to be	e less th	nan 3 time	es the de	sign speed

Table 2.8.6 Minimum Lengths of Sag Vertical CurvesBased on Stopping Sight Distance and Headlight Sight Distance

2.9 Superelevation

Superelevation rates of 0.10 maximum (rural) and 0.05 maximum (urban) are used by the Department on the State Highway System. Charts for these rates are in the criteria tables and figures. Additional data is contained in the **Design Standards, Indexes 510** and **511**.

The standard superelevation transition places 80% of the transition on the tangent and 20% on the curve. In special situations this treatment can be adjusted to allow up to 50% of the transition to be placed on the curve.

	Urban F	loonay	o ana n		TED VAL		majo			
Degree of	Radius			-		SN SPEED	(mph)			
Curve D	R (ft.)	30	35	40	45	50	55	60	65	70
0° 15'	22,918	NC	NC	NC	NC	NC	NC	NC	NC	NC
0° 30'	11,459	NC	NC	NC	NC	NC	NC	RC	RC	RC
0° 45'	7,639	NC	NC	NC	NC	RC	RC	0.023	0.025	0.028
1° 00'	5,730	NC	NC	NC	RC	0.021	0.025	0.030	0.033	0.037
1° 15'	4,584	NC	NC	RC	0.022	0.026	0.031	0.036	0.041	0.046
1° 30'	3,820	NC	RC	0.021	0.026	0.031	0.037	0.043	0.048	0.054
1 00	*R _{NC}			0.021	0.020	0.001	0.007	0.040	0.040	0.004
2° 00'	2,865	RC	0.022	0.028	0.034	0.040	0.048	0.055	0.062	0.070
	*R _{RC}	İ								
2° 30'	2,292	0.021	0.028	0.034	0.041	0.049	0.058	0.067	0.075	0.085
3° 00'	1,910	0.025	0.032	0.040	0.049	0.057	0.067	0.077	0.087	0.096
3° 30'	1,637	0.029	0.037	0.046	0.055	0.065	0.075	0.086	0.095	0.100
4° 00'	1,432	0.033	0.042	0.051	0.061	0.072	0.083	0.093	0.099	Dmax
5° 00'	1,146	0.040	0.050	0.061	0.072	0.083	0.094	0.098	Dmax =	3° 30
6° 00'	955	0.046	0.058	0.070	0.082	0.092	0.099	Dmax =	4° 15'	
7° 00'	819	0.053	0.065	0.078	0.089	0.098	Dmax =	5° 15'		-
8° 00'	716	0.058	0.071	0.084	0.095	0.100	6° 30'	l		
9° 00'	637	0.063	0.077	0.089	0.098	Dmax =				
10° 00'	573	0.068	0.082	0.094	0.100	8° 15'				
11° 00'	521	0.072	0.086	0.097	Dmax =					
12° 00'	477	0.076	0.090	0.099	10° 15'					
13° 00'	441	0.080	0.093	0.100						
14° 00'	409	0.083	0.096	Dmax = 13° 15'						
15° 00' 16° 00'	382 358	0.086	0.098	10 10]					
18° 00'	318	0.089	0.099 Dmax =							
20° 00'	286	0.095	17° 45'							
20° 00'	260	0.099								
24° 00'	239	0.100								
		Dmax = 24° 45'								
			NC/RC an	d RC/e Bi	reak Point	ts (Radius	in feet)			
Drook I	Jointo					SN SPEED				
Break F	omis	30	35	40	45	50	55	60	65	70
R _N	C	3349	4384	5560	6878	8337	9949	11709	13164	1471
R _R	C	2471	3238	4110	5087	6171	7372	8686	9783	1095
			e =	NC if R ≥ R	NC	e = I	RC if R < R	_{ic} and R ≥ F	RRC	
	Ν	IC = Norm	al Crown (-0.02)	RC	= Reverse	e Crown(+	+0.02)		
		luc = Minir		,		= Minimu				

Table 2.9.1 Superelevation Rates for Rural Highways, Urban Freeways and High Speed Urban Highways (e may =0.10)

 R_{NC} = Minimum Radius for NC

 R_{RC} = Minimum Radius for RC

Rates for intermediate D's and R's are to be interpolated





Figure 2.9.1 Superelevation Rate For Rural Highways, Urban Freeways and High Speed Urban Highways (e max =0.10)

	TABULATED VALUES					
Degree of	Radius			SIGN SPEED (n	nph)	
Curve D	<i>R</i> (ft.)	30	35	40	45	50
2° 00'	2,865	NC	NC	NC	NC	NC
2° 15'	2,546					RC
2° 45'	2,083				NC	
3° 00'	1,910				RC	
3° 45'	1,528			NC		
4° 00'	1,432			RC		
4° 45'	1,206					RC
5° 00'	1,146		NC			0.023
5° 15'	1,091		RC			0.027
5° 30'	1,042					0.030
5° 45'	996					0.035
6° 00'	955				RC	0.040
6° 15'	917				0.022	0.045
6° 30'	881				0.024	0.050
6° 45'	849				0.027	Dmax =
7° 00'	819	NC			0.030	6° 30'
7° 15'	790	RC			0.033	
7° 30'	764				0.037	1
7° 45'	739				0.041	
8° 00'	716			RC	0.045	
8° 15'	694			0.022	0.050	
8° 30'	674			0.025	Dmax =	
8° 45'	655			0.027	8° 15'	
9° 00'	637			0.030		_
9° 30'	603			0.034		
10° 00'	573			0.040		
10° 30'	546		RC	0.047		
11° 00'	521		0.023	Dmax =		
11° 30'	498		0.026	10° 45'		
12° 00'	477		0.030			
13° 00'	441		0.036			
14° 00'	409	RC	0.045			
15° 00'	382	0.023	Dmax =			
16° 00'	358	0.027	14° 15'	J		
17° 00'	337	0.032				
18° 00'	318	0.038]			
19° 00'	302	0.043				
20° 00'	286	0.050				
		Dmax = 20° 00'				

Table 2.9.2 Superelevation Rates for Urban Highways and High Speed Urban Streets (e_{max} = 0.05)

NC = Normal Crown (-0.02)

RC = Reverse Crown (+0.02)





- a. When the speed curves and the degree of curve lines intersect above this line, the pavement is to be superelevated (positive slope) at the rates indicated at the lines intersecting points.
- b. When the speed curves and the degree of curve lines intersect between these limits, the pavement is to be superelevated at the rate of 0.02 (positive slope).
- c. When the speed curves and the degree of curve lines intersect below this line, the pavement is to have normal crown (typically 0.02 and 0.03 downward slopes).

0 1 /			<u> </u>				
SLOPE RATES FOR STRAIGHT LINE SUPERELEVATION TRANSITIONS							
	De	Design Speed (mph)					
SECTION	45-50	55-60	65-70				
	SLOPE RATES						
2 Lane & 4 Lane	1:200	1:225	1:250				
6 Lane	1:160	1:180	1:200				
8 Lane	1:150	1:170	1:190				
		•					

Table 2.9.3 Superelevation Transition Slope Rates for Rural Highways, Urban Freeways and High Speed Urban Highways

The length of superelevation transition is to be determined by the relative slope rate between the travel way edge of pavement and the profile grade, except that the minimum length of transition shall be 100 feet.

For additional information on transitions, see the *Design Standards, Index 510*.

Table 2.9.4 Superelevation Transition Slope Ratesfor Urban Highways and High Speed Urban Streets

SLOPE RATES FOR STRAIGHT LINE SUPERELEVATION TRANSITIONS				
30 mph	1:100			
40 mph	1:125			
45-50 mph₁	1:150			


1. A slope rate of 1:125 may be used for 45 mph under restricted conditions.


The length of superelevation transition is to be determined by the relative slope rate between the travel way edge of pavement and the profile grade, except that the minimum length of transition shall be 50 ft. for design speeds under 40 mph and 75 ft. for design speeds of 40 mph or greater. For additional information on transitions, see the **Design Standards, Index 511**.


2.10 Vertical Clearance


Minimum vertical clearances, with the exception of structures over water (see **Section 2.10.1**), are contained in the criteria tables and figures.


Figure 2.10.1 Clearances – Rural and Urban Interstates (Freeways), Arterials and Collectors, with Projected 20-Year ADT of 1500 or Greater
















	FACILITY TYPE		CLEARANC	E _{1, 4, 6} (FEET)			
		Roadway or Railroad Over Roadway ₂	Roadway Over Railroad _{3, 4, 5}	Pedestrian Over Roadway ₂	Pedestrian Over Railroad ₃		
	Freeways, Arterials Collectors & Others	16'-6"	23'-6"	17'-6"	23'-6"		
1.	Clearance Measuren	nent:					
	The least vertical distance between the bridge structure and the surface of the roadway (traffic lanes and shoulders) or the top of the highest rail.						
2.		Includes Future Underpass Resurfacing: 6" over pavements.					
3	Includes Rail Resurfacing (Track Raised): 12" for conventional railroads. Others-see footnote No. 4 and Section 6.3.5 of this volume.						
4.	 Over High Speed Rail Systems: See Department guidelines and specifications for Intermediate Class Rail Operations entitled Standard Specifications for the Design and Construction of Railways. 						
5.	 Over Electrified Railroad: The minimum vertical clearance shall be 24 feet 3 inches. This provision is based on the FDOT's South Florida Rail Corridor Clearance Policy for 25 KV service (Topic No. 000- 725-003). 						
6.		Clearance Over Waterways: See Department <i>Drainage Manual, Topic No. 625-040-002, Chapter 4</i> and Section 2.10.1 of this volume.					

Table 2.10.1 Vertical Clearances for Bridges

	10.2 Willing Vertical Clearances for Signs
SIGNS	
Overhead Sign Structures	17'-6" over the entire width of the pavement and shoulder to the lowest sign component.

Table 2.10.2 Minimum Vertical Clearances for Signs

1. Includes 6" for future resurfacing on rural sections.

Table 2.10.3 Minimum Vertical Clearances for Signals					
SIGNALS					
Span Wire Mounted	17'-6" between the pavement and the bottom of any signal assembly.				
Mast Arm Mounted	17'-6" over the entire width of the pavement and shoulder to the lowest signal or low point of the arm.				
Truss Mounted	17'-6" over the entire width of the pavement and shoulders to the lowest signal or lowest member of the horizontal truss.				

Table 2.10.3 Minimum Vertical Clearances for Signals

1. Includes 6" for future resurfacing on rural sections.

Table 2.10.4 Minimum Vertical Clearances for Overhead Dynamic Message Signs (DMS)

SIGNS	
Overhead DMS Structures	19'-6" over the entire width of the pavement and shoulder to the lowest sign component.

1. Includes 6" for future resurfacing on rural sections.

2.10.1 Vertical Clearance Over Water

Unless otherwise specifically approved by the District Structures Design Engineer for Category 1 Structures or the State Structures Design Engineer for Category 2 Structures, the minimum vertical clearance over water shall conform to the following criteria:

1. Environment:

- a. For concrete superstructures classified as moderately aggressive or extremely aggressive due to chloride content, the minimum vertical clearance is 12 ft. above Mean High Water (MHW).
- b. For steel superstructures, the minimum vertical clearance shall be obtained from the District Maintenance Engineer, but shall not be less than those specified above for the concrete superstructures.

2. Drainage:

The minimum vertical clearance requirement shall also conform to the FDOT Drainage Manual, Chapter 4 (Topic No. 625-040-002).

3. Navigation:

The minimum vertical clearance for navigational purposes shall be determined in accordance with the *FDOT Drainage Manual, Chapter 4*, unless the agency having jurisdiction over the waterway has a more stringent requirement.

Information on the Normal High Water, control water elevation, or Mean High Water can be obtained from the appropriate Drainage Design Engineer.

Widening of existing structures which do not meet the minimum vertical clearance criteria stated above (either before or after the widening) may be justified hydraulically and/or economically. However, the encroachment of vertical clearance criteria may be limited and must be approved by the agency having jurisdiction over the navigable waterway.

2.10.2 Airspace Obstructions

Federal, state, and local regulations exist to protect the national airspace system that must be considered when planning and implementing construction that may adversely impact military or public-use aviation facilities (airport, seaport, or heliport), navigational aids, and instrument approach flight procedures in Florida.

FAA Notification:

Federal law, *Title 14 Code of Federal Regulations (CFR), Federal Aviation Regulations (FAR), Part 77, "Objects Affecting Navigable Airspace"*, requires that prior notification must be given to the Federal Aviation Administration (FAA) regarding any construction or alteration (permanent or temporary) of structures that meet the specific criteria given in *Table 2.10.5*.

For further guidance on airspace obstructions (notification and permitting) refer to **Section 13.5.1**, **FDOT Aviation Office Coordination**, this volume.

Table 2.10.5 FAA Notification Requirements		
F	FAA Notification Requirements for Construction or Alteration of Structures *	
1.	Any structure more than 200 feet above ground level (AGL) at its site.	
2.	 Any structure that is near an aviation facility and that penetrates an imaginary obstacle surface extending outward and upward at one of the following criteria: a. A slope of 100 to 1 (1 foot upward for each 100 feet outward) for a horizontal distance of 20,000 feet from the nearest point of the nearest military or public-use airport runway that is more than 3,200 feet in length (excludes heliports). b. A slope of 50 to 1 (1 foot upward for each 50 feet outward) for a horizontal distance of 10,000 feet from the nearest point of the nearest military or public-use airport runway no more than 3,200 feet in length (excludes heliports). c. A slope of 25 to 1 (1 foot upward for each 25 feet outward) for a horizontal distance of 10,000 feet from the nearest point of the nearest military or public-use airport runway no more than 3,200 feet in length (excludes heliports). c. A slope of 25 to 1 (1 foot upward for each 25 feet outward) for a horizontal distance of 10,000 feet from the nearest point of the nearest military or public-use airport runway no more than 3,200 feet in length (excludes heliports). 	
3.	 Any highway, railroad, or other traverse way for mobile objects, of a height which, if adjusted upward by the amount shown below, would exceed a standard of paragraph 1 or 2 above: a. An adjusted height of 17 feet for an Interstate Highway that is part of the National System of Military and Interstate Highways where over-crossings are designed for a minimum of 17 feet vertical distance. b. An adjusted height of 15 feet for any other public roadway. c. An adjusted height of 10 feet or the height of the highest mobile object that would normally traverse the road, whichever is greater, for a private road. d. An adjusted height of 23 feet for a railroad. e. An adjusted height equal to the height of the highest mobile object that would normally traverse it, for a waterway or traverse way not previously mentioned. 	
4.	Any structure located directly on a public-use aviation facility property, including any facility that is currently existing, planned, proposed, or under construction.	
5.	Any structure that is located in an instrument approach area and available information indicates it might exceed federal obstruction standards, if specifically requested by the FAA.	
* Note:	Structures may include: Highways, roads, railroads, waterways, traverseways (parking or rest areas), bridges, overpasses, high-mast light poles, utility poles, antenna towers, buildings, signs or billboards, fences, or gates, plus temporary-use construction materials or equipment, including dirt piles and cranes, as well as natural growth, vegetation, and landscaping, depending on location in proximity to an aviation facility, navigational aid, or instrument procedure ground track.	

Table 2 10 5 EAA Notification Poquiroments

THIS PAGE LEFT BLANK INTENTIONALLY

2.11 Horizontal Clearance

Horizontal clearance is the lateral distance from a specified point on the roadway such as the edge of travel lane or face of curb, to a roadside feature or object. Horizontal clearance applies to all highways. Horizontal clearance requirements vary depending on design speed, whether rural or urban with curb, traffic volumes, lane type, and the object or feature.

Rural highways with flush shoulders and highways with curb or curb and gutter where right of way is not restricted have roadsides of sufficient widths to provide clear zones; therefore, horizontal clearance requirements for certain features and objects are based on maintaining a clear zone wide enough to provide the recoverable terrain in **Table 2.11.10**. The procedure for determining required clear zone widths is described in **Chapter 4** of this volume.

In urban areas, horizontal clearance based on clear zone requirements for rural highways should be provided wherever practical. However, urban areas are typically characterized with lower speed, more dense abutting development, closer spaced intersections and accesses to property, higher traffic volumes, more bicyclists and pedestrians, and restricted right of way. In these areas, curb with closed drainage systems are often used to minimize the amount of right of way needed. Highways with curb or curb and gutter in urban areas where right of way is restricted do not have roadsides of sufficient widths to provide clear zones; therefore, while there are specific horizontal clearance requirements for these highways, they are based on clearances for normal operation and not based on maintaining a clear roadside for errant vehicles. It should be noted that curb has no redirectional capabilities except at speeds less than the lowest design speeds used on the State Highway System. Therefore curb should not be considered effective in shielding a hazard. Curb is not to be used to reduce horizontal clearance requirements.

Crashworthy objects shall meet or exceed the offset listed in *Tables 2.11.1* through *2.11.9* and objects that are not crashworthy are to be as close to the right of way as practical and no closer than the requirements listed in *Tables 2.11.1* through *2.11.9*.

For horizontal clearances where roadways overpass railroads refer to *Chapter 6* of this volume.

Table 2.11.1 Horizontal Clearance for Traffic Control Signs

PLACEMENT	Placement shall be in accordance with the Design Standards . Placement within sidewalks shall be such that an unobstructed sidewalk width of 4 ft. or more (not including the width of curb) is provided.
SUPPORTS	Supports, except overhead sign supports, shall be frangible or breakaway. When practicable, sign supports should be located behind barriers that are justified for other reasons. Overhead sign supports shall be located outside the clear zone unless shielded.

Table 2.11.2 Horizontal Clearance for Light Poles

	Not in the median except in conjunction with barriers that are justified for other reasons.
CONVENTIONAL LIGHTING	Rural and Urban Flush Shoulders: 20 ft. from the travel lane, 14 ft. from auxiliary lane (may be clear zone width when clear zone is less than 20 ft.).
	Urban Curb or Curb and Gutter: From right of way line to 4 ft. back of face of curb (may be 2.5 ft. back of face of curb when all other alternatives are deemed impractical). Placement within sidewalks shall be such that an unobstructed sidewalk width of 4 ft. or more (not including the width of curb) is provided.
HIGHMAST LIGHTING	Outside of the clear zone unless shielded.

	.3 Horizontal Clearance for Utility Installations
ABOVE GROUND FIXED OBJECTS (Such as Poles)	 Shall not be located within the limited access right of way, except as allowed by the <i>Policy No. 000-625-025, Telecommunications Facilities on Limited Access Rights of Way.</i> Shall not be located in the median. Rural and Urban Flush Shoulders: Not within the clear zone. Install as close as practical to the right of way without aerial encroachments onto private property. Urban Curb or Curb and Gutter: At the R/W line or as close to the R/W line as practical. Must maintain 4 ft. clear from face of curb. Placement within sidewalks shall be such that an unobstructed sidewalk width of 4 ft. or more (not including the width of the curb) is provided.
	See the <i>Utility Accommodation Manual, (Topic No. 710-020-001)</i> for additional information. Note: may be located behind barriers that are justified for other reasons.
FRANGIBLE AND BREAKAWAY	Rural and Urban Flush Shoulders:
OBJECTS	Locate as close to the right of way as practical.
(Such as Fire Hydrants)	Urban Curb or Curb and Gutter: Locate no less than 1.5 feet from face of curb.

Table 2.11.3 Horizontal Clearance for Utility Installations

Table 2.11.4Horizontal Clearance to Signal Polesand Controller Cabinets for Signals

Shall not be located in medians

Rural and Urban Flush Shoulders: Outside the clear zone.

Urban Curb or Curb and Gutter:

4 ft. from face of outside curbs and outside the sidewalk. However, when necessary, the Signal Poles may be located within sidewalks such that an unobstructed sidewalk width of 4 ft. or more (not including the width of curb) is provided.

Table 2.11.5 Horizontal Clearance to Trees

Minimum Horizontal Clearance to trees where the diameter is or is expected to be greater than 4 inches measured 6 inches above the ground shall be:

Rural and Urban Flush Shoulders: Outside the clear zone.

Urban Curb or Curb and Gutter: 4 ft. from face of outside curbs. 6 ft. from edge of inside traffic lane.

Table 2.11.6 Horizontal Clearance to Bridge Piers and Abutments

Minimum Horizontal Clearance to Bridge Piers and Abutments:

Rural and Urban Flush Shoulders: Outside the clear zone.

Urban Curb or Curb and Gutter: 16 ft. from the edge of the travel lane.

Table 2.11.7Horizontal Clearance to Railroad Grade Crossing
Traffic Control Devices

Placement shall be in accordance with the *Design Standards*.

Canals: (See also *Chapter 4* of this Volume.) Rural and Urban Flush Shoulders: Design Speeds ≥ 50 mph: 66

and Orban Flush Shoulders:Design Speeds \geq 50 mph:60 ft. from the travel lane.Design Speeds < 50 mph:</td>50 ft. from the travel lane.

Urban Curb or Curb and Gutter: 40 ft. from the edge of the travel lane.

Drop-offs: (See also *Chapter 4* of this Volume.) Rural and Urban Flush Shoulders: Treat as roadside slopes in accordance with *Design Standards, Index 700.*

Urban Curb or Curb and Gutter: 22 ft. from traveled way to the point that is 6 ft. below the hinge point.

Table 2.11.9 Horizontal Clearance to Other Roadside Obstacles

Minimum Horizontal Clearance to other roadside obstacles: Rural and Urban Flush Shoulders: Outside the clear zone. Urban Curb or Curb and Gutter:


4 ft. back of face of curb. May be 2.5 ft. back of face of curb when all other alternatives are deemed impractical.

Note: Horizontal Clearance to mailboxes is specified in the construction details contained in the **Design Standards, Index No. 532.**

	≥ 1500	AADT ⁽¹⁾	< 1500 AADT ⁽¹⁾	
DESIGN SPEED (mph)	TRAVEL LANES & MULTILANE RAMPS (feet)	AUXILIARY LANES & SINGLE LANE RAMPS (feet)	TRAVEL LANES & MULTILANE RAMPS (feet)	AUXILIARY LANES & SINGLE LANE RAMPS (feet)
< 45	18	10	16	10
45	24	14	20	14
50	24	14	20	14
55	30	18	24	14
> 55	36	24	30	18

Table 2.11.10 Recoverable Terrain

The above values are to be used in the process for determining the clear zone width as described in *Chapter 4* of this volume.






2.12 Bridge Railings and Separators


Bridge railings and separators on new and reconstruction projects shall be designed in accordance with the *Structures Design Guidelines*. On reconstruction projects, where an existing bridge is to remain, existing bridge railings must be replaced or upgraded unless the railing meets criteria for new traffic railings. All superseded FDOT Standard New Jersey Shape and F Shape Traffic Railings conforming to the designs shown in the *Structures Manual, Volume 3, "Existing FDOT Traffic Railing Details"*, are both structurally and functionally adequate.

All other former FDOT bridge traffic railings not listed above, and any other traffic railings that are not based on crash tested designs, are inadequate and shall be replaced, retrofitted or excepted, as appropriate, using the criteria included in the *Structures Design Guidelines*.

Details and typical applications of various bridge rails and separators are given in *Figures* **2.12.1 – 2.12.9**.












Figure 2.12.3 Bridge Traffic Railings – Other Shapes




Figure 2.12.4 Bridge Traffic Railings – Sound Barrier Combination




Figure 2.12.5 Bridge Railing and Separators – Median Traffic Railing and Separators




Figure 2.12.6 Bridge Fencing for Traffic Railings





Figure 2.12.7 Bridge Railing – Pedestrian / Bicycle Railing








Figure 2.12.9 Enclosed Bridge Fencing for Pedestrian Railing

2.13 Intersections

Design guides and criteria presented heretofore are also applicable to the proper design of intersections.

2.13.1 Circular Intersections (Roundabouts)

The circular intersection with all yield control is another design concept for the designer to consider. Two critical elements of the small circular traffic pattern with a central island are as follows:

- 1. Entry is by gap acceptance by having a yield condition at all entry legs.
- 2. Speeds through the intersection are 25 mph or less.

The use of this design is best for low speed facilities. Its use should be documented by a complete intersection analysis and study, including alternate types of design.

The *Florida Roundabout Guide* (available through FDOT Maps and Publications Sales) presents a methodology for identifying appropriate roundabout sites and estimating roundabout capacity and delay. It describes the design principles and standards to which roundabouts installed on state roadways must conform and offers guidelines for operational features such as signing, marking, lighting, landscaping, etc.

All roundabout designs must be approved by the State Roadway Design Engineer.

2.13.2 Queue Length for Unsignalized Intersections

Turn lanes should comply with the *Design Standards, Index 301* to the extent practical. The available queue length provided should be based on a traffic study.

For low volume intersections where a traffic study is not justified, a minimum queue length of 50 ft. (2 vehicles) should be provided for rural areas and small urban areas; for other urban areas, a minimum queue length of 100 ft. (4 vehicles) should be provided.


2.13.3 Offset Left Turn Lanes

The alignment of opposing left-turn lanes and the horizontal and vertical curvature on the approaches are the principal geometric design elements that determine how much sight distance is available to a left-turning driver. Operationally, vehicles in the opposing left-turn lane waiting to turn left can also restrict the left-turning driver's view of oncoming traffic in the through lanes. The level of blockage depends on how the opposing left-turn lanes are aligned with respect to each other, as well as the type/size of vehicles in the opposing queue and their position in the opposing lane.

The offset distance is defined as the distance between the left edge of the turn lane and the right edge of the opposing turn lane. If the offset distance is to the left of the turn lane it is considered a negative offset, and if it is to the right of turn lane it is considered a positive offset.


The conventional method of designing left turn lanes is to place the left turn lanes adjacent to the through lanes. This design creates a negative offset which severely restricts the sight distance of the left-turning driver's view of oncoming traffic when another vehicle is in the opposing turn lane. *Figure 2.13.1* indicates the negative offset when the conventional design is used.

Figure 2.13.1 Typical Opposing Left Turns (22' Median with Negative 10' Offset)




On all urban designs offset left-turn lanes should be used with median widths greater than 18 feet. A four foot traffic separator should be used when possible to channelize the left turn and provide separation from opposing traffic. On rural intersections where high turning movements are involved, offset left-turn lanes should also be considered. On median widths 30 feet or less, an offset turn lane parallel to the through lane should be used and the area between the left turn and traffic lane where vehicles are moving in the same direction should be striped out. On medians greater than 30 feet, a tapered offset should be considered. *AASHTO Exhibit 9-98* illustrates the design of parallel and tapered left turn lanes. *Figure 2.13.2* indicates an offset left turn.





As illustrated in *Figure 2.13.2*, the sight distance is improved significantly by utilizing the offset left turn design even when a positive offset is not achieved. The graph in *Figure 2.13.3* is taken from the *Older Driver Highway Design Handbook*, and gives the left turn offset guidelines that may be considered for various design speeds and vehicle types.



2.14 Interchanges

Design guides and criteria presented heretofore and in the **Design Standards** are also applicable to the proper design of interchanges with their inherent ramps, speed change, merging and weaving lanes. Where diamond ramps and partial cloverleaf arrangements intersect the crossroad at grade, an at-grade intersection is formed. In urbanized areas, high speed ramps, weaving areas and acceleration lanes are not appropriate. These ramp terminals should be designed as intersections consistent with the design speed and character of the roadway.

2.14.1 Limited Access Right of Way Limits at Interchanges

The following criteria will be used in establishing limited access limits along crossroads at interchanges:

- 1. For rural interchanges, limited access will extend along the crossroad to a point 300 ft. minimum beyond the end of the acceleration or deceleration taper. In the event these points are not opposite, the point most remote from the project will be the control and the limited access on both sides will end at that station along the crossroad. Where no taper is used, the limited access will be carried to a point 300 ft. minimum beyond the radius point of the return. In this case also, the radius point most remote from the project will control.
- 2. For interchanges in urban areas, the criteria given above will apply except that the limited access will end a minimum of 100 ft. beyond the end of taper or the radius point of the return.
- 3. For unsymmetrical interchanges such as half-diamonds and partial clover leafs, etc., the limited access right of way along the crossroad on that side having no ramp will extend to a point opposite that point controlled by the ramp.
- 4. Limited access along crossroads overpassing limited access facilities (with no interchange) shall be extended approximately 200 feet, measured from the mainline right of way line, along the crossroad. This distance may be reduced or omitted if the crossroad profile provides for adequate sight distance for existing or proposed driveways. The fence is generally tied into the crossroad structure end bent unless required along the crossroad.
- 5. Any reduction in the values shown above for limited access limits must be approved by FHWA for interstate projects and by the District Design Engineer for noninterstate limited access facilities.

Access Management Rule 14-97 standards (14-97.003(1)j) regulate the location of

driveway connections and median openings in interchange areas on arterial roads. This standard should be applied in accordance with the District procedures for implementing the Rule, and should not be confused with minimum requirements for limited access right of way.

2.14.2 Median Openings at Interchanges

Median opening locations at interchanges on arterial roads must consider **Access Management Rule 14-97 (14-97.003(1)(j)2)** which states "The minimum distance to the first median opening shall be at least 1320 feet as measured from the end of the taper of the egress ramp." This standard is to be applied in accordance with the FDOT median opening decision process. As a minimum, for all crossroad facilities at interchanges in both rural and urban areas, a median opening may be centered no less than 50 ft. beyond the end of limited access except that a minimum distance of 660 ft. to the ramp median opening will be required. In no case should access be permitted between the interchange proper and the median opening as established by these criteria.

2.14.3 Ramp Widths

Ramp widths for interchange ramp terminal design are given in *Table 2.14.1*.

RAMP WIDTHS			
DADUIO	1-LA	2-LANE	
RADIUS To Inside of Curve (FEET)	Traveled Way Width ₁ Case I-C ₂	Traveled Way Width 1 + Outside Paved Shoulder Width Case II-B 2	Traveled Way Width ₁ Case III-A ₂
	One–lane, one-way operation – no provision for passing a stalled vehicle	One-lane, one-way operation – with provision for passing a stalled vehicle	Two-lane operation – either one-way or two-way
	FEET		
50	23	26	29
75	20	23	27
100	18	22	26
150	17	21	24
200	16	20	24
300	15	20	24
400	15	19	24
≥ 500	15	19	24

Table 2.14.1 Ramp Widths - Turning Roadways

For widths on the ramp proper, see *Table 2.1.3*.

For case application, see AASHTO and the Design Standards, Index No. 525.

- 1. AASHTO adjustments do not apply.
- 2. Note: A = Predominantly P vehicles, but some consideration for SU trucks.
 - B = Sufficient SU vehicles to govern design, but some consideration for semitrailer combination trucks.
 - C = Sufficient bus and combination trucks to govern design.
- 3. Where accommodation of future resurfacing is a factor, consideration should be given to increasing the minimum width to 24 ft. where practical.

2.15 Lighting Criteria

Lighting Criteria is contained in *Tables 2.15.1 – 2.15.5* and in *Chapter 7* of this volume.

ROADWAY CLASSIFICATIONS	ILLUMINATION LEVEL AVERAGE INITIAL (H.F.C.)	UNIFORMITY RATIOS	
		AVG./MIN.	MAX./MIN.
INTERSTATE, EXPRESSWAY, FREEWAY & MAJOR ARTERIALS	1.5	4:1 or Less	10:1 or Less
ALL OTHER ROADWAYS	1.0	4:1 or Less	10:1 or Less
* PEDESTRIAN WAYS AND BICYCLE LANES	2.5	4:1 or Less	10:1 or Less

 Table 2.15.1
 Conventional Lighting - Roadways

^{*} This assumes a separate facility. Facilities adjacent to a vehicular roadway should use the levels for that roadway.

		louumuyo	
ROADWAY	ILLUMINATION LEVEL	UNIFORMITY RATIOS	
CLASSIFICATIONS	AVERAGE INITIAL (H.F.C.)	AVG./MIN.	MAX./MIN.
INTERSTATE, EXPRESSWAY, FREEWAY & MAJOR ARTERIALS	0.8 to 1.0	3:1 or Less	10:1 or Less
ALL OTHER ROADWAYS	0.8 to 1.0	3:1 or Less	10:1 or Less

Table 2.15.2 Highmast Lighting - Roadways

Note: These values should be considered standard, but should be increased if necessary to maintain an acceptable uniformity ratio. The maximum value should be one and one-half values.

Table 2.15.5 Underdeck Lighting - Roadways			
LUMINAIRE TYPE	LIGHT SOURCE	MOUNTING LOCATION	
PIER CAP	150 watt to 250 watt HPS	Pier or Pier Cap	
PENDANT HUNG	150 watt to 250 watt HPS	Bridge Deck	

Table 2.15.3 Underdeck Lighting - Roadways

Note:

- 1. The light levels for underdeck lighting shall be equal to the adjacent roadway lighting.
- 2. Underdeck lighting is accomplished by mounting either pier cap or pendant hung fixtures under the bridge structure.
- 3. Pier cap luminaires should be installed when bridge piers are located less than 15 ft. from edge of travel lane.
- 4. Pendant hung luminaires shall be mounted to the bottom of the bridge deck and should suspend where 50% of the lamp is below bridge beam.

Table 2.15.4Rest Area Lighting

	ILLUMINATION LEVEL AVERAGE INITIAL (H.F.C.)	UNIFORMITY RATIOS	
AREA ILLUMINATED		AVG./MIN	MAX./MIN.
ENTRANCE & EXIT	1.5	4:1 or Less	10:1 or Less
INTERIOR ROADWAYS	1.5	4:1 or Less	10:1 or Less
PARKING AREAS	1.5	4:1 or Less	10:1 or Less

Table 2.15.5Mounting Height Restrictions


LUMINAIRE WATTAGE	LIGHT SOURCE	MOUNTING HEIGHT (MIN) (FEET)
150	High Pressure Sodium (HPS)	25
200	High Pressure Sodium (HPS)	30
250	High Pressure Sodium (HPS)	30
400	High Pressure Sodium (HPS)	40
750	High Pressure Sodium (HPS)	50
1000	High Pressure Sodium (HPS)	80


2.16 Four-Lane High-Speed Suburban Arterial Highways

The two classifications of rural and urban are generally sufficient for the design of Florida's arterial highways; however, there are some areas that do not lend themselves to these classifications. These are transitional areas where conditions along the highway change from rural to urban or from urban to rural. Also, there are urban arterial highways where the anticipated operating speeds are higher than standard urban design speeds. Because of the undesirable effects of having curb and gutter on high speed highways, four-lane high speed suburban arterial highway typical sections have been developed to insure that these highways are designed consistently and to minimize the need to process design exceptions and variations. These typical sections are found in *Exhibit TYP-13* and *TYP-14* of *Chapter 6*, *Volume II*.

Special design criteria in this section have been developed for these four-lane high-speed suburban arterial highways. For criteria and other guidance not listed below, the designer is to use the values that are commensurate with a four-lane rural arterial highway having the same design speed and traffic volumes. Use of these special criteria is restricted to facilities in developing suburban areas which are initially constructed with 4 lanes and are included in the State Transportation Improvement Program (STIP) for 6 lanes in the future.


The design of the initial 4 lane facility should also take into consideration the ultimate 6 lane section that these roadways will have in the future. Special attention to the ultimate location of drainage structures, sidewalk offset and elevation, superelevation and curve radii can minimize the amount of reconstruction of these elements. To illustrate two possible scenarios, *Figure 2.16.1* and *Figure 2.16.2* show examples of four-lane high-speed suburban arterial sections with the future six-lane low-speed urban arterial typical section superimposed.





ULTIMATE 6-LANE LOW-SPEED URBAN SECTION





ULTIMATE 6-LANE LOW-SPEED URBAN SECTION

2.16.1 Design Speed

The maximum design speed of four-lane high-speed suburban arterial highways is 55 mph.

2.16.2 Pedestrian and Bicycle Facilities

Four-lane high-speed suburban arterial highways shall have bike lanes and sidewalks.

2.16.3 Medians

The minimum median width for four-lane high-speed suburban arterial highways may be reduced to 30 feet as opposed to 40 feet minimum required in *Table 2.2.1*. When this is done neither a design exception nor design variation is required.

2.16.4 Friction Course

Because of the higher speeds and the associated risk of hydroplaning, FC-5 friction course is to be provided to reduce surface water. The FC-5 friction course should be placed at the lip of the gutter in accordance with the **Design Standards, Index 300**.

2.16.5 Border Width

A minimum border width of 35 feet measured from the outside edge of the traveled way to the right of way is to be provided on all four-lane high-speed suburban arterial highways with or without curb and gutter.

2.16.6 Grades

The maximum grade for four-lane high-speed suburban arterial highways is 5%.


2.16.7 Horizontal Curves

The maximum deflection without horizontal curvature is commensurate with rural new construction and comparable design speeds.

2.16.8 Superelevation

When these suburban typical sections are superelevated, the superelevation rates are based on the $e_{max} = 0.10$ calculations, however the maximum superelevation rate that may be used is 0.05 (See *Figure 2.16.3*). Superelevation transition rates are to be commensurate with those for rural highways with 55 mph design speeds.

Figure 2.16.3 Superelevation Rates for High-Speed Urban or Suburban Sections



R = RADIUS OF CURVE - FEET

MAXIMUM DESIGN SUPERELEVATION RATE = 0.05(BASED ON $e_{max} = 0.00$)

2.16.9 Horizontal Clearance

Horizontal Clearance requirements are to be commensurate with new construction conditions for flush shoulder highways.

2.16.10 Monitoring

These high-speed suburban arterial highways will require that the county, section, begin milepost and end milepost for these sections be reported to the State Roadway Design Office during the Phase II Design. The District Design Engineer shall report to the State Roadway Design Engineer a speed study containing the speed histograms, the 85th percentile and the 10 mph pace speeds within one year after opening, then again between three to four years after opening. This data along with other data collected will be used to evaluate the overall effectiveness and safety of these high-speed suburban arterial highways.

2.17 High-Speed Urban Arterial Highways

There are urban arterial highways where the anticipated operating speeds are higher than standard urban design speeds. Because urban curbed roadway sections which typically provide roadside clearances that satisfy only operational needs are not suitable for high speed highways, and because of the right of way demands of rural highways, a high-speed urban arterial highway typical section has been developed. This typical section provides for reduced right of way requirements, yet still provides for horizontal clearances/clear zones commensurate with rural highway design. A six-lane high-speed urban typical section is found in *Exhibit TYP-16* of *Chapter 6, Volume II*. A four-lane high-speed urban typical section *2.17.5*.

Special design criteria in this section have been developed for these high-speed urban arterial highways. For criteria and other guidance not listed in this section, the designer is to use the values that are commensurate with a rural arterial highway having the same design speed and traffic volumes. Use of these special criteria is restricted to facilities within FHWA Urban or Urbanized boundaries where right of way is constrained.

2.17.1 Design Speed

The design speed for the high-speed urban arterial highway shall be 50 mph. The special criteria listed in this section do not apply to facilities with higher design speeds.

2.17.2 Curbs

To minimize right of way requirements, the high-speed urban arterial highway typical section incorporates the use of curbs and a closed drainage system. The type of curb used within the clear zone on this section is restricted to the FDOT Type E shape (sloping curb not greater than 5" in height above adjacent pavement). This applies to both median and outside shoulder locations.

2.17.3 Pedestrian and Bicycle Facilities

High-speed urban arterial highways shall have shoulders and sidewalks.

2.17.4 Medians

The minimum median width for high-speed urban arterial highways may be reduced to 30 feet (inclusive of median shoulders) as opposed to 40 feet minimum required in **Table 2.2.1**. A 30 foot median provides sufficient width for a 24 foot clear zone. This median width also allows space at intersections for dual left turn lanes (11' lanes with 4' traffic separator), and directional median openings using 4' traffic separators.

2.17.5 Shoulders

The minimum shoulder width (median and outside) for six-lane high-speed urban arterial highways is 6.5 feet measured to the lip of the gutter. This provides for 8 feet of usable shoulder to the curb face. Under special circumstances (i.e., dual left turn lanes, directional median openings, etc.) it may be necessary to encroach into the median shoulder. In these locations only, the minimum median shoulder width may be reduced to 4 feet (measured to face of curb or separator) while maintaining the same median width. For a four-lane design, the median shoulder may be reduced to 4 feet (measured to the curb face) while maintaining the 30 foot median.

2.17.6 Friction Course

Because of the higher speeds and the associated risk of hydroplaning, FC-5 friction course is to be provided to reduce surface water. The FC-5 friction course should be placed at the lip of the gutter in accordance with the **Design Standards, Index 300**.

2.17.7 Border Width

A minimum border width of 29 feet measured from the outside edge of the traveled way to the right of way is to be provided on all high-speed urban arterial highways with or without curb and gutter.

2.17.8 Grades

The maximum grade for high-speed urban arterial highways is 6%.

2.17.9 Horizontal Curves

The maximum deflection without horizontal curvature is commensurate with rural new construction and comparable design speeds.

2.17.10 Superelevation

When these high-speed urban typical sections are superelevated, the superelevation rates are based on the $e_{max} = 0.10$ calculations, however the maximum superelevation rate that may be used is 0.05 (See *Figure 2.16.3*). Superelevation transition rates are to be commensurate with those for rural highways with 50 mph design speeds.

2.17.11 Horizontal Clearance

Horizontal Clearance requirements are to be commensurate with new construction conditions for flush shoulder highways.

Standards for Low and High Volume Highways in Annual Average Daily Volumes

HIGHWAY TYPE	LOW VOLUME AADT	HIGH VOLUME AADT
FREEWAY - URBAN 4-LANE FACILITY 6-LANE FACILITY 8-LANE FACILITY	57,000 86,000 114,000	69,000 103,000 138,000
FREEWAY - RURAL 4-LANE FACILITY 6-LANE FACILITY 8-LANE FACILITY	46,000 69,000 92,000	56,000 83,000 111,000
ARTERIALS - URBAN 2-LANE FACILITY 4-LANE FACILITY 6-LANE FACILITY 8-LANE FACILITY	16,000 37,000 55,000 69,000	20,000 43,000 64,000 80,000
ARTERIALS - RURAL 2-LANE FACILITY 4-LANE FACILITY 6-LANE FACILITY	9,000 38,000 58,000	14,000 47,000 71,000
COLLECTOR - URBAN 2-LANE FACILITY 4-LANE FACILITY	11,000 37,000	16,000 45,000
COLLECTOR - RURAL 2-LANE FACILITY 4-LANE FACILITY	8,000 30,000	13,000 38,000

LOW VOLUME FACILITIES ARE HIGHWAY TYPES WITH PROJECTED DESIGN YEARS AADT VOLUME EQUAL TO OR LESS THAN THE LOW VOLUME VALUES SHOWN.

HIGH VOLUME FACILITIES ARE HIGHWAY TYPES WITH PROJECTED DESIGN YEAR AADT VOLUME EQUAL TO OR GREATER THAN THE HIGH VOLUME VALUES SHOWN.