

102-8.6 Temporary Guardrail.

(REV 2-15-99) (FA 3-16-99) (7-00)

The quantity to be paid for will be the length, in feet [meters], of temporary guardrail actually constructed. The length of a run of guardrail will be determined as a multiple of the nominal panel lengths.

Price and payment will be full compensation for furnishing all materials required for a complete installation, including end anchorage assemblies and any end connections to other structures and for installing, maintaining and removing guardrail.

Payment will be made under:

Item No. 102- 73- Guardrail (Temporary) - per foot.

Item No. 2102- 73- Guardrail (Temporary) - per meter.