

**102-8.6 Work Zone Signs.**

**(REV 3-13-98) (FA 4-2-98) (7-02)**

The number of signs (Warning or Temporary Regulatory) properly placed and maintained on the project, as authorized by the Engineer on any calendar day or portion thereof, within the allowable Contract Time, including time extensions which may be granted, will be paid for at the Contract unit price for Work Zone Signs. When multiple signs are located on single or multiple post(s), each sign panel will be paid individually. Signs  $>20 \text{ ft}^2$  [ $>1.9 \text{ m}^2$ ] will be paid for under Pay Item No. 102-1 [Pay Item No. 2102-1], Lump Sum MOT.

Portable signs (excluding Mesh signs and signs mounted with  $<1$  foot [ $<0.3$  m] ground clearance) and Vehicular Mounted Signs will be included for payment under work zone signs, only if used in accordance with the Design Standards.

Price and payment will constitute full payment for furnishing signs, supports and necessary hardware, installation, relocating, maintaining and removing signs.

Payment will be made under:

Item No. 102- 60- Work Zone Signs - per each per day.

Item No. 2102- 60- Work Zone Signs- per each per day.