

102-8.6 Concrete Barrier Wall (Temporary) (With or Without Glare Screen).
(REV 5-31-95) (7-00)

Furnish a temporary concrete barrier wall as detailed on Design Standards, Index No. 415, except space the Type C Steady-Burn lights on 50 foot [15 m] centers for transitions, 100 foot [30 m] centers for curves and 200 foot [60 m] centers for tangents. When called for, temporary glare screens shall be in accordance with 102-3.4.

Furnish the barrier wall and glare screen and take ownership upon completion of the project. When the plans indicate the availability of a Department owned barrier, the Contractor may use it in lieu of furnishing Contractor owned barrier wall. Furnish the necessary bolts and plate assemblies. Upon completion of the project, return the Department owned wall to the original stockpile unless otherwise specified in the plans.

The Contract unit price for Concrete Barrier Wall (Temporary) will be full compensation for furnishing, installing, maintaining, and removing the concrete barrier. When called for, the Contract unit price for Concrete Barrier Wall (Temporary) (Relocate) will be full compensation for relocating the concrete barrier. The quantity to be paid for will be determined by the number of precast sections times the nominal length of each section.

The Contract unit price for Type C Steady Burn Lights will be full compensation for furnishing, installing and maintaining the warning lights. Payment will not be made for lights that are improperly placed or are not working.

Payment will be made under:

- Item No. 102- 70- Concrete Barrier Wall (Temporary) - per foot.
- Item No. 2102- 70- Concrete Barrier Wall (Temporary) - per meter.
- Item No. 102- 79- Lights, Temporary, Barrier Wall Mount - per each per day.
- Item No. 2102- 79- Lights, Temporary, Barrier Wall Mount - per each per day.