

**102-8.6 Temporary Vehicular Impact Attenuator (Inertia).**

**(REV 3-28-96) (FA 4-16-96) (7-02)**

Temporary vehicular impact attenuator modules necessary to form the attenuator in accordance with the details and notes shown in the plans will be paid for at the Contract unit price each for the number of modules furnished and installed in accordance with the details and notes shown in the plans, and the Design Standards, Index No. 415. Temporary foundation pallets will be allowed. The pallets shall be 42 by 42 inches [1.0 by 1.0 m], 4 inches [100 mm] or less in height, constructed of wood or other frangible or resilient materials other than metals; and be sufficiently durable to support the modules for their expected period of use.

Maintain the attenuators until their authorized removal. Replace damaged modules within 24 hours.

Price and payment for the number of modules necessary for the completed attenuator will be full compensation for furnishing, installing, maintenance and removal at each specified location. In addition, payment will be made for new modules replaced due to damages, excluding damage caused by the Contractor's operations.

Payment will be made under:

Item No. 102- 81- 1- Vehicular Impact Attenuator Modules  
(Inertia) Temporary) - each

Item No. 2102- 81- 1- Vehicular Impact Attenuator Modules  
(Inertia) (Temporary) - each.