

102-8.6 Temporary Traffic Control Signals.

(REV 3-17-94) (7-02)

Install and operate temporary Traffic Control Signals as indicated in the plans. Temporary Traffic Control Signals will consist of either portable or fixed traffic signals.

Certify that the portable traffic signals meet the requirements of the Design Standards as set out in 102-3.1, and have been properly maintained. Ensure that fixed traffic signals to the Department's general requirements for equipment and material as set out in Section 603. Used signal equipment may be approved by the Engineer if it is in acceptable condition.

The quantity of Temporary Traffic Control Signals to be paid for will be the number of completed installations (each signalized location) of portable traffic signals, or the number of fixed traffic signals actually in place and operating on the project, as authorized by the Engineer on any calendar day or portion thereof within the original Contract Time including any extensions which may be granted.

Price and payment will constitute full compensation for furnishing, installing, operating, maintaining and removing Temporary Traffic Control Signals including all equipment and components necessary to provide an operable traffic signal. Take ownership of all equipment and components.

Payment will be made under:

- Item No. 102-104- 1- Temporary Traffic Control Signals (Portable) - per each per day.
- Item No. 2102-104- 1- Temporary Traffic Control Signals (Portable) - per each per day.
- Item No. 102-104- 2- Temporary Traffic Control Signals (Fixed) - per each per day.
- Item No. 2102-104- 2- Temporary Traffic Control Signals (Fixed) - per each per day.