

210 REWORKING LIMEROCK BASE.

(REV 10-31-01) (FA 1-3-02) (7-02)

ARTICLE 210-3 (Page 187) is deleted and the following substituted:

210-3 Equipment.

Provide equipment meeting the requirements of 200-3.

SUBARTICLE 210-6.1 (Page 188) is deleted and the following substituted:

210-6.1 General: Scarify and disk, or otherwise loosen the existing base to such extent that no pieces larger than 3 1/2 inches [90 mm] in greatest dimension remain bonded together. Then, spread the material to the full width of the proposed new base course and to a grade and cross-section roughly parallel to the finished grade. Meet the requirements of 200-7.1.