

REMOVAL AND DISPOSAL OF FENDER SYSTEM.

(REV 3-18-94) (FA 6-21-99) (7-00)

SUBARTICLE 110-6.1 (of the Supplemental Specifications) is expanded by the following:

The specific work to be done under this Subarticle includes the removal and disposal of the existing fender system.

SUBARTICLE 110-6.2 (of the Supplemental Specifications) is expanded by the following:

Pull the existing piles to be removed.

Maintain temporary navigation lights and clearance gauges satisfactory to the Department while existing clearance gauges and navigation lights are removed.

ARTICLE 110-12 (of the Supplemental Specifications) is expanded by the following:

Price and payment will be full compensation for the removal and disposal of the existing fender system, furnishing and maintaining temporary clearance gauges, navigation and warning lights and installing signs, clearance gauges and incidental items. Measurement for the removal will be made along the top of the fender before removal.

The following new pay items are added:

Item No. 110- 71- 1- Removal and Disposal of Fender System - per foot.

Item No. 2110- 71- 1- Removal and Disposal of Fender System - per meter.