

# EXPECTED IMPLEMENTATION JULY 2003

## 230 LIMEROCK STABILIZED BASE. (REV ~~11-4-02~~12-6-02) (FA 12-13-02) (7-03)

ARTICLE 230-10 (Page 192) is deleted and the following substituted:

### 230-10 Basis of Payment.

Prices and payments will be full compensation for all work specified in this Section, including furnishing, hauling, placing, spreading, mixing, compacting, *prime coat application as specified in 300-87* and finishing all limerock stabilizing material; any necessary excavating below the finished grade of the base to provide for placing the stabilizing material; and disposing of all surplus excavation resulting from this work.

Where extra limerock material is placed at locations of culverts, etc., as detailed in the plans, the volume of such material, determined as provided above, will be included in the quantity of Limerock Material to be paid for, but no adjustment will be made in the area of base to be paid for.

~~Prime coat will be paid for under Section 300.~~

Payment will be made under:

Item No. 230- 1-	Limerock Stabilized Base - per square yard.
Item No. 2230- 1-	Limerock Stabilized Base - per square meter.
Item No. 230- 2-	Limerock Material - per cubic yard.
Item No. 2230- 2-	Limerock Material - per cubic meter.