



Florida Department of Transportation

JEB BUSH
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

THOMAS F. BARRY,
JR.
SECRETARY

MEMORANDUM

DATE: January 14, 2003

TO: Specification Review Distribution List

FROM: Duane F. Brautigam, P.E., State Specifications Engineer

SUBJECT: Proposed Specifications Change – D4500022 – Precast Prestressed Concrete Construction.

In accordance with Specification Development Procedures, we are sending you a copy of a proposed specification change to Precast Prestressed Concrete Construction.

This change was proposed by Susan Blazo, State Materials Office as a result of moving personnel requirements to Section 105.

Please share this proposal with others within your responsibility. Review comments are due within four weeks and should be sent to Mail Station 75 or to my attention via e-mail at SP965DB or duane.brautigam@dot.state.fl.us. Comments received after February 11, 2003 may not be considered. Your input is encouraged.

DFB/jho

Attachment

COMMENTS:

Submitted by:

Phone #:

PRECAST PRESTRESSED CONCRETE CONSTRUCTION.
(REV 7-8-021-13-03)(FA 7-22-02)(1-037-03)

SUBARTICLE 450-2.2 (of the Supplemental Specifications) is deleted and the following substituted:

~~**450-2.2 Plant:** Ensure each plant has an on-site production manager, an on-site Quality Control Manager (QCM), a plant engineer, and adequate on-site QC inspectors/technicians to provide complete QC inspections and testing.~~

~~_____ Include with the QCP the work experience and qualifications of key plant production personnel and QC personnel such as the production manager, qualified tensioning machine operator, yard supervisor, and QCM.~~

~~_____ Ensure the QCM has at least five years of related experience and a current PCI Quality Control personnel Level III certification and a certificate of completion of 450 Specification examination. Ensure that the QC inspector/technician has current PCI QC Technician/Inspector Level II certification and a certificate of completion of 450 Specification examination. Department certified prestressed concrete inspectors are exempt from PCI Level II certification and from completion of 450 Specification examination, until the time of expiration of their certificates. QC managers certified by the Department as prestressed concrete inspectors are exempt from PCI Level III certification and from completion of 450 Specification examination, until the time of expiration of their certificates~~ *Ensure each plant has an on site Quality Control Manager meeting the requirements of Section 105.*