

210 REWORKING LIMEROCK BASE.
(REV 12-6-02) (FA 12-13-02) (7-03)

ARTICLE 210-3 (Page 187) is deleted and the following substituted:

210-3 Equipment.

Provide equipment meeting the requirements of 200-3.

SUBARTICLE 210-6.1 (Page 188) is deleted and the following substituted:

210-6.1 General: Scarify and disk, or otherwise loosen the existing base to such extent that no pieces larger than 3 1/2 inches [90 mm] in greatest dimension remain bonded together. Then, spread the material to the full width of the proposed new base course and to a grade and cross-section roughly parallel to the finished grade. Meet the requirements of 200-7.1.

ARTICLE 210-9 (Pages 188 and 189) is deleted and the following substituted:

210-9 Basis of Payment.

Prices and payments will be full compensation for performing all work specified in this Section including prime coat application as specified in 300-7, except all earthwork required for this work, and the work of removal and disposal of the existing bituminous surfaces, if required, as indicated in the plans.

When the plans do not provide for direct payment for such work, the cost will be included in the Contract unit price for Reworking Limerock Base.

Payment will be made under:

Item No. 210- 1-	Reworking Limerock Base - per square yard.
Item No. 2210- 1-	Reworking Limerock Base - per square meter.
Item No. 210- 2-	Limerock, New Material - per cubic yard.
Item No. 2210- 2-	Limerock, New Material - per cubic meter.