

PILE INSTALLATION.

(REV 1-21-05) (7-05)

ARTICLE 455-44 (Pages 530-531). The last paragraph is deleted and the following substituted:

15. Leave any temporary supports of/for items placed into a grouted pile (reinforcement template, anchor bolt template, precast column supports, etc.) in place for a minimum of 12 hours after the completion of the pile. Do not place wall panels or other significant loads, before the grout has set a minimum of seven days or reached the 28 day strength.