

EXPECTED IMPLEMENTATION JANUARY 2006

105 CONCRETE PRODUCTION FACILITY MANAGER OF QUALITY CONTROL. (REV 6-8-05) (FA 6-21-05) (1-06)

SUBARTICLE 105-5.7.4 (of the Supplemental Specifications) is deleted and the following substituted:

105-5.7.4 Concrete Production Facility Manager of Quality Control: Ensure each concrete production facility has a Facility Manager for QC with the following qualifications:

1. CTQP Concrete Laboratory Technician Level I, Concrete Field Technician-Level I, and Batch Plant Operator. As alternatives to these qualifications, the Department will accept:
 - Prestressed Concrete Institute (PCI) Level III or
 - National Ready Mixed Concrete Association (NRMCA) Concrete Technologist Level II, as equivalent qualifications.
2. Three years of QC experience directly related to cement concrete production.
3. Demonstrated proficiency in implementing, supervising, and maintaining surveillance over a QC Program.
4. Experience and certification in performance of required QC tests and statistical evaluation of quality control test results.