

ORIGINATION FORM

THE INFORMATION BELOW IS TO BE PROVIDED BY THE ORIGINATOR

(The person who receives or originates the issue and needs to forward the issue for action.)

Modify Specification _____1050050SS_____.
Section/File number

New Section _____.
Section number

Subject: Contractor Quality Control General Requirements – Concrete
Production Facility Manager of Quality Control

Origination date: March 11, 2005

Originator: Michael Bergin
Office/Phone: State Material Office/352-955-6666
Email address/ michael.bergin@dot.state.fl.us
Userid:

Problem statement: Requirement No 1 needs to be expanded to allow alternative requirements for the position of Concrete Production Facility Manager of Concrete Control.

Information source: State Materials Office

Background data: Changes are made for clarification and to allow other alternatives to meet the qualification. Added a, b and c to the requirements for the Concrete Production Facility Manager of Quality Control.

Recommended Usage Note: All Jobs

Desired implementation date: Beginning with the January 2006 letting.



Florida Department of Transportation

JEB BUSH
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

JOSÉ ABREU
SECRETARY

MEMORANDUM

DATE: May 9, 2005

TO: Specification Review Distribution List

FROM: Duane F. Brautigam, P.E., State Specifications Engineer

SUBJECT: Proposed Specifications Change: 1050574-Concrete Production Facility Manager of Quality Control

In accordance with Specification Development Procedures, we are sending you a copy of a proposed specification change to Concrete Production Facility Manager of Quality Control.

This change was proposed by Michael Bergin of the State Materials Office to expand qualification requirement No. 1 to include alternative for the position of Concrete Production Facility Manager of Quality Control.

Please share this proposal with others within your responsibility. Review comments are due within four weeks and should be sent to Mail Station 75 or to my attention via e-mail at SP965DB or duane.brautigam@dot.state.fl.us. Comments received after June 6, 2005 may not be considered. Your input is encouraged.

DFB/sh

Attachment

COMMENTS:

Submitted by:

Phone #:

CONCRETE PRODUCTION FACILITY MANAGER OF QUALITY CONTROL.
(REV 4-22-05)

SUBARTICLE 105-5.7.4 (of the Supplemental Specifications) is deleted and the following substituted:

105-5.7.4 Concrete Production Facility Manager of Quality Control: Ensure each concrete production facility has a Facility Manager for QC with the following qualifications:

~~1. The Concrete Production Facility Manager of Quality Control will maintain one of the following:~~

~~a. Qualified as a CTQP Concrete Laboratory Technician Level II or, qualified as a1. -CTQP Concrete Laboratory Technician Level I, Concrete Field Technician-Level I, and Batch Plant Operator. As alternatives to CTQP qualification, the Department will accept:~~

~~b. Prestressed Concrete Institute (PCI) Level III or~~

~~e. National Ready Mixed Concrete Association (NRMCA) Concrete Technologist Level II, as equivalent qualifications.~~

2. Three years of QC experience directly related to cement concrete production.
3. Demonstrated proficiency in implementing, supervising, and maintaining surveillance over a QC Program.
4. Experience or certification in performance of required QC tests and statistical evaluation of quality control test results.