

# EXPECTED IMPLEMENTATION JULY 2006

## 102 MAINTENANCE OF TRAFFIC. (REV 12-6-05) (FA 12-20-05) (7-06)

SUBARTICLE 102-5.8 (of the Supplemental Specifications) is deleted and the following substituted:

**102-5.8 Conflicting Pavement Markings:** Where the lane use or where normal vehicle paths are altered during construction, remove all pavement markings (paint, tape, thermoplastic, raised pavement markers, etc.) that will conflict with the adjusted vehicle paths. Use of paint to cover conflicting pavement markings is prohibited. Remove conflicting pavement markings using a method that will not damage the surface texture of the pavement and which will eliminate the previous marking pattern regardless of weather and light conditions.

Remove all pavement markings that will be in conflict with “next phase of operation” vehicle paths as described above, before opening to traffic.

Cost for removing conflicting pavement markings (paint, tape, thermoplastic, raised pavement markers, etc.) to be included in Maintenance of Traffic, Lump Sum.

**102-5.9 No Waiver of Liability:** Conduct operations in such a manner that no undue hazard results due to the requirements of this Article. The procedures and policies described herein in no way acts as a waiver of any terms of the liability of the Contractor or his surety.

ARTICLE 102-7 (of the Supplemental Specifications) is deleted and the following substituted:

### 102-7 Traffic Control Officer.

Provide uniformed law enforcement officers, including marked law enforcement vehicles, to assist in controlling and directing traffic in the work zone when the following types of work is necessary on projects:

1. Traffic control in a signalized intersection when signals are not in use.
2. When Standard Index No. 619 is used on Interstate at nighttime and required by the plans.
3. When pacing/rolling blockade specification is used.

SUBARTICLE 102-9.5.2 (of the Supplemental Specifications) is deleted and the following substituted:

**102-9.5.2 Barrier Wall (Temporary):** Furnish, install, maintain, remove and relocate a temporary barrier wall in accordance with the plans. Temporary concrete barrier wall, for use on roadway sections, will be in accordance with Index No. 415 or 414 as specified in the plans. Temporary water filled barrier wall used on roadway sections shall conform to the requirements of the pre-approved alternatives listed on the Department’s Qualified Products List (QPL), unless otherwise called for in the plans. Proprietary barrier walls for use on roadway sections must meet NCHRP Report 350 criteria and be identified on the QPL. Temporary concrete barrier wall for use on bridge and wall sections, will be in accordance with Index No.414. Barriers meeting the requirements of Index Nos. 415 or temporary water filled barriers on the QPL will not be accepted as an alternate to barriers meeting the requirements of Index No. 414.

# EXPECTED IMPLEMENTATION JULY 2006