

# EXPECTED IMPLEMENTATION JULY 2006

5570201

557-1; 2557-1

## 557 VIBRATORY PLOWING-CONSTRUCTION SITE REQUIREMENTS. (REV 1-5-06) (FA 1-31-06) (7-06)

ARTICLE 557-2 (Pages 646 and 647) is deleted and the following substituted:

### 557-2 Construction Site Requirements.

**557-2.1 Site Conditions:** Consider vibratory plowing an excavation method and comply with all applicable provisions required of excavation methods.

(a) Ensure that subsequent excavation for manholes, hand pulls, or other service vaults, recovery pits or any other excavation is carried out as specified in Section 120.

(b) After completing installation of the product, restore the work site. Restore excavated or plowed areas in accordance with the Specifications and Design Standards.

(c) It is the plowing Contractor's responsibility for removal of excess material or debris created during the construction process as well as restoring the site to the condition which existed before construction.

(d) Exposure may be allowed for periods exceeding 14 consecutive days if the exposure is limited to 3 feet [1 m] or less. Periods longer than described above may be approved by the Engineer if it will not affect maintenance or construction activities.

(e) Ensure that equipment does not impede visibility of the roadway user without taking the necessary precautions of proper signing and Maintenance of Traffic Operations.

**557-2.2 Damage Restoration:** Take responsibility for restoring any damage caused by cutting, heaving, settlement or separation of pavement at no cost to the Department.

**557-2.2.1 Remediation Plans:** When required by the Engineer, provide detailed plans which show how damage to any roadway facility will be remedied and include this as part of the As-Built Plans Package. Remediation Plans must follow the same guidelines for development and presentation of the As-Built Plans.