



Florida Department of Transportation

JEB BUSH
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

DENVER J. STUTLER, JR.
SECRETARY

MEMORANDUM

DATE: September 12, 2005
TO: Specification Review Distribution List
FROM: Duane F. Brautigam, P.E., State Specifications Engineer
SUBJECT: Proposed Specifications Change: 162A000 - Organic Soil Layer

In accordance with Specification Development Procedures, we are sending you a copy of a proposed specification change to Organic Soil Layer.

This change was proposed by David Sadler of the State Construction Office to delete this Section since it has been incorporated into the new Section 162 rewrite.

Please share this proposal with others within your responsibility. Review comments are due within four weeks and should be sent to Mail Station 75 or to my attention via e-mail at SP965DB or duane.brautigam@dot.state.fl.us. Comments received after October 10, 2005 may not be considered. Your input is encouraged.

DFB/jf

Attachment

COMMENTS:

Submitted by:

Phone #:

ORGANIC SOIL LAYER.

(REV ~~1-19-009-7-05~~) (~~FA 1-25-00~~) (~~7-00~~)

SECTION 162A (of the Special Provisions) is deleted.

~~SECTION 162A~~
~~ORGANIC SOIL LAYER~~

~~162A-1 Description.~~

~~Prepare a 6 inch [150 mm] thick layer organic soil, at locations shown in the plans.~~

~~162A-2 Materials.~~

~~Meet the requirements of Section 987-2.1.~~

~~162A-3 Construction Methods.~~

~~**162A-3.1 Preparation of Areas:** Prior to the beginning of the work, construct the surface of the earthwork to such lines and elevations that will provide a surface conforming to the plan lines and elevations upon completion of the organic soil operations. Leave the surface of the earthwork in a roughened and loose condition.~~

~~Prevent contamination of the organic soil layer material by other construction operations. Remove any contaminated material and replace at no cost to the Department.~~

~~**162A-3.2 Spreading:** Uniformly spread the necessary material over areas to receive treatment.~~

~~Correct any slippage of this material at no cost to the Department.~~

~~Immediately after spreading, the top 6 inches [150 mm] of the material will be sampled and tested for organic matter content in accordance with AASHTO T 267 by the Engineer. When the source of added material changes, an additional sample will be required. Test results will be averaged for each increment thereof to determine specification compliance. Out of tolerance individual tests to a minimum of 1% organic content will be allowed.~~

~~162A-4 Method of Measurement.~~

~~The quantity to be paid for will be the area, in square yards [square meters], for the organic soil layer meeting the requirements of 162A-2, completed and accepted.~~

~~162A-5 Basis of Payment.~~

~~Prices and payments will be full compensation for completing all work specified in this Section, including hauling any material from the project right-of-way, designated borrow areas, other sources as may be provided by the Contractor, or any combination of the above; leveling as required to provide a relatively uniform layer throughout the 6 inches [150 mm] within the prescribed lines and grades.~~

~~Payment will be made under:~~

~~Item No. 162-4 Organic Soil Layer per square yard.~~

~~Item No. 2162-4 Organic Soil Layer per square meter.~~