

EXPECTED IMPLEMENTATION JANUARY 2007

110 ASBESTOS LANGUAGE FOR FDOT SPECIFICATIONS-REMOVAL OF EXISTING STRUCTURES.

(REV 4-10-06) (FA 8-11-06) (1-07)

SUBARTICLE 110-6.1 (Page 141) is deleted and the following substituted:

110-6.1 Structures to be Removed: Remove and dispose of the materials from existing structures. Remove the following: (1) those structures, or portions of structures, shown in the plans to be removed; (2) those structures, or portions of structures, found within the limits of the area to be cleared and grubbed, and directed by the Engineer to be removed; (3) those structures, or portion of structures, which are necessary to remove in order to construct new structures; and (4) other appurtenances or obstructions which may be designated in the Contract Documents as to be included in an item of payment for the work under this Article.

Provide detailed schedule information to the Engineer 15 working days prior to the commencement of any demolition or renovation of any structures, even if asbestos is not found on the project, for the Engineer's use in notifying the Department of Environmental Protection (DEP) on DEP Form 62-257.900(1) "Notice of Asbestos Renovation or Demolition".

D

R

A

F

T