



Florida Department of Transportation

CHARLIE CRIST
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

STEPHANIE KOPELOUSOS
SECRETARY

June 4, 2007

Dr. Leslie McCarthy, PhD, P.E.
Program Operations Engineer
Federal Highway Administration
545 John Knox Road, Suite 200
Tallahassee, Florida 32303

Re: Office of Design, Specifications
Section 600
Proposed Specification: 0060600 Control of Materials – Additional Requirements for
Lump Sum Projects

Dear Dr. McCarthy:

We are submitting, for your approval, two copies of a proposed Supplemental Specification for Control of Materials – Lump Sum Projects.

This change was proposed by David Sadler of the State Office of Construction to clarify that FDOT only needs or expects monthly updates on quantities on Lump Sum jobs with regard to the Job Guide Schedule.

Please review and transmit your comments, if any, within two weeks. Comments should be sent via Email to SP965DB or duane.brautigam@dot.state.fl.us.

If you have any questions relating to this specification change, please call Duane F. Brautigam, State Specifications Engineer at 414-4110.

Sincerely,

Signature on File

Duane F. Brautigam, P.E.
State Specifications Engineer

DFB/ft

Attachment

cc: General Counsel
Florida Transportation Builders' Assoc.
State Construction Engineer

CONTROL OF MATERIALS.

(REV ~~2-19-07~~~~2-5-07~~)-(FA ~~3-7-07~~)-(7-07)

ARTICLE 6-6 (of the Supplemental Specifications) is deleted and the following substituted:

6-6 Additional Requirements for Lump Sum Projects.

Prepare and submit to the Engineer a project-specific list of material items and quantities to be used on the project as a Job Guide Schedule in the same format as the current Sampling, Testing, and Reporting Guide 21 calendar days prior to commencement of construction. Provide ~~an~~-up-to-date *quantities for the items on the* Job Guide Schedule to the Engineer with each monthly progress estimate. The Department may not authorize payment of any progress estimate not accompanied by ~~an~~-up-to-dated Job Guide Schedule *quantities*. Maintain the Job Guide Schedule throughout the project including the quantity placed since the previous submittal, and total to date quantity and any additional materials placed. Do not commence work activities that require testing until the Job Guide Schedule has been reviewed and accepted by the Engineer. At final acceptance, submit a final Job Guide Schedule that includes all materials used on the project in the same format as the monthly reports.

CONTROL OF MATERIALS.
(REV 2-5-07)

ARTICLE 6-6 (of the Supplemental Specifications) is deleted and the following substituted:

6-6 Additional Requirements for Lump Sum Projects.

Prepare and submit to the Engineer a project-specific list of material items and quantities to be used on the project as a Job Guide Schedule in the same format as the current Sampling, Testing, and Reporting Guide 21 calendar days prior to commencement of construction. Provide up-to-date quantities for the items on the Job Guide Schedule to the Engineer with each monthly progress estimate. The Department may not authorize payment of any progress estimate not accompanied by updated Job Guide Schedule quantities. Maintain the Job Guide Schedule throughout the project including the quantity placed since the previous submittal, and total to date quantity and any additional materials placed. Do not commence work activities that require testing until the Job Guide Schedule has been reviewed and accepted by the Engineer. At final acceptance, submit a final Job Guide Schedule that includes all materials used on the project in the same format as the monthly reports.