

EXPECTED IMPLEMENTATION JANUARY 2008

D

**450 PRECAST PRESTRESSED CONCRETE CONSTRUCTION – MATERIALS
ACCEPTANCE AND TESTING – CONCRETE.**

(REV 4-24-07) (FA 6-28-07) (1-08)

SUBARTICLE 450-4.1 (Pages 448 and 449) is deleted and the following substituted:

450-4.1 Concrete: Perform the QC sampling and testing of concrete in accordance with the requirements of Section 346.

R

A

F

T