



Florida Department of Transportation

CHARLIE CRIST
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

STEPHANIE KOPELOUSOS
SECRETARY

December 18, 2007

Dr. Leslie McCarthy, PhD, P.E.
Program Operations Engineer
Federal Highway Administration
545 John Knox Road, Suite 200
Tallahassee, Florida 32303

Re: Office of Design, Specifications
Section 700
Proposed Specification: 7000702 – Highway Signage

Dear Dr. McCarthy:

We are submitting, for your approval, two copies of a proposed Supplemental Specification for Highway Signage.

This change was proposed by Tom Malerk of the State Materials Office to specify that precast concrete footings be obtained from a plant that is listed on Producers with Accepted Quality Control Program.

Please review and transmit your comments, if any, within two weeks. Comments should be sent via Email to SP965DB or duane.brautigam@dot.state.fl.us.

If you have any questions relating to this specification change, please call Duane F. Brautigam, State Specifications Engineer at 414-4110.

Sincerely,

Signature on file

Duane F. Brautigam, P.E.
State Specifications Engineer

DFB/sh
Attachment

cc: Gregory Jones, General Counsel
Florida Transportation Builders' Assoc.
State Construction Engineer

700—HIGHWAY SIGNAGE.

———(~~REV 2-13-07~~~~10-15-07~~~~11-9-07~~)(~~FA 2-28-07~~)(~~7-07~~)

SUBARTICLE 700-7.2 (of the Supplemental Specifications) is deleted and the following substituted:

700-7.2 Mixing and Placing Concrete: For batching and mixing of concrete for footings, meet the requirements of Section 346, except that the Engineer will allow hand mixing by approved methods where the quantity to be mixed does not exceed 1/2 yd³. Use cast-in-place or precast concrete for the footings. *Obtain precast concrete footings from a plant that is currently on the list of Producers with Accepted Quality Control Programs for Incidental Precast products. Producers seeking inclusion on the list shall meet the requirements of 105-3.*

HIGHWAY SIGNAGE.**(REV 11-9-07)**

SUBARTICLE 700-7.2 (of the Supplemental Specifications) is deleted and the following substituted:

700-7.2 Mixing and Placing Concrete: For batching and mixing of concrete for footings, meet the requirements of Section 346, except that the Engineer will allow hand mixing by approved methods where the quantity to be mixed does not exceed $1/2$ yd³. Use cast-in-place or precast concrete for the footings. Obtain precast concrete footings from a plant that is currently on the list of Producers with Accepted Quality Control Programs. Producers seeking inclusion on the list shall meet the requirements of 105-3.